Tune up procedure

The test frequency of this project covers 450MHz~512MHz.

1. It must provide an operational voltage (3.7~4.2V DC) to turn on the device and on one certain channel in service mode by means of company proprietary software.

2. The maximum gain of each individual device are adjusted until the target value met.

Output power of range：36.5 ± 1.0 dBm