

1. Effective (Isotropic) Radiated Power Output Data

1.1 Test Result

1.1.1 Band II_EIRP

Band: II								
ENV	Mode		Frequency (MHz)	Conducted Power (dBm)	Gain (dBi)	EIRP (dBm)		Verdict
	Network	Subset				Result	Limit	
NTNV	RMC	12.2kbps RMC	1852.4	22.00	-0.91	21.09	<=33.01	Pass
			1880	22.23	-0.91	21.32	<=33.01	Pass
			1907.6	22.59	-0.91	21.68	<=33.01	Pass
	HSDPA	Subtest 1	1852.4	21.51	-0.91	20.60	<=33.01	Pass
		Subtest 2	1852.4	21.54	-0.91	20.63	<=33.01	Pass
		Subtest 3	1852.4	21.55	-0.91	20.64	<=33.01	Pass
		Subtest 4	1852.4	21.54	-0.91	20.63	<=33.01	Pass
		Subtest 1	1880	21.93	-0.91	21.02	<=33.01	Pass
		Subtest 2	1880	21.87	-0.91	20.96	<=33.01	Pass
		Subtest 3	1880	21.88	-0.91	20.97	<=33.01	Pass
		Subtest 4	1880	21.87	-0.91	20.96	<=33.01	Pass
		Subtest 1	1907.6	22.15	-0.91	21.24	<=33.01	Pass
		Subtest 2	1907.6	22.16	-0.91	21.25	<=33.01	Pass
		Subtest 3	1907.6	22.17	-0.91	21.26	<=33.01	Pass
		Subtest 4	1907.6	22.21	-0.91	21.30	<=33.01	Pass
	HSUPA	Subtest 1	1852.4	20.55	-0.91	19.64	<=33.01	Pass
		Subtest 2	1852.4	20.60	-0.91	19.69	<=33.01	Pass
		Subtest 3	1852.4	20.53	-0.91	19.62	<=33.01	Pass
		Subtest 4	1852.4	20.86	-0.91	19.95	<=33.01	Pass
		Subtest 5	1852.4	20.56	-0.91	19.65	<=33.01	Pass
		Subtest 1	1880	20.72	-0.91	19.81	<=33.01	Pass
		Subtest 2	1880	20.69	-0.91	19.78	<=33.01	Pass
		Subtest 3	1880	19.87	-0.91	18.96	<=33.01	Pass
		Subtest 4	1880	19.47	-0.91	18.56	<=33.01	Pass
		Subtest 5	1880	19.78	-0.91	18.87	<=33.01	Pass
		Subtest 1	1907.6	19.91	-0.91	19.00	<=33.01	Pass
		Subtest 2	1907.6	19.97	-0.91	19.06	<=33.01	Pass
		Subtest 3	1907.6	19.88	-0.91	18.97	<=33.01	Pass
		Subtest 4	1907.6	20.05	-0.91	19.14	<=33.01	Pass
		Subtest 5	1907.6	19.70	-0.91	18.79	<=33.01	Pass

Note1: EIRP=Conducted Power+Antenna Gain

---End---