

1. Effective (Isotropic) Radiated Power Output Data

1.1 Test Result

1.1.1 Band IV_EIRP

Band: IV								
ENV	Mode		Frequency (MHz)	Conducted Power (dBm)	Gain (dBi)	EIRP (dBm)		Verdict
	Network	Subset				Result	Limit	
NTNV	RMC	12.2kbps RMC	1712.4	21.49	-1.52	19.97	<=30	Pass
			1732.6	21.82	-1.52	20.30	<=30	Pass
			1752.6	21.79	-1.52	20.27	<=30	Pass
	HSDPA	Subtest 1	1712.4	21.89	-1.52	20.37	<=30	Pass
		Subtest 2	1712.4	21.94	-1.52	20.42	<=30	Pass
		Subtest 3	1712.4	21.96	-1.52	20.44	<=30	Pass
		Subtest 4	1712.4	21.91	-1.52	20.39	<=30	Pass
		Subtest 1	1732.6	21.56	-1.52	20.04	<=30	Pass
		Subtest 2	1732.6	21.58	-1.52	20.06	<=30	Pass
		Subtest 3	1732.6	21.59	-1.52	20.07	<=30	Pass
		Subtest 4	1732.6	21.57	-1.52	20.05	<=30	Pass
		Subtest 1	1752.6	21.66	-1.52	20.14	<=30	Pass
		Subtest 2	1752.6	21.66	-1.52	20.14	<=30	Pass
		Subtest 3	1752.6	21.69	-1.52	20.17	<=30	Pass
		Subtest 4	1752.6	21.65	-1.52	20.13	<=30	Pass
	HSUPA	Subtest 1	1712.4	20.91	-1.52	19.39	<=30	Pass
		Subtest 2	1712.4	18.84	-1.52	17.32	<=30	Pass
		Subtest 3	1712.4	20.91	-1.52	19.39	<=30	Pass
		Subtest 4	1712.4	21.19	-1.52	19.67	<=30	Pass
		Subtest 5	1712.4	18.98	-1.52	17.46	<=30	Pass
		Subtest 1	1732.6	20.57	-1.52	19.05	<=30	Pass
		Subtest 2	1732.6	18.78	-1.52	17.26	<=30	Pass
		Subtest 3	1732.6	20.79	-1.52	19.27	<=30	Pass
		Subtest 4	1732.6	18.46	-1.52	16.94	<=30	Pass
		Subtest 5	1732.6	18.82	-1.52	17.30	<=30	Pass
		Subtest 1	1752.6	20.64	-1.52	19.12	<=30	Pass
		Subtest 2	1752.6	19.00	-1.52	17.48	<=30	Pass
		Subtest 3	1752.6	20.65	-1.52	19.13	<=30	Pass
		Subtest 4	1752.6	21.00	-1.52	19.48	<=30	Pass
		Subtest 5	1752.6	20.70	-1.52	19.18	<=30	Pass

Note1: EIRP=Conducted Power+Antenna Gain

---End---