

1. Effective (Isotropic) Radiated Power Output Data

1.1 Test Result

1.1.1 Band2_EIRP

Band: 2								
ENV	Mode		Frequency (MHz)	Conducted Power (dBm)	Gain (dBi)	EIRP (dBm)		Verdict
	Network	Subset				Result	Limit	
NTNV	RMC	12.2kbps RMC	1852.4	23.96	1.31	25.27	<=33.01	Pass
			1880	24.08	1.31	25.39	<=33.01	Pass
			1907.6	24.01	1.31	25.32	<=33.01	Pass
	HSDPA	Subtest 1	1852.4	22.21	1.31	23.52	<=33.01	Pass
		Subtest 2	1852.4	22.27	1.31	23.58	<=33.01	Pass
		Subtest 3	1852.4	22.40	1.31	23.71	<=33.01	Pass
		Subtest 4	1852.4	22.39	1.31	23.70	<=33.01	Pass
		Subtest 1	1880	22.44	1.31	23.75	<=33.01	Pass
		Subtest 2	1880	22.44	1.31	23.75	<=33.01	Pass
		Subtest 3	1880	22.32	1.31	23.63	<=33.01	Pass
		Subtest 4	1880	22.41	1.31	23.72	<=33.01	Pass
		Subtest 1	1907.6	22.28	1.31	23.59	<=33.01	Pass
		Subtest 2	1907.6	22.27	1.31	23.58	<=33.01	Pass
		Subtest 3	1907.6	22.27	1.31	23.58	<=33.01	Pass
		Subtest 4	1907.6	22.44	1.31	23.75	<=33.01	Pass
	HSUPA	Subtest 1	1852.4	20.13	1.31	21.44	<=33.01	Pass
		Subtest 2	1852.4	20.39	1.31	21.70	<=33.01	Pass
		Subtest 3	1852.4	20.20	1.31	21.51	<=33.01	Pass
		Subtest 4	1852.4	19.67	1.31	20.98	<=33.01	Pass
		Subtest 5	1852.4	19.17	1.31	20.48	<=33.01	Pass
		Subtest 1	1880	19.70	1.31	21.01	<=33.01	Pass
		Subtest 2	1880	20.47	1.31	21.78	<=33.01	Pass
		Subtest 3	1880	20.48	1.31	21.79	<=33.01	Pass
		Subtest 4	1880	19.09	1.31	20.40	<=33.01	Pass
		Subtest 5	1880	19.35	1.31	20.66	<=33.01	Pass
		Subtest 1	1907.6	19.90	1.31	21.21	<=33.01	Pass
		Subtest 2	1907.6	20.22	1.31	21.53	<=33.01	Pass
		Subtest 3	1907.6	20.49	1.31	21.80	<=33.01	Pass
		Subtest 4	1907.6	19.70	1.31	21.01	<=33.01	Pass
		Subtest 5	1907.6	19.23	1.31	20.54	<=33.01	Pass

Note1: EIRP=Conducted Power+Antenna Gain