FCC TEST REPORT
FCC ID: 2BNXJ-CWTB1G077

Product	:	keyless transmitter
Model Name	:	RHK-SUB-008, RHK-SUB-006
Brand	:	GTL
Report No.	:	SZNTT26036053E1-1

Prepared for

Genesis Tecspro Ltd

Building 15, 16, Zhongnan High-tech Electronic Information Industrial Park, Chenjiang Street, Huicheng District, Huizhou City, Guangdong Province

Prepared by

Shenzhen NTT Testing Technology Co.,Ltd.

1B, Building 2, Factory Building & 103, Building 3, Factory Building, Dayang Industrial Park No.4, Industrial Avenue, Tangwei Community, Fuhai Sub-district, Bao 'an District, Shenzhen City, China

TEL: 0755-27889935

FAX: /

1 TEST RESULT CERTIFICATION

Applicant's name	:	Genesis Tecspro Ltd
Address	:	Building 15, 16, Zhongnan High-tech Electronic Information Industrial Park, Chenjiang Street, Huicheng District, Huizhou City, Guangdong Province
Manufacture's name	:	Genesis Tecspro Ltd
Address	:	Building 15, 16, Zhongnan High-tech Electronic Information Industrial Park, Chenjiang Street, Huicheng District, Huizhou City, Guangdong Province
Product name	:	keyless transmitter
Model name	:	RHK-SUB-008, RHK-SUB-006
Standards	:	FCC PART 15C 15.231
Test procedure	:	ANSI C63.10-2020 + Cor. 1-2023+C63.10a-2024 + Errata to C63.10a-2024
Date of test	:	Jul. 30, 2026 to Sep. 08, 2026
Date of Issue	:	Sep. 08, 2026

This device described above has been tested by NTT, and the test results show that the equipment under test (EUT) is in compliance with the FCC requirements. And it is applicable only to the tested sample identified in the report.

This report shall not be reproduced except in full, without the written approval of NTT, this document may be altered or revised by NTT, personal only, and shall be noted in the revision of the document.

Prepared by(Test Engineer):
Cindy Qin

Reviewer(Supervisor):
Ken Wu

Approved(Manager):
Abel Yu

Shenzhen NTT Testing Technology Co., Ltd.Special Seal for Inspection and Testing

Table of Contents Page

1 TEST RESULT CERTIFICATION 2
2. SUMMARY OF TEST RESULTS 5
2.1 TEST FACILITY 6
2.2 MEASUREMENT UNCERTAINTY 6
3.GENERAL INFORMATION 7
3.1 GENERAL DESCRIPTION OF EUT 7
3.2 DESCRIPTION OF TEST MODES 8
3.3 BLOCK DIGRAM SHOWING THE CONFIGURATION OF SYSTEM TESTED 8
3.4 DESCRIPTION OF SUPPORT UNITS(CONDUCTED MODE) 8
3.5 EQUIPMENTS LIST FOR ALL TEST ITEMS 9
4. EMC EMISSION TEST 11
4.1 CONDUCTED EMISSION MEASUREMENT 11
4.1.1 POWER LINE CONDUCTED EMISSION LIMITS 11
4.1.2 TEST PROCEDURE 12
4.1.3 DEVIATION FROM TEST STANDARD 12
4.1.4 TEST SETUP 12
4.1.5 EUT OPERATING CONDITIONS 12
4.1.6 TEST RESULTS 12
4.2 RADIATED EMISSION MEASUREMENT 13
4.2.1 RADIATED EMISSION LIMITS 13
4.2.2 TEST PROCEDURE 14
4.2.3 TEST SETUP 15
4.2.4 EUT OPERATING CONDITIONS 16
4.2.5 TEST RESULTS 16
5.1 APPLIED PROCEDURES / LIMIT 20
5.2 TEST PROCEDURE 20
5.3 DEVIATION FROM STANDARD 20
5.4 TEST SETUP 20
5.5 EUT OPERATION CONDITIONS 20
5.6 TEST RESULTS 21
6. CALCULATION OF AVERAGE FACTOR 22
7. DWELL TIME 24
7.1 APPLICABLE STANDARD 24
7.2 TEST PROCEDURE 24
7.5 EUT OPERATION CONDITIONS 24
7.6 TEST RESULTS 25

Table of Contents Page

8. ANTENNA REQUIREMENT.....26
9. TEST SETUP PHOTO.....27
10. EUT CONSTRUCTIONAL DETAILS.....27

2. 1SUMMARY OF TEST RESULTS

Test procedures according to the technical standards:

FCC Part15 (15.231) , Subpart C			
Standard Section	Test Item	Judgment	Remark
15.207	Conducted Emission	N/A	
15.209,15.231b	Fundamental &Radiated Spurious Emission Measurement	PASS	
15.231c	Occupy Bandwidth	PASS	
15.231a	Dwell time	PASS	
15.203	Antenna Requirement	PASS	

NOTE:

(1)" N/A" denotes test is not applicable in this Test Report

2.11.1 TEST FACILITY

Site Description

EMC Lab. :

Designation Number: CN3446

Test Firm Registration Number: 129414

Accredited by ANAB, Dec. 19, 2025

The Certificate Registration Number is AT-3446

Name of Firm : Shenzhen NTT Testing Technology Co.,Ltd.

Site Location : 1B, Building 2, Factory Building & 103, Building 3, Factory Building, Dayang Industrial Park No.4, Industrial Avenue, Tangwei Community, Fuhai Sub-district, Bao 'an District, Shenzhen City, China

2.21.2 MEASUREMENT UNCERTAINTY

The reported uncertainty of measurement y ± U，where expended uncertainty U is based on a standard uncertainty multiplied by a coverage factor of k=2，providing a level of confidence of approximately 95 %。

Parameter	**Uncertainty**
RF output power, conducted	±1.0dB
Power Spectral Density, conducted	±2.2dB
Radio Frequency	± 1 x 10^{-6}
Bandwidth	± 1.5 x 10^{-6}
Time	±2%
Duty Cycle	±2%
Temperature	±1°C
Humidity	±5%
DC and low frequency voltages	±3%
Conducted Emissions (150kHz~30MHz)	±3.64dB
Radiated Emission(9KHz~30MHz)	±4.51dB
Radiated Emission(30MHz~1GHz)	±5.03dB
Radiated Emission(1GHz~25GHz)	±4.74dB
Radiated Emission(25GHz~40GHz)	±3.38dB
Remark: The coverage Factor (k=2), and measurement Uncertainty for a level of Confidence of 95%	

3.2GENERAL INFORMATION

3.12.1 GENERAL DESCRIPTION OF EUT

Product Name	:	keyless transmitter
Model Name	:	RHK-SUB-008
Sample ID	:	N/A
Sample(s) Status:	:	N/A
Series Model	:	RHK-SUB-006
Model Different.:	:	All the model are the same circuit and RF module, only the names are different. Test sample model: RHK-SUB-008
Operating frequency	:	433.928MHz
Number of Channels	:	1 channels
Type of Modulation	:	FSK
Antenna installation	:	PCB Antenna
Antenna Gain	:	1.0dBi
Power supply	:	DC 3V
Hardware Version	:	N/A
Software Version	:	N/A
Note:433MHz Remote Control for Pool Light Model DS306.		
Remark：the Antenna gain is provided by customer from Antenna spec. and the laboratory will not be responsible for the accumulated calculation results which covers the information provided by the applicant.		

3.22.2 DESCRIPTION OF TEST MODES

For All Emission	
Final Test Mode	Description
Transmitting mode	Keep the EUT in continuously transmitting mode

Note:

(1) Fully-charged battery is used during the test

3.32.3 BLOCK DIGRAM SHOWING THE CONFIGURATION OF SYSTEM TESTED

Conducted Emission Test



Spurious emissions



3.42.4 DESCRIPTION OF SUPPORT UNITS(CONDUCTED MODE)

The EUT has been tested as an independent unit together with other necessary accessories or support units. The following support units or accessories were used to form a representative test configuration during the tests.

Item	Equipment	Mfr/Brand	Model/Type No.	Series No.	Note

Item	Shielded Type	Ferrite Core	Length	Note

Note:

(1) The support equipment was authorized by Declaration of Confirmation.

(2) For detachable type I/O cable should be specified the length in cm in『Length』column.

(3) “YES” is means “shielded” “with core”; “NO” is means “unshielded” “without core”.

3.52.5 EQUIPMENTS LIST FOR ALL TEST ITEMS

Radiated emission & Radio Frequency Test Equipment

Name	Model No.	Serial No.	Manufacturer	Date of Cal.	Due Date
966 Shielded Room	966 Room	/	EMToni	2025/7/24	2028/7/23
EMI Test Receiver	ESCI	101018	RS	2025/9/8	2026/9/7
Amplifi（30MHz-1GHz）	BBV 9718D	00042	SCHWARZBECK	2025/9/8	2026/9/7
Bilog Antenna（30MHz-1GHz）	VULB9168	1858	SCHWARZBECK	2025/9/9	2026/9/8
Horn antenna（1GHz-18GHz）	BBHA 9120 D	02622	SCHWARZBECK	2025/9/9	2026/9/8
Pream plifier（1GHz-18GHz）	BBV 9718D	0024	SCHWARZBECK	2025/9/8	2026/9/7
Spectrum Analyze（10Hz-40GHz）	FSV 40	100952	Rohde & Schwarz	2025/9/8	2026/9/7
Pream plifier（18GHz-40GHz）	BBV 9721	0056	SCHWARZBECK	2025/9/8	2026/9/7
Double Ridge Guide Horn Antenna（18GHz-40GHz）	SAS-574	588	A.H.System	2025/9/8	2026/9/7
Loop Antenna (9KHz-30MHz)	FMZB1519B	014	SCHWARZBECK	2025/9/8	2026/9/7
Amplifier (9KHz-30MHz)	CVP 9222 C	00109	SCHWARZBECK	2025/9/8	2026/9/7
MXG Signal Analyzer	N9020A	MY50510202	Agilent	2025/9/8	2026/9/7
MXG Vector Signal Generator	N5182A	MY50140020	Agilent	2025/9/8	2026/9/7
MXG Analog Signal Generator	N5181A	MY47420919	Agilent	2025/9/8	2026/9/7
Power Sensor	TR1029-2	512364	Techoy	2025/9/8	2026/9/7
RF Swith	TR1029-1	512364	Techoy	2025/9/8	2026/9/7
Cable	DA800-4000MM	NA	DA	2025/9/8	2026/9/7
Cable	DA800-11000MM	NA	DA	2025/9/8	2026/9/7

Conducted emission Test Equipment

Name	Model No.	Serial No.	Manufacturer	Date of Cal.	Due Date
944 Shielded Room	HSRCE944	/	HTEC	2025/4/30	2028/4/29
EMI Test Receiver	ESPI	/	RS	2025/9/8	2026/9/7
LISN	NNLK 8129	00603	Schwarzbeck	2025/9/8	2026/9/7
LISN	NNHV 8123-400	00694	Schwarzbeck	2025/9/8	2026/9/7
LISN	NNHV 8123-400	00680	Schwarzbeck	2025/9/8	2026/9/7
Cable	RG223-1500MM	NA	RG	2025/9/8	2026/9/7

Other

Item	Name	Manufacturer	Model	Software version
1	EMC Conduction Test System	FALA	EZ-EMC	Ver.EMC-CON 3A1.1+
2	EMC radiation test system	FALA	EZ-EMC	Ver.FA-03A2 RE+
3	RF test system	TACHOY	RFTest	V1.0.0
4	RF communication test system	TACHOY	RFTest	V1.0.0

4. 3EMC EMISSION TEST

4.13.1 CONDUCTED EMISSION MEASUREMENT

Test Requirement:	FCC Part15 C Section 15.207
Test Method:	ANSI C63.10-2020 + Cor. 1-2023+C63.10a-2024 + Errata to C63.10a-2024
Test Frequency Range:	150KHz to 30MHz
Receiver setup:	RBW=9KHz, VBW=30KHz, Sweep time=auto

4.1.1 POWER LINE CONDUCTED EMISSION LIMITS

(Frequency Range 150KHz-30MHz)

FREQUNCY (MHz)	Limit (dBuV)		Standard
	Quasi-peak	Average	
0.15 -0.5	66 - 56 *	56 - 46 *	FCC
0.50 -5.0	56.00	46.00	FCC
5.0 -30.0	60.00	50.00	FCC

Note:

(1) The tighter limit applies at the band edges.

(2) The limit of " * " marked band means the limitation decreases linearly with the logarithm of the frequency in the range.

The following table is the setting of the receiver

Receiver Parameters	Setting
Attenuation	10 dB
Start Frequency	0.15 MHz
Stop Frequency	30 MHz
IF Bandwidth	9 kHz

4.1.23.1.1 TEST PROCEDURE

a. The EUT was placed 0.8 meters from the horizontal ground plane with EUT being connected to the power mains through a line impedance stabilization network (LISN). All other support equipments powered from additional LISN(s). The LISN provide 50 Ohm/ 50uH of coupling impedance for the measuring instrument.
b. Interconnecting cables that hang closer than 40 cm to the ground plane shall be folded back and forth in the center forming a bundle 30 to 40 cm long.
c. I/O cables that are not connected to a peripheral shall be bundled in the center. The end of the cable may be terminated, if required, using the correct terminating impedance. The overall length shall not exceed 1 m.
d. LISN at least 80 cm from nearest part of EUT chassis.
e. For the actual test configuration, please refer to the related Item –EUT Test Photos.

4.1.3 DEVIATION FROM TEST STANDARD

No deviation

4.1.43.1.2 TEST SETUP



Note: 1.Support units were connected to second LISN.
2.Both of LISNs (AMN) are 80 cm from EUT and at least 80 from other units and other metal planes

4.1.53.1.3 EUT OPERATING CONDITIONS

The EUT was configured for testing in a typical fashion (as a customer would normally use it). The EUT has been programmed to continuously transmit during test. This operating condition was tested and used to collect the included data.

4.1.63.1.4 TEST RESULTS

N/A

3.2 4.2 RADIATED EMISSION MEASUREMENT

Test Requirement:	FCC Part15 C Section 15.209
Test Method:	ANSI C63.10-2020 + Cor. 1-2023+C63.10a-2024 + Errata to C63.10a-2024
Test Frequency Range:	9kHz to 25GHz
Test site:	Measurement Distance: 3m
Receiver setup:	

Frequency	Detector	RBW	VBW	Value
9KHz-150KHz	Quasi-peak	200Hz	600Hz	Quasi-peak
150KHz-30MHz	Quasi-peak	9KHz	30KHz	Quasi-peak
30MHz-1GHz	Quasi-peak	100KHz	300KHz	Quasi-peak
Above 1GHz	Peak	1MHz	3MHz	Peak
	Peak	1MHz	10Hz	Average

4.2.13.2.1 RADIATED EMISSION LIMITS

20dBc in any 100 kHz bandwidth outside the operating frequency band. In case the emission fall within the restricted band specified on 15.205(a), then the 15.231(b) limit in the table below has to be followed.

Frequencies(MHz)	Field Strength(micorvolts/meter)	Measurement Distance(meters)
0.009~0.490	2400/F(KHz)	300
0.490~1.705	24000/F(KHz)	30
1.705~30.0	30	30
30~88	100	3
88~216	150	3
216~960	200	3
Above 960	500	3

LIMITS OF RADIATED EMISSION MEASUREMENT

FREQUENCY (MHz)	Limit (dBuV/m) (at 3M)	
	PEAK	AVERAGE
Above 1000	74	54

Notes:

(1) The limit for radiated test was performed according to FCC PART 15C.

(2) The tighter limit applies at the band edges.

(3) Emission level (dBuV/m)=20log Emission level (uV/m).

FUNDAMENTAL AND HARMONICS EMISSION LIMITS

Fundamental Frequency (MHz)	Field Strength of Fundamental (microvolts/meter)	Field Strength of Spurious Emissions (microvolts/meter)
40.66 - 40.70	2,250	225
70 - 130	1,250	125
130 - 174	1,250 to 3,750 **	125 to 375 **
174 - 260	3,750	375
260 - 470	3,750 to 12,500 **	375 to 1,250 **
Above 470	12,500	1,250

** linear interpolations

[Where F is the frequency in MHz, the formulas for calculating the maximum permitted fundamental field strengths are as follows: for the band 130-174 MHz, μV/m at 3 meters = 56.81818(F) - 6136.3636; for the band 260-470 MHz, μV/m at 3 meters = 41.6667(F) - 7083.3333. The maximum permitted unwanted emission level is 20 dB below the maximum permitted fundamental level.]

FREQUENCY RANGE OF RADIATED MEASUREMENT (For unintentional radiators)

Highest frequency generated or Upper frequency of measurement used in the device or on which the device operates or tunes (MHz)	Range (MHz)
Below 1.705	30
1.705 – 108	1000
108 – 500	2000
500 – 1000	5000
Above 1000	5th harmonic of the highest frequency or 40 GHz, whichever is lower

Spectrum Parameter	Setting
Attenuation	Auto
Start Frequency	1000 MHz
Stop Frequency	10th carrier harmonic
RBW / VBW setting	1 MHz / 1 MHz for Peak, 1 MHz / 10Hz for Average

Receiver Parameter	Setting
Attenuation	Auto
Start ~ Stop Frequency	9kHz~150kHz / RB 200Hz for QP
Start ~ Stop Frequency	150kHz~30MHz / RB 9kHz for QP
Start ~ Stop Frequency	30MHz~1000MHz / RB 120kHz for QP

4.2.23.2.2 TEST PROCEDURE

a. The measuring distance of at 3 m shall be used for measurements at frequency up to 1GHz. For frequencies above 1GHz, any suitable measuring distance may be used.
b. The EUT was placed on the top of a rotating table 0.8 meters above the ground at a 3 meter open area test site. The table was rotated 360 degrees to determine the position of the highest radiation.

c. The height of the equipment or of the substitution antenna shall be 0.8 m; above 1GHz, the height was 1.5m, the height of the test antenna shall vary between 1 m to 4 m. Both horizontal and vertical polarizations of the antenna are set to make the measurement.
d. The initial step in collecting conducted emission data is a spectrum analyzer peak detector mode pre-scanning the measurement frequency range. Significant peaks are then marked and then Quasi Peak detector mode re-measured.
e. If the Peak Mode measured value compliance with and lower than Quasi Peak Mode Limit, the EUT shall be deemed to meet QP Limits and then no additional QP Mode measurement performed.
f. For the actual test configuration, please refer to the related Item –EUT Test Photos.

Note:

Both horizontal and vertical antenna polarities were tested
and performed pretest to three orthogonal axis. The worst case was X axis and the emissions were reported

4.2.33.2.3 TEST SETUP

（A）Radiated Emission Test-Up Frequency Below 30MHz



（B）Radiated Emission Test-Up Frequency 30MHz~1GHz



（C）Radiated Emission Test-Up Frequency Above 1GHz



4.2.43.2.4 EUT OPERATING CONDITIONS

The EUT tested system was configured as the statements of 2.4 Unless otherwise a special operating condition is specified in the follows during the testing.

4.2.53.2.5 TEST RESULTS

Radiated Spurious Emission (Below 9KHz – 30MHz)

Temperature :	26 ℃	Relative Humidity :	54%
Pressure :	101 kPa	Polarization :	---
Test Voltage :	DC 3V		
Test Mode :	TX Mode		

Freq.	Reading	Limit	Margin	State
(MHz)	(dBuV/m)	(dBuV/m)	(dB)	P/F
--	--	--	--	PASS
--	--	--	--	PASS

NOTE:
The amplitude of spurious emissions which are attenuated by more than 20dB below the permissible value has no need to be reported.
Distance extrapolation factor =40 log (specific distance/test distance)(dB);
Limit line = specific limits(dBuv) + distance extrapolation factor.

Radiated Spurious Emission (Between 30MHz – 1GHz)

Temperature :	26 ℃	Relative Humidity :	54%
Pressure :	101 kPa	Polarization :	Horizontal
Test Voltage :	DC 3V		
Test Mode :	TX Mode		



No.	Mk.	Freq.	Reading Level	Correct Factor	Measure-ment	Limit	Over	
		MHz	dBuV	dB	dBuV/m	dB/m	dB	Detector
1		44.1202	28.02	-6.10	21.92	40.00	-18.08	QP
2		88.9639	34.23	-7.99	26.24	43.50	-17.26	QP
3		164.3301	26.13	-3.40	22.73	43.50	-20.77	QP
4		328.4627	25.48	-2.06	23.42	46.00	-22.58	QP
5		434.8268	84.11	-0.26	83.85	100.8	-16.95	peak
6	*	869.1302	56.28	9.22	65.50	80.80	-15.30	peak

Remarks:
1.Final Level =Receiver Read level + Antenna Factor + Cable Loss – Preamplifier Factor
2.The emission levels of other frequencies are very lower than the limit and not show in test report.

Temperature :	26 ℃	Relative Humidity :	54%
Pressure :	101 kPa	Polarization :	Vertical
Test Voltage :	DC 3V		
Test Mode :	TX Mode		



No.	Mk.	Freq.	Reading Level	Correct Factor	Measure-ment	Limit	Over	
		MHz	dBuV	dB	dBuV/m	dB/m	dB	Detector
1	*	44.1202	32.52	-6.10	26.42	40.00	-13.58	QP
2		72.7190	29.70	-8.09	21.61	40.00	-18.39	QP
3		88.9639	35.23	-7.99	27.24	43.50	-16.26	QP
4		170.1948	26.65	-3.38	23.27	43.50	-20.23	QP
5		434.8268	83.11	-0.26	82.85	100.8	-17.95	peak
6		869.1302	49.78	9.22	59.00	80.80	-21.80	peak

Remarks:
1.Final Level =Receiver Read level + Antenna Factor + Cable Loss – Preamplifier Factor
2.The emission levels of other frequencies are very lower than the limit and not show in test report.

For average Emission

Frequency MHz	Peak Level dBuV/m	Duty cycle factor	AverageLevel dBuV/m	Limit AV	Margin	Polarization
434.83	83.85	-10.27	73.58	80.8	-7.22	Horizontal
869.13	65.50	-10.27	55.23	60.8	-5.57	Horizontal
434.83	82.85	-10.27	72.58	80.8	-8.22	Vertical
869.13	59.00	-10.27	48.73	60.8	-12.07	Vertical

Notes: Average emission Level = Peak Level + Duty cycle factor

Above 1GHz Test Results

Frequency MHz	Peak Level dBuV/m	Duty cycle factor	Average Level dBuV/m	Limit		Margin dB		Polarization
				PK	AV	PK	AV	
1304.49	50.60	-10.27	40.33	74	54	-23.4	-13.67	Vertical
1739.32	48.17	-10.27	37.9	80.8	60.8	-32.63	-22.9	Vertical
2174.15	42.28	-10.27	32.01	80.8	60.8	-38.52	-28.79	Vertical
2608.98	42.86	-10.27	32.59	80.8	60.8	-37.94	-28.21	Vertical
3043.81	41.09	-10.27	30.82	80.8	60.8	-39.71	-29.98	Vertical
3478.64	40.31	-10.27	30.04	80.8	60.8	-33.69	-23.96	Vertical
1304.49	50.61	-10.27	40.34	74	54	-23.39	-13.66	Horizontal
1739.32	48.37	-10.27	38.1	80.8	60.8	-32.43	-22.7	Horizontal
2174.15	42.67	-10.27	32.4	80.8	60.8	-38.13	-28.4	Horizontal
2608.98	42.33	-10.27	32.06	80.8	60.8	-38.47	-28.74	Horizontal
3043.81	41.85	-10.27	31.58	80.8	60.8	-38.95	-29.22	Horizontal
3478.64	40.96	-10.27	30.69	80.8	60.8	-33.04	-23.31	Horizontal

Notes: Average emission Level = Peak Level + Duty cycle factor

5. 3.2.6BANDWIDTH TEST

5.13.2.1 APPLIED PROCEDURES / LIMIT

According to FCC 15.231(c) requirement:

The bandwidth of the emission shall be no wider than 0.25% of the center frequency for devices operating between 70 MHz to 900 MHz. Those devices operating above 900 MHz, the emission spurious shall be no wider than 0.5% of the center frequency. Bandwidth is determined at the points 20 dB down from the modulated carrier.

B.W (20dBc) Limit = 0.25% * f(MHz) = 0.25% * 433.92MHz = 1.085MHz

Spectrum Parameter	Setting
Attenuation	Auto
Span Frequency	> Measurement Bandwidth or Channel Separation
RB	10kHz
VB	≥RBW
Detector	Peak
Trace	Max Hold
Sweep Time	Auto

5.23.2.1.1 TEST PROCEDURE

a. The EUT was directly connected to the spectrum analyzer and antenna output port as show in the block diagram below,
b. Spectrum Setting : RBW= 10kHz, VBW≥ RBW, Sweep time = Auto.

5.33.2.1.2 DEVIATION FROM STANDARD

No deviation.

5.43.2.1.3 TEST SETUP



5.53.2.1.4 EUT OPERATION CONDITIONS

The EUT tested system was configured as the statements of 2.4 Unless otherwise a special operating condition is specified in the follows during the testing.

5.63.2.1.5 TEST RESULTS

Temperature：	26 ℃	Relative Humidity：	54%
Pressure：	101kPa	Test Voltage ：	DC 3V
Test Mode ：	TX Mode		

Frequency	20dB Bandwidth (KHz)	Limit (MHz)	Result
433.928MHz	139.2	1.082	PASS



6. 4CALCULATION OF AVERAGE FACTOR

The output field strengths of specification in accordance with the FCC rules specify measurements with an average detector. During the test, a spectrum analyzer incorporating a peak detector was used. Therefore, a reduction factor can be applied to the resultant peak signal level and compared to the limit for measurement instrumentation incorporating an average detector.

The duty cycle is measured in 100 ms or the repetition cycle period, whichever is a shorter time frame. The duty cycle is measured by placing the spectrum analyzer to set zero span at 1MHz resolution bandwidth.

Averaging factor in dB =20log (duty cycle)

The duration of one cycle =100.00ms

The duty cycle is simply the on-time divided the duration of one cycle

Duty Cycle = (30.64×1)/ 100.00

=30.64ms / 100.00ms

Therefore, the averaging factor is found by 20log0.3064= -10.27dB

Test plot as follows:

Note: During the 100ms, the amount of pulse and on-time of pulse are the same for every pulse train.

Temperature：	26 ℃	Relative Humidity：	54%
Pressure：	101kPa	Test Voltage ：	DC 3V
Test Mode ：	TX Mode		

Cycle			

Pulse			
On-time1			

7. 5DWELL TIME

7.1 APPLICABLE STANDARD

According to FCC 15.231(a) requirement:

A manually operated transmitter shall employ a switch that will automatically deactivate the transmitter within not more than 5 seconds of being released.

7.2 TEST PROCEDURE

Check the calibration of the measuring instrument using either an internal calibrator or a known signal from an external generator.

1.Position the EUT without connection to measurement instrument. Turn on the EUT and connect its antenna terminal to measurement instrument via a low loss cable. Then set it to any one measured frequency within its operating range, and make sure the instrument is operated in its linear range.

2.Set RBW to 100kHz and VBW of spectrum analyzer to 300kHz with a convenient frequency span including 100 KHz bandwidth from band edge.

3.Measure the highest amplitude appearing on spectral display and set it as a reference level. Plot the graph with marking the highest point and edge frequency.

4.Repeat above procedures until all measured frequencies were complete.

5.17.3 DEVIATION FROM STANDARD

No deviation.

7.45.2 TEST SETUP



7.55.3 EUT OPERATION CONDITIONS

The EUT tested system was configured as the statements of 2.4 Unless otherwise a special operating condition is specified in the follows during the testing.

7.65.4 TEST RESULTS

Dwell time (second)	Limit (second)	Result
1.850	<5s	Pass

Test plot as follows:



8. 6ANTENNA REQUIREMENT

Standard requirement:	FCC Part15 C Section 15.203
15.203 requirement: An intentional radiator shall be designed to ensure that no antenna other than that furnished by the responsible party shall be used with the device. The use of a permanently attached antenna or of an antenna that uses a unique coupling to the intentional radiator, the manufacturer may design the unit so that a broken antenna can be replaced by the user, but the use of a standard antenna jack or electrical connector is prohibited.	
EUT Antenna:	
The antennas are PCB Antenna , the best case gain of the antennas are 1.0dBi, reference to the attachment for details	

9. TEST SETUP PHOTO

Reference to the Test photo attachment for details.

10. EUT CONSTRUCTIONAL DETAILS

Reference to EUT photo attachment for details.

※※※※※ **END OF REPORT** ※※※※※