

| Comment      | Test Frequency (MHz) | Meter Reading (dBuV) | Total Loss (dB) | Antenna Polarization | Result @ 300m (uV/m) | Limit @ 300m (uV/m) | Margin (uV/m) |
|--------------|----------------------|----------------------|-----------------|----------------------|----------------------|---------------------|---------------|
| Side band    | 2398.637275          | 30.50                | 35.08           | V                    | 11.79716926          | 34.22               | 22.42283074   |
| Fundamental  | 2435.654165          | 59.76                | 35.11           | H                    | 348.8256828          | EXEMPT              |               |
| Side band    | 2501.002004          | 15.16                | 35.16           | H                    | 2.117580286          | 34.22               | 32.10241971   |
| Spurious     | 4382.164165          | 14.56                | 42.34           | H                    | 6.852247049          | 34.22               | 27.36775295   |
| 2nd.Harmonic | 4943.654642          | 16.34                | 43.37           | V                    | 9.671637267          | 34.22               | 24.54838273   |
| Spurious     | 6476.553106          | 17.41                | 46.63           | H                    | 15.92208727          | 34.22               | 18.29791273   |
| 3rd.Harmonic | 7364.729459          | 19.32                | 48.50           | H                    | 24.60367604          | 34.22               | 9.616323959   |
| Spurious     | 8187.144965          | 15.17                | 50.60           | H                    | 19.43121692          | 34.22               | 14.78878308   |
| 4th.Harmonic | 9891.783567          | 9.25                 | 52.13           | H                    | 11.72195366          | 34.22               | 22.49804634   |
| 5th.Harmonic | 12024.16541          | 13.05                | 52.13           | H                    | 18.15515663          | 34.22               | 16.06484337   |

#### 5. Safety check

At 275ml water load was placed in the center of the oven. The power setting was set to maximum power. While the oven was operating, the radiation emission instrument was moved at 2.5cm/s around the door seams to check for leakage.

Safety check: 0.07MW/cm<sup>2</sup>.

Remark: Attachment 2: Test photographs

Follow is blank