

1. Dayway 450SX4

a) Channel 1

Operation Mode : Transmitting / Receiving

Test Date : Jan. 27, 2001

Temperature : 14

Humidity: 71 %

Frequency (MHz)	Reading (dBuV)		Factor (dB)	Result (dBuV)		Limit (dBuV)	Margin (dB)
	Va	Vb		Va	Vb		
0.4857	29.9	35.1	0.2	30.1	35.3	48.0	-12.7
2.4010	28.0	26.9	0.3	28.3	27.2	48.0	-19.7
5.9824	32.4	32.1	0.4	32.8	32.5	48.0	-15.2
6.4204	24.8	26.8	0.4	25.2	27.2	48.0	-20.8
8.7352	26.0	25.6	0.5	26.5	26.1	48.0	-21.5
17.9501	42.2	42.1	0.9	43.1	43.0	48.0	-4.9

b) Channel 6

Operation Mode : Transmitting / Receiving

Test Date : Jan. 27, 2001

Temperature : 14

Humidity: 71 %

Frequency (MHz)	Reading (dBuV)		Factor (dB)	Result (dBuV)		Limit (dBuV)	Margin (dB)
	Va	Vb		Va	Vb		
0.4857	30.2	35.4	0.2	30.4	35.6	48.0	-12.4
2.4010	27.6	26.3	0.3	27.9	26.6	48.0	-20.1
5.9824	32.2	31.8	0.4	32.6	32.2	48.0	-15.4
6.4204	25.4	25.8	0.4	25.8	26.2	48.0	-21.8
8.7352	25.3	26.4	0.5	25.8	26.9	48.0	-21.1
17.9501	43.2	43.0	0.9	44.1	43.9	48.0	-3.9

c) Channel 11

Operation Mode : Transmitting / Receiving

Test Date : Jan. 27, 2001

Temperature : 14

Humidity: 71 %

Frequency (MHz)	Reading (dBuV)		Factor (dB)	Result (dBuV)		Limit (dBuV)	Margin (dB)
	Va	Vb		Va	Vb		
0.4857	30.3	34.5	0.2	30.5	34.8	48.0	-13.2
2.4010	27.5	26.6	0.3	27.8	26.9	48.0	-20.2
5.9824	32.4	32.8	0.4	32.7	33.2	48.0	-14.8
6.4204	25.6	26.5	0.4	26.0	26.8	48.0	-21.2
8.7352	26.3	25.6	0.5	26.8	26.0	48.0	-21.2
17.9501	42.9	42.9	0.9	43.8	43.7	48.0	-4.2

2. Gateway 600YGR

a) Channel 1

Operation Mode : Transmitting / Receiving

Test Date : Jan. 27, 2001

Temperature : 14

Humidity: 71 %

Frequency (MHz)	Reading (dBuV)		Factor (dB)	Result (dBuV)		Limit (dBuV)	Margin (dB)
	Va	Vb		Va	Vb		
0.4842	29.8	37.3	0.2	30.0	37.5	48.0	-10.5
0.8553	29.6	35.8	0.3	29.9	36.1	48.0	-11.9
2.3034	27.7	25.8	0.3	28.0	26.1	48.0	-20.0
5.9826	35.4	31.6	0.4	35.8	32.0	48.0	-12.2
8.3336	25.6	26.7	0.4	26.0	27.1	48.0	-20.9
17.9502	43.7	43.6	0.9	44.6	44.5	48.0	-3.4

b) Channel 6

Operation Mode : Transmitting / Receiving

Test Date : Aug. 24, 2001

Temperature : 24

Humidity: 71 %

Frequency (MHz)	Reading (dBuV)		Factor (dB)	Result (dBuV)		Limit (dBuV)	Margin (dB)
	Va	Vb		Va	Vb		
0.4842	29.0	38.3	0.2	29.3	38.5	48.0	-9.5
0.8553	28.6	34.9	0.3	28.9	35.2	48.0	-12.8
2.3034	28.4	25.6	0.3	28.7	25.9	48.0	-19.3
5.9826	36.2	32.1	0.4	36.5	32.4	48.0	-11.5
8.3336	25.1	25.9	0.4	25.5	26.4	48.0	-21.6
17.9502	43.7	44.0	0.9	44.6	44.9	48.0	-3.1

c) Channel 11

Operation Mode : Transmitting / Receiving

Test Date : Jan. 27, 2001

Temperature : 14

Humidity: 71 %

Frequency (MHz)	Reading (dBuV)		Factor (dB)	Result (dBuV)		Limit (dBuV)	Margin (dB)
	Va	Vb		Va	Vb		
0.4842	30.2	37.7	0.2	30.4	37.9	48.0	-10.1
0.8553	30.0	36.8	0.3	30.3	37.0	48.0	-11.0
2.3034	27.9	26.7	0.3	28.2	27.0	48.0	-19.8
5.9826	36.0	31.0	0.4	36.4	31.4	48.0	-11.6
8.3336	25.8	27.6	0.4	26.3	28.1	48.0	-19.9
17.9502	43.6	43.0	0.9	44.5	43.9	48.0	-3.5