

GNS 430 Pilot's Guide and Reference

GARMIN Corporation
1200 E. 151st Street
OLATHE, KS 66062




Dwg. Number 190-00140-00 REV. F

	APPROVALS	DATE
DRAWN	K. Otterman	12/1/98
CHKD.	J W D	12/1/98
PROJ. MGR.	T L J	12/1/98
RELEASED	M L R	12/8/98

CONFIDENTIAL
This document and the specifications contained herein are the property of GARMIN Corporation and may not be reproduced or used in whole or in part as the basis for manufacturing or sale of products without written permission of GARMIN Corporation.

ARCHIVE FILE: 190-00140-00_OF
FILE TYPE: QuarkXPress for Windows

REV	DATE	DESCRIPTION OF CHANGE	ECO#
A	12/1/98	INITIAL RELEASE	N/A
B	4/30/99	Update to conform to recent software changes	10944
C	6/24/99	Reference Update for ECO #11294	11294
D	7/28/99	Update for software 2.10	11507
E	4/14/00	Update for software 2.15	13131
F	7/24/00	Update pwr on, wind vctr, crossfill, DME, fuel plan	13800



GARMIN International, Inc., 1200 East 151st Street, Olathe, Kansas 66062 USA
Tel: 913/397.8200 Fax: 913/397.8282

GARMIN (Europe) LTD, Unit 5, The Quadrangle, Abbey Park, Romsey, Hampshire SO51 9AQ, UK
Tel: 44/1794.519944 Fax: 44/1794.519222

GARMIN (Asia) Corp., No. 68, Jangshu 2nd Road., Shijr, Taipei County, Taiwan
Tel: 886/2.2642.9199 Fax: 886/2.2642-9099

Website Address: www.garmin.com

© 1998- 2000 GARMIN Corporation. All rights reserved. Except as expressly provided herein, no part of this manual may be reproduced, copied, transmitted, disseminated, downloaded or stored in any storage medium, for any purpose without the express prior written consent of GARMIN Corporation. GARMIN Corporation hereby grants permission to download a single copy of this manual and of any revision to this manual onto a hard drive or other electronic storage medium to be viewed and to print one copy of this manual or of any revision hereto, provided that such electronic or printed copy of this manual or revision must contain the complete text of this copyright notice and provided further that any unauthorized commercial distribution of this manual or any revision hereto is strictly prohibited.

Information in this document is subject to change without notice. GARMIN reserves the right to change or improve their products and to make changes in the content of this material without obligation to notify any person or organization of such changes or improvements.

July 2000

190-00140-00 Rev. F

INTRODUCTION

Foreword

Visit the GARMIN website for the latest updates and supplemental information concerning the operation of this and other GARMIN products.

GARMIN, GNS 430, Spell'N'Find, AutoLocate and PhaseTrac12 are trademarks of GARMIN and may only be used with permission.

NavData® is a registered trademark of Jeppesen, Inc.

This manual incorporates changes included in Main System Software version 2.17. It includes information contained in the Addendum to Pilot's Guide P/N 190-00140-11 Rev A, covering crossfill and fuel management operation for software 2.11 and above.



INTRODUCTION

Cautions

NOTE: This device complies with Part 15 of the FCC limits for Class B digital devices. This equipment generates, uses, and can radiate radio frequency energy and, if not installed and used in accordance with the instructions, may cause harmful interference to radio communications. Furthermore, there is no guarantee that interference will not occur in a particular installation.

If this equipment does cause harmful interference, the user is encouraged to try to correct the interference by relocating the equipment or connecting the equipment to a different circuit than the affected equipment. Consult an authorized dealer or other qualified avionics technician for additional help if these remedies do not correct the problem.

Operation of this device is subject to the following conditions: (1) This device may not cause harmful interference, and (2) this device must accept any interference received, including interference that may cause undesired operation.

The GARMIN GNS 430 does not contain any user-serviceable parts. Repairs should only be made by an authorized GARMIN service center. Unauthorized repairs or modifications could void your warranty and authority to operate this device under Part 15 regulations.

CAUTION

The Global Positioning System is operated by the United States government, which is solely responsible for its accuracy and maintenance. The system is subject to changes which could affect the accuracy and performance of all GPS equipment. Although the GARMIN GNS 430 is a precision electronic NAVigation AID (NAVAID), any NAVAID can be misused or misinterpreted and therefore become unsafe.

Use the GNS 430 at your own risk. To reduce the risk of unsafe operation, carefully review and understand all aspects of this Owner's Manual and the Flight Manual Supplement, and thoroughly practice basic operation prior to actual use. When in actual use, carefully compare indications from the GNS 430 to all available navigation sources, including the information from other NAVAIDS, visual sightings, charts, etc. For safety, always resolve any discrepancies before continuing navigation.

The altitude calculated by the GNS 430 is geometric height above mean sea level and could vary significantly from altitude displayed by pressure altimeters in aircraft. GPS accuracy may be degraded by the U.S. Department of Defense-imposed Selective Availability (SA) program. With "SA" on, GPS altitude may be in error by several hundred feet. Never use GPS altitude for vertical navigation.

GPS receivers operate by receiving and decoding very low power radio signals broadcast by satellites. It is possible that in some situations other radio equipment or electronic equipment used in close proximity to a GPS receiver may create electromagnetic interference (EMI) which may affect the ability of the GPS receiver to receive and decode the satellite signals. In such event, the interference may be reduced or eliminated by switching off the source of interference or relocating equipment.

The Jeppesen database incorporated in the GNS 430 must be updated regularly in order to ensure that its information is current. Updates are released every 28 days. A database information packet is included in your GNS 430 package.

Pilots using an out-of-date database do so entirely at their own risk.

Accessories & Packing List

Congratulations on choosing the finest, most advanced panel mount IFR navigation/communication system available. The GNS 430 represents GARMIN's commitment to provide accurate, easy-to-use avionics for all of your flying needs.

Before installing and getting started with your new system, please check to see that your package includes the following items. If any parts are missing or damaged, please see your GARMIN dealer immediately.

Standard Package:

- GNS 430 Unit & NavData® Card
- Installation Rack & Connectors
- Pilot's Guide & Quick Reference Guide
- Database Subscription Packet
- Warranty Registration Card

Your GARMIN dealer will perform the installation and configuration of your new GNS 430. After installation, the NavData® card will already be installed into the correct slot on the front of the unit (see Appendix A). The GNS 430 will be secured in the installation rack with the proper wiring connections performed. Have your dealer answer any questions you may have about the installation—such as location of antennas or any connections to other equipment in the panel.

INTRODUCTION

Accessories and Packing List

To obtain accessories for your GNS 430, please contact your GARMIN dealer.

The GNS 430 display lens is coated with a special anti-reflective coating which is very sensitive to skin oils, waxes and abrasive cleaners. It is very important to clean the lens using an eyeglass lens cleaner which is specified as safe for anti-reflective coatings (one suitable product is Wal-Mart® Lens Cleaner) and a clean, lint-free cloth.

Help us better support you by completing our online registration today! Registration ensures you will be notified of product updates, new products and provides lost or stolen unit tracking. Have the serial number of your GNS 430 handy and connect to our website (www.garmin.com). Look for the Product Registration link on the home page.

INTRODUCTION

Warranty

GARMIN is fully committed to your satisfaction as a customer. If you have any questions regarding the GNS 430, please contact our customer service department at:

*GARMIN International, Inc.
1200 East 151st Street
Olathe, KS 66062-3426
(913) 397-8200
FAX (913) 397-8282*

To obtain warranty service, call the GARMIN Customer Service department for a returned merchandise tracking number. The unit should be securely packaged with the tracking number clearly marked on the outside of the package, and sent freight prepaid and insured to a GARMIN warranty service station. A copy of the original sales receipt is required as proof of purchase for warranty repairs. GARMIN retains the exclusive right to repair or replace the unit or software or offer a full refund of the purchase price at its sole discretion. SUCH REMEDY SHALL BE YOUR SOLE AND EXCLUSIVE REMEDY FOR ANY BREACH OF WARRANTY.

GARMIN Corporation warrants this product to be free from defects in materials and workmanship for one year from the date of purchase. GARMIN will, at its sole option, repair or replace any components that fail in normal use. Such repairs or replacement will be made at no charge to the customer for parts or labor. The customer is, however, responsible for any transportation costs. This warranty does not cover failures due to abuse, misuse, accident or unauthorized alteration or repairs.

THE WARRANTIES AND REMEDIES CONTAINED HEREIN ARE EXCLUSIVE, AND IN LIEU OF ALL OTHER WARRANTIES EXPRESSED OR IMPLIED, INCLUDING ANY LIABILITY ARISING UNDER WARRANTY OF MERCHANTABILITY OR FITNESS FOR A PARTICULAR PURPOSE, STATUTORY OR OTHERWISE. THIS WARRANTY GIVES YOU SPECIFIC LEGAL RIGHTS, WHICH MAY VARY FROM STATE TO STATE.

IN NO EVENT SHALL GARMIN BE LIABLE FOR ANY INCIDENTAL, SPECIAL, INDIRECT OR CONSEQUENTIAL DAMAGES, WHETHER RESULTING FROM THE USE, MISUSE OR INABILITY TO USE THIS PRODUCT OR FROM DEFECTS IN THE PRODUCT. SOME STATES DO NOT ALLOW THE EXCLUSION OF INCIDENTAL OR CONSEQUENTIAL DAMAGES, SO THE ABOVE LIMITATIONS MAY NOT APPLY TO YOU.

PART ONE: INTRODUCTION

Foreword	i
Cautions	ii
Accessories/Packing List	iii
Warranty	iv
Table of Contents	v-vi
Takeoff Tour	1-20

PART TWO: REFERENCE

Section 1: Communicating with the GNS 430	21
COM and VLOC frequencies	
Active and standby frequencies	
Section 2: NAV Page Group (GPS navigation)	27
Using page groups and selecting the desired page	
Using the default NAV and map pages	
Section 3: Direct-to Navigation	49
Using the ▷◁ key	
Section 4: Flight Plans (FPL key and FPL page group)	54
Creating and using flight plans	
Retrieving and editing stored flight plans	
Section 5: Approaches, Departures and Arrivals (PROC key)	66
Selecting and flying non-precision/precision approaches	
Selecting and using departures (SIDs) and arrivals (STARs)	

INTRODUCTION

Table of Contents

CONVENTIONS USED IN THIS MANUAL

A circled number (e.g., "⑧") will appear next to many of the illustrations shown along the side of a page. This number refers back to a specific step on the same page (or in rare instances, to a step on the following page).

When more than one option is possible within a procedure, the procedures are described using an "a"/"b" convention with the same numbering (e.g., "3a" and "3b" for two step#3 options). This same convention is used when multiple procedures are listed on the same page and illustrations are provided for the steps described in one or both procedures (e.g., "③a" and "③b").

A highlighted "NOTE" area appears on many pages to point out additional information or items of particular importance related to a given subject.

INTRODUCTION

Table of Contents

To quickly and easily locate information on specific tasks, please refer to the Index on page 187.

Section 6: WPT Page Group (Waypoint/database information)	94
Finding and viewing airport location, runway and frequency data	
Finding and viewing navaid information	
Creating user-defined waypoints	
Section 7: NRST Page Group (Nearest airports, etc.)	119
Viewing nearest listings for airports, navaids and airspaces	
Displaying frequencies for nearest flight service station (FSS) and center (ARTCC/FIR)	
Section 8: VLOC (VOR/Localizer/Glideslope) Receiver Operations	131
Section 9: AUX page group (Flight Planning and Unit Settings)	135
Section 10: Messages, Abbreviations & Navigation Terminology	163
Appendix A: NavData [®] Card Use	177
Appendix B: Specifications	178
Appendix C: Map Datums	179
Appendix D: Troubleshooting Q & A	181
Appendix E: Index	187

Key and Knob Functions

The GNS 430 is designed to make operation as simple as possible. The key and knob descriptions on the next three pages provide a general overview of the primary function(s) for each key and knob. This Takeoff Tour section is intended to provide a brief overview of the primary functions of your GNS 430. Experiment with the unit and refer to the Reference sections for more information.

Left-hand Keys and Knobs



The COM power/volume knob controls unit power and communications radio volume. Press momentarily to disable automatic squelch control.



The VLOC volume knob controls audio volume for the selected VOR/Localizer frequency. Press momentarily to enable/disable the ident tone.



The large left knob (COM/VLOC) is used to tune the megahertz (MHz) value of the standby frequency for the communications transceiver (COM) or the VLOC receiver, whichever is currently selected by the tuning cursor.




The small left knob (COM/VLOC) is used to tune the kilohertz (kHz) value of the standby frequency for the communications transceiver (COM) or the VLOC receiver, whichever is currently selected by the tuning cursor. Press this knob momentarily to toggle the tuning cursor between the COM and VLOC frequency fields.




The COM flip-flop key is used to swap the active and standby COM frequencies. Press and hold to select emergency channel (121.500 MHz).



The VLOC flip-flop key is used to swap the active and standby VLOC frequencies (i.e., make the selected standby frequency active).



Left-hand Keys and Knobs



TAKEOFF TOUR

Key and Knob Functions



Data is entered using the large and small knobs. Experiment with them to become efficient at entering data. This will greatly reduce the amount of time spent operating the GNS 430 in flight.



Right-hand Keys and Knobs



The range key allows you to select the desired map scale. Use the up arrow side of the key to zoom out to a larger area, or the down arrow side to zoom in to a smaller area.



The direct-to key provides access to the direct-to function, which allows you to enter a destination waypoint and establishes a direct course to the selected destination. See Section 3.



The menu key displays a context-sensitive list of options. This options list allows you to access additional features or make settings changes which relate to the currently displayed page.



The clear key is used to erase information or cancel an entry. Press and hold this key to immediately display the Default Navigation Page (see pages 12 and 28), regardless of which page is currently displayed.




The enter key is used to approve an operation or complete data entry. It is also used to confirm information, such as during power on.



The large right knob (CRSR) is used to select between the various page groups: NAV, WPT, AUX or NRST. With the on-screen cursor enabled, the large right knob allows you to move the cursor about the page.



The small right knob (CRSR) is used to select between the various pages within one of the groups listed above. Press this knob momentarily to display the on-screen cursor. The cursor allows you to enter data and/or make a selection from a list of options.



Bottom Row Keys

CDI

The CDI key is used to toggle which navigation source (GPS or VLOC) provides output to an external HSI or CDI.

OBS

The OBS key is used to select manual or automatic sequencing of waypoints. Pressing the OBS key selects OBS mode, which will retain the current “active to” waypoint as your navigation reference even after passing the waypoint (i.e., prevents sequencing to the next waypoint). Pressing the OBS key again will return to normal operation, with automatic sequencing of waypoints. Whenever OBS mode is selected, you may set the desired course to/from a waypoint using the OBS Page, or an external OBS selector on your HSI or CDI.

MSG

The message key is used to view system messages and to alert you to important warnings and requirements. See Sections 10 and 9 for more information on messages and unit settings.

FPL

The flight plan key allows you to create, edit, activate and invert flight plans, as well as access approaches, departures and arrivals. A closest point to flight plan feature is also available from the flight plan key. See Section 4 for more information on flight plans.

PROC

The procedures key allows you to select and remove approaches, departures and arrivals from your flight plan. When using a flight plan, available procedures for your departure and/or arrival airport are offered automatically. Otherwise, you may select the desired airport, then the desired procedure.

TAKEOFF TOUR

Key and Knob Functions

NEAREST AIRPORT			
APT	BRG	DIS	APR
KCOU	358°	0.0 ⁿ	ILS
twr	119.300	rwly	6500'
KFTT	081°	10.2 ⁿ	VOR
uni	122.800	rwly	3200'
KJEF	166°	14.0 ⁿ	ILS
twr	125.600	rwly	6000'

GPS HSG NRST 0000000

scroll bar

Whenever the GNS 430 is displaying a list of information that is too long for the display screen, a scroll bar will appear along the right-hand side of the display. The scroll bar graphically indicates the number of additional items available within the selected category.


Simply press the small right knob (PUSH CRSR) to activate the cursor and rotate the large right knob (PUSH C/V) to scroll through the list.

TAKEOFF TOUR

Power On



The welcome page appears when the GNS 430 is turned on. During the time this screen is displayed, the GNS 430 performs a self-test to ensure proper operation.



The database confirmation page shows the effective and expiration dates of the Jeppesen database on the NavData Card.

The GARMIN GNS 430 provides you accurate navigational data and communication capability, along with non-precision and precision approach certification in the IFR environment. The Takeoff Tour is designed to familiarize you with the operation of the GNS 430 — including powering up the unit, changing frequencies, entering data, performing a simple direct-to, selecting IFR procedures and provides a limited introduction to using flight plans. In addition, this section briefly covers the default navigation, map and frequency pages available as part of the NAV page group. These pages will be used for most of your in-flight navigation.


The Takeoff Tour assumes that the unit and antennas have been properly installed and you have not changed any of the GNS 430's default settings. If you have changed any of the factory default settings (position format, units of measure, selectable fields, etc.), the pictures shown here may not exactly match what you see on your GNS 430. Prior to using your GNS 430 for the first time, we recommend that you taxi to a location that is well away from buildings and other aircraft so the unit can collect satellite data without interruption.

Powering up the GNS 430

The GNS 430's power and COM volume are controlled using the **C** (power/volume) knob at the top left corner of the unit. Rotating it clockwise will turn unit power on and increase the COM radio volume. After turning the unit on, a *welcome page* will be displayed while the unit performs a self test, followed by the *land data page*.

The *database confirmation page* will appear next, which shows the current database information on the NavData card (with the valid operating dates, cycle number and database type indicated). The database is updated every 28 days, and must be current for approved instrument approach operations. Information on database subscriptions is available inside your GNS 430 package.

To acknowledge the database information, press the **ENT** key.



Once the database has been acknowledged, the *instrument panel self-test* page will appear. To ensure that your GNS 430 and any connected instruments are working properly, check for the following indications on your CDI/HSI, RMI, external annunciators and other connected instruments:

- Course deviation - half left / no flag
- TO/FROM flag - TO
- Bearing to destination - 135°
- Distance to dest. - 10.0 nautical mi.
- All external annunciators (if installed) - on
- Glideslope - half up / no flag
- Time to destination - 4 minutes
- Desired track - 149.5°
- Ground speed - 150 knots



The *instrument panel self-test* page indicates the currently selected OBS course, fuel capacity (CAP), fuel on board (FOB) and fuel flow (FF). The fuel capacity, fuel on board and fuel flow may be manually entered if your installation does not include connection to sensors which automatically provide these figures.

To enter fuel capacity, fuel on board or fuel flow figures (if not provided by sensors):

1. Rotate the large right knob (⌚) to select the "CAP", "FOB" or "FF" field.
2. Rotate the small (⌚) and large (⌚) right knobs to enter the desired figure, then press **ENT**.

TAKEOFF TOUR

Instrument Panel Self-Test



Enter the fuel capacity, fuel on board or fuel flow figures directly onto the appropriate field of the instrument panel self-test page. These figures will automatically be provided if your installation includes connection to external sensors.

TAKEOFF TOUR

Fuel On Board and Checklists



Select "Set Full Fuel?" to set fuel on board (FOB) to full capacity.



Select "Go To Chklist?" to display the checklist page and any available checklists. The GNS 430 can hold up to nine checklists with up to 30 entries in each checklist.

The *instrument panel self-test* page includes selections to set fuel on board (FOB) to full capacity and access the *checklists* page. This allows you to quickly set fuel to full limits and display any checklists you've entered, such as start up or take-off checklists.

To set fuel on board to full (if not provided by sensor):

1. Rotate the large right knob (⊙) to highlight "Set Full Fuel?".
2. Press **ENT** and verify that fuel on board ("FOB") now matches the fuel capacity (CAP) figure. Fuel on board will now be reduced, over time, based on the fuel flow (FF) figure.

To view the checklists page:

1. Rotate the large right knob (⊙) to highlight "Go To Chklist?" and press **ENT**.
2. Rotate the large (⊙) right knob to select the desired checklist, then follow the steps on page 147 to execute each step in the selected checklist.
3. Once you complete the desired checklist(s), press the small right knob (⊙) to return to the checklists page. Press the small right knob (⊙) again to return to normal operation on the satellite status or map pages.

Once you've verified instrument operation with the instrument panel self-test page displayed, press the **ENT** key.

The *satellite status* page will appear as the GNS 430 begins to collect satellite information. An 'Acquiring' status will be displayed on the *satellite status* page, and the signal strength of any satellites received will appear as "bar graph" readings. This is a good indication that you are receiving signals and a position fix will be determined. Following the first-time use of your GNS 430, the time required for a position fix will vary—usually from one to two minutes.

If the unit can only obtain enough satellites for 2D navigation (no altitude), the unit will use the altitude provided by your altitude encoder (if one is connected).

If the GNS 430 has not been operated for a period of six months or more, it may have to 'Search the Sky' to collect new data. This means the unit is acquiring satellite data to establish almanac and satellite orbit information, which can take 5 to 10 minutes. The *satellite status page* will display a 'Search Sky' status, and the message annunciator (MSG), above the **MSG** key, will also flash to alert you of a system message, 'Searching the Sky'.

To view a system message, press **MSG**.




Message Page

The *message page* will appear and display the status or warning information applicable to the receiver's current operating condition.

To return to the previous page after viewing a message, press **MSG** again.

TAKEOFF TOUR

Acquiring Satellites & Viewing Messages




The *satellite status page* shows the ID numbers for the satellites and the relative signal strength of each satellite received (as a "bar graph" reading).

'Search Sky' indicates that satellite almanac data is not available or has expired (if the unit hasn't been used for six months or more). The data will be recollected from the first available satellite.


The 'INTEG' annunciator (bottom left corner of the screen) indicates that satellite coverage is insufficient to pass built-in integrity monitoring tests. In the example above, not enough satellites are being received to determine a position.

TAKEOFF TOUR

Selecting COM and VLOC Frequencies



Satellite status page with cursor active in COM window.



To switch the active and standby frequencies, press the **↕** key. Switching the active and standby frequencies will not remove the cursor from the COM window.


While the GNS 430 is acquiring a position, let's take a minute to dial in the active and standby frequencies you'll be using for the first phase of your flight. The GNS 430's display is divided into separate 'windows' (or screen areas), including a COM window, VLOC window and the GPS window (the right 3/4 of the display).

Active Frequency on top &

Standby on bottom
(highlighted by cursor)

COM Window

VLOC Window



GPS Window

Pushing the small left knob (**⦿**) activates the tuning cursor in the desired frequency window. To select the active frequency, you must first enter the frequency in the standby field, and use the **↕** (or **⦿**) key to move it to the active field.

To change the standby communication frequency:

1. Press the small left knob (**⦿**) if needed, to move the tuning cursor to the COM window.
2. Rotate the large left knob (**⦿**) to select the MHz, and the small left knob (**⦿**) to select the kHz of the desired frequency.

To place the standby communication frequency in the active field, press **↕**.


Once you've entered the active frequency, simply repeat steps 1 and 2, above, to enter the standby frequency. After both communication frequencies have been entered, you may elect to keep the COM window 'hot' by leaving the cursor on the standby frequency, or move the cursor to the VLOC window by pressing the small left knob (**⦿**). NOTE: When selecting VLOC frequencies, the tuning cursor will automatically return to the COM window after 30 seconds of inactivity.

To change the standby VLOC frequency:

1. Press the small left knob (PUSH IN), if needed, to activate the tuning cursor in the VLOC window.
2. Rotate the large left knob (PUSH IN) to select the MHz, and the small left knob (PUSH IN) to select the kHz of the desired frequency.

To place the standby frequency in the active field, press **V**.

After the GNS 430 acquires satellites and computes a position, the *map page* will appear automatically.



The *map page* displays your present position (using an airplane symbol) relative to nearby airports, VORs, NDBs, intersections, user waypoints and airspace boundaries—and your route displayed as a solid line. Data fields for destination waypoint (WPT), distance to waypoint (DIS), desired track (DTK) and ground speed (GS) appear on the right hand side of the display. These fields are user selectable (see page 37 for more information) to allow you to configure the unit to your own preferences. Available settings include: altitude, bearing, enroute safe altitude, estimated time of arrival, minimum safe altitude, and ground track. See Section 10 for definitions of these navigation terms.

TAKEOFF TOUR

Map Page



The map page combines a moving map display and navigation data for complete situational awareness. Map setup pages are provided to designate the maximum scale at which each map feature will appear. These settings provide an automatic decluttering of the map (based upon your preferences) as you adjust the scale.

While viewing the map page, you can quickly declutter and remove many of the background map details by pressing the **CLR** key (repeatedly) until the desired detail is depicted.

To change the map scale, press the **▽** or **△** side of the **▽ RNG △** key.

TAKEOFF TOUR

NAV Pages & Page Groups



The bottom right corner of the screen indicates which page group is currently being displayed (e.g., NAV or NRST), the number of screens available within that group (indicated by square icons) and the placement of the current screen within that group (indicated by a highlighted square icon). To select a different page within the group, rotate the small right knob (PUSH knob).

* Seven NAV Pages are available when the GNS 430 installation includes connection to traffic and/or weather information sources. See 400 Series Pilot's Guide Addendum, part number 190-00140-10.

The map page is one of six pages available under the NAV group*:

- Default NAV page
- NAVCOM page
- Satellite status page
- Map page
- Position page
- Vertical navigation page

To select the desired NAV page, rotate the small right knob (PUSH knob) until the desired page is displayed.

If you are currently viewing a page which is not part of the NAV group, you can quickly return to the NAV group using the CLR key.

To select the NAV group and display the default NAV page, press and hold CLR.


MAIN PAGE GROUPS

NAV	WPT	AUX	NRST
6 available pages* (see list above)	10 available pages (see list on pg. 94)	4 available pages (see list on pg. 131)	8 available pages (see list on pg. 16)

In addition to the NAV group of pages, additional groups of pages are available for waypoint information (WPT), auxiliary (AUX) functions such as flight planning or unit settings, and listings for nearest (NRST) airports or other facilities.

To select the desired page group, rotate the large right knob (PUSH knob) until a page from the desired group is displayed.

To select the desired page within the group, rotate the small right knob (PUSH knob) until the desired page is displayed.




Selection of any main page is performed using the large (PUSH CRSR) and small (PUSH CRSR) right knobs. The large right knob (PUSH CRSR) selects the page group: NAV, WPT, AUX or NRST. The small right knob (PUSH CRSR) selects the desired page within a group. To quickly select the default NAV page, press and hold CLR.

TAKEOFF TOUR

Direct-To Navigation



Confirm the selected direct-to destination by highlighting "Activate?" and pressing **ENT**.



Once a direct-to destination is selected, press and hold **CLR** to display the default NAV page.

Destination
Waypoint
Identifier Field




Select Direct-To Waypoint Page

"Activate?"
Function Field

The GNS 430 can use direct point-to-point navigation to guide you from takeoff to touchdown, even in the IFR environment. Once a destination is selected, the unit will provide speed, course and distance data based upon a direct course from your present position to your destination. A destination can be selected from any page with the **-B>** (direct-to) key.

To select a direct-to destination:

1. Press the **-B>** key. The select direct-to waypoint page will appear with the destination field highlighted.
2. Rotate the small right knob (PUSH) to enter the first letter of the destination waypoint identifier. The destination waypoint may be an airport, VOR, NDB, intersection or user waypoint, as long as it is in the database or stored in memory as a user waypoint.
3. Rotate the large right knob (PUSH) to the right to move the cursor to the next character position.
4. Repeat steps 2 and 3 to spell out the rest of the waypoint identifier.
5. Press **ENT** to confirm the identifier. The "Activate?" function field will be highlighted.
6. Press **ENT** to activate a direct-to course to the selected destination.



During most flights, the *default NAV*, *map* and *NAVCOM* pages will be the primary pages used for navigation. The *default NAV page* displays a graphic course deviation indicator (CDI), the active leg of your flight plan (as defined by the current “from” and “to” waypoints), and six user-selectable data fields. The default settings for these fields are distance to waypoint (DIS), desired track (DTK), bearing to waypoint (BRG), ground speed (GS), ground track (TRK) and estimated time en route (ETE). See Section 10 for definitions of these navigation terms. The *default NAV page* is selected using the steps described on page 10.

From the *default NAV page*, simply rotate the small right knob (⌚) to display the *map page* (see page 9) and again to display the *NAVCOM page*. The *NAVCOM page* displays the available frequencies (communications and navigation) for the departure airport, any en route airports which are included in your flight plan, and the final destination airport. When using the direct-to function, frequencies will be listed for the airport nearest to your starting position and the destination airport.

To display the frequency list for the desired flight plan or direct-to airport:

1. Push the small right knob (⌚) to activate the cursor on the airport identifier field (in the GPS window).

{continued}

TAKEOFF TOUR

Default NAV Page



The data fields on the default NAV page may be custom-tailored to your preferences. A menu selection is provided to “Change Fields?”



The large right knob (⌚) is used to select the data field you wish to change. Then use the small right knob (⌚) to display a list of data options and select the desired data item.

TAKEOFF TOUR


NAVCOM Page



The navigation/communications (NAVCOM) page provides a complete list of airport frequencies at your departure, en route and arrival airports. To place a frequency from this list on standby, highlight the desired frequency and press **ENT**.

To display frequencies for a different airport along your flight plan, press the small right knob (PUSH CRSEL) to highlight the airport identifier field. Rotate the small right knob (PUSH CRSEL) to display the list of airports within your flight plan. Continue rotating the small right knob (PUSH CRSEL) to select the desired airport and press **ENT**.

2. Rotate the small right knob (PUSH CRSEL) to display the list of airports (departure, arrival and en route) for your flight plan or direct-to. Continue to rotate the small right knob (PUSH CRSEL) until the desired airport is selected.
3. Press **ENT** to display the frequency list for the selected airport.



A frequency listed on the NAVCOM page can be quickly transferred to the standby field of the COM or VLOC windows. This time saving process prevents having to “re-key” a frequency already displayed elsewhere on the screen.

To select a communication or navigation frequency:

1. Push the small right knob (PUSH CRSEL) to activate the cursor in the GPS window.
2. Rotate the large right knob (PUSH CRSEL) to select the desired frequency from the list.
3. Press **ENT** to transfer the selected frequency to the standby field in the COM or VLOC window. COM frequencies will automatically go to the standby field of the COM window and navigation frequencies will automatically go to the standby field of the VLOC window, regardless of which window is currently highlighted by the cursor.
4. To activate the selected frequency, press the **C** or **V** key.

Once the direct-to or flight plan is confirmed, the whole range of instrument procedures is available to you. Departures (SIDs), arrivals (STARs), non-precision and precision approaches are stored within the NavData card and available using the **PROC** (procedures) key.

To display the procedures page, press **PROC**.

The steps required to select and activate an approach, departure or arrival are identical. In this introductory section, we'll show examples of the steps required to select an approach, but keep in mind the same process also applies to departures and arrivals.


To select an approach, departure or arrival:

1. Rotate the small right knob (PUSH CRN) to select the desired option ("Select Approach?", "Select Arrival?" or "Select Departure?") from the procedures page.
2. Press **ENT** to display a list of available procedures for the arrival (when using approaches or STARs) or departure (when using SIDs) airport.
3. Rotate the small right knob (PUSH CRN) to select the desired procedure and press **ENT**.
4. For approaches, a window appears to select the desired initial approach fix (IAF) or provide a "vectors" option to select just the final course segment of the approach. Rotate the small right knob (PUSH CRN) to select the desired option and press **ENT**. (The "vectors" option extends the final inbound course beyond the final approach fix, allowing you to intercept the final course segment beyond its normal limits.)
5. For departures and arrivals, a window appears to select the desired transition. Rotate the small right knob (PUSH CRN) to select the desired option and press **ENT**.


In your flight plan or direct-to, the departure or arrival airport is replaced with the sequence of waypoints contained within the selected procedure.

TAKEOFF TOUR

IFR Procedures



Press the **PROC** key to display the procedures page. Rotate the large right knob (PUSH CRN) to select the desired option.



A window will appear to select the desired procedure. Use the large right knob (PUSH CRN) to make your selection.

TAKEOFF TOUR

Nearest Airport Emergency Search

COM	NEAREST AIRPORT			
118.300	APT	BRG	DIS	APR
135.325	KIXD	327° _M	5.3 _N _M	ILS
	twr	118.300	rwyl	7300'
VLOC	K34	296° _M	6.5 _N _M	NDB
113.00	uni	122.800	rwyl	2900'
115.90	KOJC	035° _M	7.3 _N _M	LOC
ENR	twr	126.000	rwyl	4000'
GPS	HSG	NRST	0000000	

To display a list of nearby airports, rotate the large right knob (⌚) to select the NRST page group and (if needed) the small right knob (⌚) to select the nearest airport page.

COM	NEAREST AIRPORT			
118.300	APT	BRG	DIS	APR
135.325	KOJC	035° _M	7.3 _N _M	LOC
	twr	126.000	rwyl	4000'
VLOC	51K	344° _M	11.0 _N _M	VFR
113.00	uni	122.700	rwyl	2400'
115.90	53K	065° _M	11.4 _N _M	VFR
ENR	mul	122.900	rwyl	1800'
GPS	HSG	NRST	0000000	

To scroll through the list, press the small right knob (⌚), then rotate the large right knob (⌚).

From page 10 you may recall that one of the main page groups, NRST, provides listings for nearest airports or other facilities. The NRST group provides detailed information on the nine nearest airports, VORs, NDBs, intersections and user-created waypoints within 200 nautical miles of your current position. In addition, pages are also provided to display the five nearest center (ARTCC/FIR) and Flight Service Station (FSS) points of communication, plus alert you to any special-use or controlled airspace you may be in or near.

To display the NRST pages:

1. If necessary, press the small right knob (⌚) to remove the cursor from the page.
2. Rotate the large right knob (⌚) to select the NRST page group, as indicated by "NRST" appearing in the lower right corner of the screen (see page 10).
3. Rotate the small right knob (⌚) to select the desired NRST page.

The nearest airport page (shown at left) is one of eight pages available under the NRST group:

- Nearest airport page
- Nearest intersection page
- Nearest NDB page
- Nearest VOR page
- Nearest user waypoints page
- Nearest ARTCC page
- Nearest FSS page
- Nearest airspace page

You may examine both the communication frequencies and runway information directly from the nearest airport page. As discussed earlier for the NAVCOM page (see page 14), you may also place any displayed frequency into the standby COM or VLOC field by highlighting the frequency with the cursor and pressing **ENT**.

To view additional information for a nearby airport:

1. Press the small right knob (PUSH CURS) to activate the cursor.
2. Rotate the large right knob (PUSH CURS) to select the desired airport from the list.
3. Press **ENT** to display waypoint (WPT) information pages for the selected airport.
4. To display runway and frequency information, press (PUSH CURS) to remove the cursor and rotate the small right knob (PUSH CURS) to display the desired information page.

The *nearest airport page* may be used in conjunction with the direct-to (**B>**) key to quickly set a course to a nearby facility in an in-flight emergency. Selecting a nearby airport as a direct-to destination will override your flight plan or cancel a previously selected direct-to destination. (You'll still have the option of returning to your flight plan by cancelling the direct-to. See page 53.)

To select a nearby airport as a direct-to destination:

From the nearest airport page...

1. Press the small right knob (PUSH CURS) to activate the cursor.
2. Rotate the large right knob (PUSH CURS) to select the desired airport from the list.
3. Press **B>**, **ENT** and **ENT** (again) to navigate to the nearby airport.

From an airport information page...

1. Press **B>**, **ENT** and **ENT** (again) to navigate to the nearby airport.

TAKEOFF TOUR

Nearest Airports: Additional Information and Direct-to

COM 118.300	APT KOJC Public Done?
135.325	FACILITY & CITY NAME JOHNSON CO EXECUTIVE OLATHE KS
VLOC 113.00	POSITION ELEV FUEL N 38°50.86' 1100' Avgas
115.90	W094°44.25' Jet
ENR	APR LOC RADAR Yes ARSPC
GPS	HSG HPT 0000000000

Additional information for a nearby airport is available by highlighting an identifier on the list and pressing **ENT**.

COM 118.300	SELECT → WAYPOINT
135.325	KOJC N CEN USA
VLOC 113.00	JOHNSON CO EXECUTIVE
115.90	OLATHE KS
ENR	FPL KIXO NRST KIXO
GPS	N 38°50.86' CRS 035°M
	W094°44.25' Activate?
	HSG DRCT


To select a nearby airport as a new destination, highlight its identifier, press **B>**, **ENT** and **ENT** (again).

TAKEOFF TOUR

Special-use and Controlled Airspace



When an airspace alert occurs, the message (MSG) annunciator will flash. Press **MSG** to view the alert message.



To view additional information about the airspace, select the nearest airspace page. Detailed information is available by highlighting the airspace name and pressing **ENT**.

The last page in the NRST group, the *nearest airspace page*, provides information for up to nine controlled or special-use airspaces near or in your flight path. Airspace information appears on this page based upon the same criteria used for airspace alert messages. Nearby airspace information and airspace alert messages are provided according to the following conditions:

- If your projected course will take you inside an airspace within the next ten minutes, the message “**Airspace ahead -- less than 10 minutes**” will appear.
- If you are within two nautical miles of an airspace and your current course will take you inside, the message “**Airspace near and ahead**” will appear.
- If you are within two nautical miles of an airspace and your current course will **not** take you inside, the message “**Near airspace less than 2nm**” will appear.
- If you have entered an airspace, the message “**Inside Airspace**” will appear.

By default, airspace alert messages are turned off. When turned on, the message (MSG) annunciator located directly above the **MSG** key will flash to alert you to the airspace message. (See page 154 for information on enabling airspace alert messages.)

To view an airspace alert message:

1. Press the **MSG** key. The message page appears with the alert message.
2. Press **MSG** again to return to the previous display.

Note that the airspace alerts are based upon three-dimensional data (latitude, longitude and altitude) to avoid nuisance alerts. The alert boundaries for controlled airspace are also sectorized to provide complete information on any nearby airspace. Additional information about a nearby airspace—such as controlling agency, frequency and floor/ceiling limits—is available from the *nearest airspace page* (see page 128 and illustrations shown at left).

The GNS 430 lets you create up to 20 flight plans, with up to thirty-one waypoints in each flight plan. Flight plans are created, edited and activated using the **FPL** key. The FPL page group includes two pages: the *active flight plan page* and the *flight plan catalog*. The *active flight plan page* provides information and editing features for the flight plan currently in use (referred to as “flight plan 00”). The *flight plan catalog* serves as the main page for creating new flight plans, as well as editing or activating previously created flight plans.

Since using flight plans is arguably one of the more complex features of the GNS 430, we’ll only discuss it briefly here — focusing on creating a new flight plan and activating it to use for navigation. After reading through this brief introduction, answers to additional questions you may have about flight plans can be found in the reference section, starting on page 54.

To create a new flight plan:

1. Press the **FPL** key and rotate the small right knob (PUSH) to select the flight plan catalog.
2. Press the **MENU** key to display the flight plan catalog options.
3. Rotate the large right knob (ENT) to select “Create New Flight Plan?” and press **ENT**.
4. The cursor will appear on the first waypoint identifier field (located directly below “WAY-POINT”). Use the large (ENT) and small (PUSH) right knobs to enter the identifier of the first waypoint in the flight plan. (The small knob is used to select the desired letter or number and the large knob is used to move to the next character space.)
5. Press **ENT** once the identifier has been selected. The cursor will move to the next blank waypoint identifier field.
6. Repeat steps 4 and 5, above, until all waypoints for the flight plan have been entered.

TAKEOFF TOUR

Flight Plans

ACTIVE FLIGHT PLAN			
00 K34 / 4M1			
WAYPOINT	DTK	DIS	
K34			
BUM	141°M	38.5	n.m.
KNVD	154°M	26.6	n.m.
4M1	156°M	94.0	n.m.

Left side of screen: COM 118.300, 135.325, VLOC 113.00, 115.90, TERM, GPS MSG FPL 00

Active flight plan page with flight plan currently in use.

PAGE MENU	
Activate Flight Plan?	
Invert & Activate FPL?	
Create New Flight Plan?	
Crossfill?	
Copy Flight Plan?	
Delete Flight Plan?	

Left side of screen: COM 128.450, 121.600, VLOC 110.70, 113.00, TERM, GPS MSG FPL 00

To create a new flight plan, select “Create New Flight Plan?” from the flight plan catalog options.

TAKEOFF TOUR

Flight Plans and Additional Reading



Enter the identifier for each airport and/or navaid into the flight plan in the same sequence you wish to fly.



Select "Activate Flight Plan?" from the page menu to begin using the new flight plan.

Once the flight plan is created, it may be activated from an options window. Activating the flight plan will place it into "flight plan 00" (a copy of it will still reside in the original catalog location) and replaces any flight plan which currently exists in "flight plan 00."

To activate the new flight plan:

1. Press the **MENU** key to display the flight plan catalog options.
2. Rotate the small right knob (Push Knob) to select "Activate Flight Plan?" and press **ENT**.

This Takeoff Tour is intended to provide a brief introduction of the GNS 430's major features. The Reference section of this manual describes these features, and others, in additional detail. Use the Reference section, as needed, to learn or review the details regarding a particular feature. The Index (beginning on page 187) may be used to quickly locate the information you want within the reference section.

Now that you're familiar with the basics, some suggested reading within the Reference section includes:

- Flight plan features - see page 54
- Waypoint information pages (database information) - see page 94
- IFR procedures - see page 66
- Unit settings (configuring the unit to your preferences) - see page 135

If you're unable to locate the information you need, we're here to help! GARMIN's Customer Service staff is available during normal business hours (U.S. Central time zone) at the phone and fax numbers listed on page iv. You can also reach us by mail (see page iv) or at our web site address: www.garmin.com.

Section 1

Communicating with the GNS 430

The GNS 430 features a digitally-tuned VHF COM radio that provides a seamless transition from communication to navigation, bringing the two most important functions in flying together in one panel-mounted unit. The GNS 430's COM radio operates in the aviation voice band, from 118.000 to 136.975 MHz, in 25 kHz steps (default). For European operations, a COM radio configuration to allow for 8.33 kHz steps is also provided (see pages 160-161).

Volume

COM radio volume is adjusted using the  knob. Rotate the  knob clockwise to increase volume, or counterclockwise to decrease volume.

Squelch

The COM radio features an automatic squelch, providing maximum sensitivity to weaker signals while rejecting many localized noise sources. You may wish to override this automatic squelch function when listening to a distant station or when setting the desired volume level. The  knob allows you to disable the automatic squelch and keep the COM audio open continuously.

To override the automatic squelch, press the  knob momentarily. Press  again to return to automatic squelch operation.



Press the  knob momentarily to override the automatic squelch. Note the "RX" receive indication when receiving a station.



"TX" appears at the upper right corner of the screen while transmitting.

1

COM Tuning Cursor Active/Standby Freqs



Tuning cursor in the COM window. Use the small (⊖) and large (⊕) left knobs to dial in the desired standby frequency.



Once the standby frequency is selected, use the (C) (flip-flop) key to make the frequency active for transmit and receive operations.

COM Window and Tuning

Communication frequencies are selected with the tuning cursor in the *standby* COM frequency field, and using the small (⊖) and large (⊕) left knobs to dial in the desired frequency. The standby frequency always appears below the *active* frequency. The active frequency is the frequency currently in use for transmit and receive operations.

A frequency may also be quickly selected from the database by simply highlighting the desired frequency on any of the main pages and pressing the (ENT) key. This process is referred to as *auto-tuning*. Once a frequency is selected in the standby field, it may be transferred to the active frequency by pressing the (C) key.

While receiving a station, an “RX” indication appears in the upper right corner of the COM window — to the immediate right of “COM”. A “TX” indication appears at this location while you are transmitting.

NOTE

The tuning cursor will normally appear in the COM window, unless placed in the VLOC window by pressing (VLOC). When the tuning cursor is in the VLOC window, it will automatically return to the COM window after 30 seconds of inactivity.

The active frequency in either window cannot be accessed directly—only the standby frequency will be highlighted by the tuning cursor.

To select a COM frequency:

1. If the tuning cursor is not currently in the COM window, press the small left knob (Ⓢ) momentarily.
2. Rotate the large left knob (Ⓢ) to select the desired megahertz (MHz) value. For example, the "118" portion of the frequency "118.300".
3. Rotate the small left knob (Ⓢ) to select the desired kilohertz (kHz) value. For example, the ".300" portion of the frequency "118.300".

To make the standby frequency the active frequency, press the **C** (flip flop) key.

The tuning cursor will remain in the *COM window*. If you wish to select a VOR/localizer/ILS frequency, press the small left knob (Ⓢ) momentarily to place the cursor in the *VLOC window*. Additional instructions for VOR/localizer/ILS operations are available in Sections 5 and 8 (beginning on pages 66 and 131).

Auto-Tuning

The GNS 430's auto-tune feature allows you to quickly select any database frequency in the GPS window as your standby frequency. Any COM frequency displayed in the GPS window can be transferred to the standby COM frequency field, with a minimum of keystrokes required. The following are some examples of selecting COM frequencies from some of the main GPS pages.

To select a COM frequency for a nearby airport:

1. Select the nearest airport page from the NRST page group. (See page 119, or press and hold **CLR**, then rotate the large right knob, Ⓢ, until the nearest pages appears. Finally, if necessary, rotate the small right knob, Ⓢ, to display the nearest airport page.)

{continued}

COM Auto-Tuning from Nearest Airport Page

1



Cursor in VLOC window allows for VOR and ILS operations. See Section 8, starting on page 131.



Nearest airport page with common traffic advisory frequency (CTAF) for the closest airport highlighted.

1

Auto-Tuning FSS, Center or Flight Plan



From the nearest airport page, select the desired airport to show a more detailed listing of frequencies for that airport.



Use the nearest ARTCC page to quickly retrieve the frequency(s) for the nearest center (ARTCC) facility.

- Press the small right knob (PUSH) momentarily to place the cursor on the airport identifier field of the first airport in the list. If you wish to select another airport, rotate the large right knob (R) to highlight the desired airport.
- The nearest airport page displays the *common traffic advisory frequency* (CTAF) for each listed airport. To select this frequency, rotate the large right knob (R) to highlight the desired airport's CTAF frequency and press **ENT** to place the frequency in the standby field of the COM window.
- To display the entire list of frequencies for a nearby airport and select from that list, start with the desired airport highlighted on the nearest airport page (as described in step 3 above), then press **ENT**. Now press the small right knob (PUSH) momentarily to remove the cursor and rotate the small right knob (PUSH) to display the frequency list. Press the small right knob (PUSH) momentarily to reactivate the cursor and rotate the large right knob (R) to highlight the desired frequency. Press **ENT** to place the highlighted frequency in the standby COM window field.

To select a COM frequency for a nearby flight service station (FSS) or center (ARTCC):

- Select the nearest center or flight service page from the NRST page group. (See page 119, or rotate the large right knob, (R), until the NRST pages appear. Then, if necessary, rotate the small right knob, (PUSH), to display the desired NRST page.)
- Press the small right knob (PUSH) momentarily to place the cursor on the page.
- Rotate the large right knob (R) to highlight the FSS/ARTCC frequency and press **ENT** to place the frequency in the standby field of the COM window.

To select a COM frequency for any airport in your flight plan:

1. Select the NAVCOM page from the NAV page group. (See page 27, or press and hold **CLR**, then rotate the small right knob, , until the NAVCOM page appears.)
2. Press the small right knob () to place the cursor on the airport identifier field. To the left of this field appears *Departure, Enroute* or *Arrival* — depending on the placement of the displayed airport within your flight plan.
3. Rotate the small right knob () to display a window listing the airports in your flight plan. Continue rotating the small right knob () to select the desired airport.
4. Press **ENT** to return to the NAVCOM page with the frequencies for the selected airport.
5. Rotate the large right knob () to highlight the desired frequency.
6. Press **ENT** to place the highlighted frequency in the standby COM window field.

To select a COM frequency for any airport in the database:


1. Select the airport frequencies page from the WPT page group. (See page 94, or rotate the large right knob, , to select the WPT page group. Then rotate the small right knob, , until the airport frequencies page appears.)
2. Press the small right knob () to place the cursor on the airport identifier field.
3. Use the small () and large () right knobs to enter the identifier of the desired airport. Press **ENT** when finished.
4. Rotate the large right knob () to highlight the desired frequency.
5. Press **ENT** to place the highlighted frequency in the standby COM window field.

COM Auto-Tuning from Flight Plan/Database

1



The NAVCOM page provides a frequency list for all the airports (departure, en route and arrival) along your active flight plan.



Use the airport frequencies page to retrieve a frequency list for ANY airport in the Jeppesen NavData database.

1

Emergency Channel Stuck Mic



Press and hold the  (flip-flop) key for two seconds to activate the 121.500 MHz emergency frequency.



A “COM push-to-talk key stuck” message appears to warn you of a stuck microphone. Transmitting is disabled after 35 seconds of continuous broadcasting.

Emergency Channel

The GNS 430’s emergency channel select provides a quick method of selecting 121.500 MHz as the active frequency in the event of an in-flight emergency. The emergency channel select is available whenever the unit is on, regardless of GPS or cursor status, or loss of the display.

To quickly tune and activate 121.500, press and hold  for approximately two seconds.

Stuck Microphone

As mentioned earlier, whenever the GNS 430 is transmitting, a ‘TX’ indication will appear in the COM window. If the microphone is stuck or accidentally left in the keyed position, or continues to transmit after the key is released, the COM transmitter will automatically timeout (or cease transmitting) after 35 seconds of continuous broadcasting. You’ll also receive a “COM push-to-talk key stuck” message as long as the stuck condition exists.

Section 2 NAV Pages

Main Page Groups

The GNS 430's main pages are divided into groups: NAV, WPT, AUX and NRST. While viewing any of these pages, selection of another page is a simple selection process using the small (Ⓢ) and large (Ⓛ) right knobs.

NAV	WPT	AUX	NRST
6 available pages (see list below)	10 available pages (see list on pg. 94)	4 available pages (see list on pg. 135)	8 available pages (see list on pg. 119)

To select the desired page group, rotate the large right knob (Ⓛ) until a page from the desired group is displayed.

To select the desired page within the group, rotate the small right knob (Ⓢ) until the desired page is displayed.

NAV Page Group



The NAV page group includes six pages. While viewing any NAV page, rotate the small right knob (Ⓢ) to select a different NAV page. You may find this selection process convenient to cycle between the *default* NAV and *map* pages—two of the most frequently used pages. Other pages are provided to list frequencies for your flight plan, show your current position, display current satellite reception, and make vertical navigation settings.



The bottom right corner of the screen indicates which page group is currently being displayed (e.g., NAV or NRST), the number of screens available within that group (indicated by square icons) and the placement of the current screen within that group (indicated by a highlighted square icon). To select a different page within the group, rotate the small right knob (Ⓢ).



This part of the screen is also used to display the GNS 430's turn advisories (e.g., "Turn to 230°") and waypoint alerts (e.g., "Next DTK 230°") during flight plan and approach operations. See Section 5 for more information.

2


NAV PAGES

Default NAV Page

The following symbols are used—on the default NAV page directly below the CDI—to depict the “active leg” of a flight plan or direct-to:

-  Direct-To a Waypoint
-  Course to a Waypoint, or Desired Course between Two Waypoints
-  Left Procedure Turn
-  Right Procedure Turn
-  Vectors-To-Final
-  DME Arc to the left
-  DME Arc to the right
-  Left-hand Holding Pattern
-  Right-hand Holding Pattern

Default NAV Page



The first NAV page is the *default NAV page*. This page may be quickly selected from ANY page by using the **CLR** key.

To select the NAV group and display the default NAV page, press and hold **CLR**.

The *default NAV page* displays a graphic course deviation indicator (CDI) across the top of the page. Unlike the angular limits used on a mechanical CDI coupled to a VOR or ILS receiver, full scale limits for this CDI are defined by a GPS-derived distance (0.3, 1.0 or 5.0 nm), as indicated at both ends of the CDI. By default, the CDI scale will automatically adjust to the desired limits based upon the current phase of flight: en route, terminal area or approach. You may also manually select the desired scale setting as outlined on pages 153 and 155.

The graphic CDI shows your position at the center of the indicator, relative to the desired course (the moving course deviation needle). As with a traditional mechanical CDI, when you're off course simply steer toward the needle. The TO/FROM arrow in the center of the scale indicates whether you are heading to (an up arrow) the waypoint or if you have passed the waypoint (a down arrow).

NOTE

The GNS 430 always navigates TO a waypoint unless the OBS switch is set (preventing automatic waypoint sequencing), or you have passed the last waypoint in your flight plan.

Directly below the CDI appears the active leg of your flight plan, or the direct-to destination when using the **-B>** key. This will automatically sequence to the next leg of your flight plan as you reach each interim waypoint. If no flight plan or direct-to destination has been selected, the destination field will remain blank.

Selecting Desired On-Screen Data

At the bottom of the *default NAV page* you'll find six user-definable fields which display the data you'll need as your flight progresses. By default these fields display: distance to destination (DIS), desired track (DTK), bearing to destination (BRG), ground speed (GS), ground track (TRK) and estimated time en route (ETE). However, each of these fields can be custom-tailored to your preferences by selecting a different data item. Available data items include:

- Bearing to destination (BRG)
- Distance to destination (DIS)
- En route safe altitude (ESA)
- Estimate time en route (ETE)
- Minimum safe altitude (MSA)
- Ground track (TRK)
- Cross track error (XTK)
- Course to steer (CTS)
- Desired track (DTK)
- Estimated time of arrival (ETA)
- Ground speed (GS)
- Track angle error (TKE)
- Vertical speed required (VSR)

If no flight plan or direct-to destination has been selected only speed, track, altitude and minimum safe altitude data may be displayed. All other data types will appear as blank lines—on the *default NAV page*—until a destination is selected.

To select a different data item for any data field:


1. Starting with the default NAV page, press the **MENU** key to display an options menu.
2. The "Change Fields?" option is already highlighted, so press **ENT** to select this option.
3. Use the large right knob (⦿) to highlight the data field you wish to change.
4. Rotate the small right knob (⦿) to display the list of available data items. Continue rotating the small right knob (⦿) to select the desired data item from the list.

{continued}

NAV PAGES

Default NAV Page

2



2

NAV PAGES

Map Page



5. Press **ENT** to select the desired data item and return to the default NAV page.

6. Press the small right knob (**PUSH ENTER**) momentarily to remove the cursor from the page.

Restoring Factory Settings

You can also quickly return all data field settings to their original factory settings.


To restore all six data fields to factory default settings:

1. Starting with the default NAV page, press the **MENU** key to display an options menu.
2. Rotate the large right knob (**⊖**) to highlight the "Restore Defaults?" option and press **ENT**.

Dual Unit Considerations

A "Crossfill?" option is also provided for the *default NAV page*. This option allows you to transfer a direct-to destination or flight plan to a second 400-series GARMIN unit. See page 58 and 142 for additional details on using the "Crossfill?" option.

Map Page



The second NAV page is the *map page*, which displays your present position using an airplane symbol, along with nearby airports, nav aids, user-defined waypoints, airspace boundaries, lakes, rivers, highways and cities.

NOTE

If the GNS 430 is unable to determine a GPS position, the present position (airplane) symbol will not appear on the map page.

Different symbols are used to distinguish between waypoint types. The identifiers for any on-screen waypoints can also be displayed. (By default the identifiers are enabled.) Special-use and controlled airspace boundaries appear on the map, showing the individual sectors in the case of Class B or Class C airspace. The following symbols are used to depict the various airports and navaids on the *map page*:

	Airport with hard surface runway(s); Primary runway shown		
	Airport with soft surface runway(s) only		
	Private Airfield		Intersection
	VOR		VORTAC
	VOR/DME		TACAN
	DME		NDB
	Localizer		Locator Outer Marker

The map display can be set to 23 different scale settings from 500 feet to 2000 nautical miles (statute and metric units are also available). The scale is indicated in the lower left-hand corner of the map display, and represents the top-to-bottom distance covered by the map display.

To select a map scale:

1. Press the up arrow side of the  key to zoom out to a larger map area.
2. Press the down arrow side of the  key to zoom in to a smaller map area and more detail.

NAV PAGES

Map Page


2



2

NAV PAGES

Map Page



The **CLR** key allows you to quickly declutter the map display, providing four levels of map detail. Note the “-1” and “-2” (“-3” is also provided) suffix designations above, indicating each successive declutter level.

An autozoom feature is available which will automatically adjust from an en route scale of 2000 through each lower scale, stopping at a scale of 1.0 as you approach your destination waypoint. The autozoom feature is turned on/off from the map setup page described on page 36.

The *map page* also displays a background map showing lakes, rivers, coastlines, highways, railways and towns. When a map scale is selected below the lower limit at which the map detail was originally created, an “overzoom” indication will appear on the map display, below the scale reading. “Overzoom” indicates that the detail at this scale may not accurately represent actual conditions. If you continue to zoom in to lower scale settings, “overzoom” will be replaced with “no map” and the geographic detail is removed from the map display (but, the airport and navaid detail will remain).

The “Setup Map?” option (described on page 35) allows you to define the maximum scale at which each map feature will appear. This provides you with complete control to minimize screen clutter. You can also quickly remove items from the map using the **CLR** key.

To quickly declutter the map display, press the **CLR** key momentarily (as often as needed) to select the desired amount of map detail.

The right-hand side of the map page includes four user-selectable data fields. By default, the displayed data is: destination waypoint name (WPT), desired track (DTK), distance to destination waypoint (DIS) and ground speed (GS). Any of these data fields may be changed to display a different data type, as outlined on page 37. You may also remove the four data fields from the map to show a larger map image, as described on page 37.

Map Panning

Another *map page* function is panning, which allows you to move the map beyond its current limits without adjusting the map scale. When you select the panning function — by pressing the small right knob (PUSH CURSR) — a target pointer will flash on the map display. A window will also appear at the top of the map display showing the latitude/longitude position of the pointer, plus the bearing and distance to the pointer from your present position.

To select the panning function and pan the map display:

- 1a. Press the small right knob (PUSH CURSR) to activate the panning target pointer.
- 2a. Rotate the small right knob (PUSH CURSR) to move up (rotate clockwise) or down (counterclockwise).
3. Rotate the large right knob (PUSH) to move right (rotate clockwise) or left (counterclockwise).
4. To cancel the panning function and return to your present position, press the small right knob (PUSH CURSR).

When the target pointer is placed on an object, the name of that object will be highlighted (even if the name wasn't originally displayed on the map). This feature applies to airports, nav aids, user-created waypoints, roads, lakes, rivers — pretty much everything displayed on the map except route lines.

When an airport, nav aid, or user waypoint is selected on the map display, you can review information about the waypoint or designate the waypoint as your direct-to destination.


To review information for an on-screen airport, nav aid or user waypoint:

- 1b. Use the panning function (as described above) to place the target pointer on a waypoint.
- 2b. Press **ENT** to display the waypoint information page(s) for the selected waypoint.
3. Press **CLR** to exit the information page(s).

NAV PAGES

Map Page

2



2

NAV PAGES

Map Page



1b



3b

**Map Direct-To**

To designate an on-screen airport, navaid or user waypoint as your direct-to destination:

- 1a. Use the panning function (see previous page) to place the target pointer on a waypoint.
2. Press **[B-]** to display the select direct-to waypoint page, with the selected waypoint already listed.
- 3a. Press **[ENT]** twice to confirm the selection and begin navigating to the waypoint.

The direct-to function can be used anywhere on the map. If nothing currently exists at the crosshair position, a new waypoint (called “+MAP”; shown at left) will be created at the target pointer location before the direct-to is initiated.

Airspace Information on the Map

When a special-use or controlled airspace boundary appears on the map display, you can quickly retrieve information — such as floor/ceiling limits and controlling agency — directly from the map.

To view airspace information for an on-screen special-use or controlled airspace:

- 1b. Use the panning function (see previous page) to place the target pointer on an open area within the boundaries of an airspace. If the area is congested and it is difficult to select an open area, you may need to zoom in or press **[CLR]** to make the selection easier.
2. Press **[ENT]** to display an options menu.
- 3b. “Review Airspace?” should already be highlighted, if not select it with the small right knob (**[PUSH CRSEL]**). Press **[ENT]** to display the airspace information page for the selected airspace.
4. To display the com frequency(s) for the controlling agency, rotate the large right knob (**[CRSEL]**) to highlight “Frequencies?” and press **[ENT]**. Press **[CLR]** to return to the airspace information page.
5. Press **[CLR]** to exit the airspace information page.

Many of the GNS 430's functions are menu driven. Each of the main pages has an options menu, allowing you to custom tailor the corresponding page to your preferences and/or select special features which specifically relate to that page. A *map page options menu* provides additional settings to customize the *map page* and additional features related specifically to the *map page*.

To display the map page options menu, press **MENU** (with the map page displayed).

The following options are available: "Setup Map?", "Measure Dist?", "Data Fields Off?", "Change Fields?" and "Restore Defaults?".


Map Setup

"Setup Map?" allows you to configure the map display to your preferences, including map orientation, land data enable/disable, Jeppesen data enable/disable, automatic zoom, airspace boundaries, and text size. The following table lists the group names and available settings:

Map	Orientation, AutoZoom, Land Data, Aviation Data
Weather	Lightning Mode/Symbol (when applicable)
Traffic	Traffic Mode/Symbol/Label (when applicable)
Airport	Large/Medium/Small Airports and Text
NAVAID	VORs, NDBs, Intersections and Text
Waypoint	User Waypoints, Waypoint Text, Flight Plan Wpts
Line	Active Flight Plan/Direct-To, Lat/Long Grid
Control	Controlled Airspace: Class B, C, D (tower zone)
Airspace	Special-Use Airspace: Restricted, MOA, Other
City	Large/Medium/Small Cities and Text
Road	Freeway, National Highway, Local Hwy, Local Road
Other	States/Prov, Rivers/Lakes, Railroads, Wind Vector


NAV PAGES Map Page Options

2



Large, Medium and Small classifications are used on the GNS 430 for airports and cities. Large airports are those with a runway longer than 8100 feet. Medium airports include those with a runway longer than 5000 feet or with a control tower. Large cities are those with approximate populations greater than 200,000 and Medium cities are greater than 50,000.

2

NAV PAGES
Map Page Options

To change a map setup feature:

1. Rotate the large right knob (⌚) to highlight "Setup Map?" and press **ENT**.
2. To change map orientation, rotate the small right knob (⌚) to select "Map" and press **ENT**. Rotate the large right knob (⌚) to highlight the "Orientation" field and rotate the small right knob (⌚) to select the desired option. Select "North up" to fix the top of the map display to a north heading. Select "Track up" to adjust the top of the map display to your current track heading. Select "DTK up" to fix the top of the map display to your desired course. Press **ENT** to accept the selected option.
3. To enable/disable automatic zoom, rotate the small right knob (⌚) to select "Map" and press **ENT**. Rotate the large right knob (⌚) to highlight the "Auto Zoom" field and rotate the small right knob (⌚) to select "On" or "Off". Press **ENT** to accept the selected option. The automatic zoom feature will automatically adjust the map scale from 2000 nm through each lower scale, stopping at 1.0 nm as you approach your destination waypoint.
4. To enable/disable the wind vector, all background land data or all Jeppesen aviation data, rotate the small right knob (⌚) to select "Map" and press **ENT**. Use the large right knob (⌚) to highlight the appropriate field and rotate the small right knob (⌚) to select "On" or "Off". Press **ENT** to accept the selected option.
5. For airports, NAVAIDs, active flight plan waypoints, user-created waypoints, state/provincial boundaries, rivers/lakes and cities: rotate the small right knob (⌚) to select the appropriate "Group" name (per the chart on the previous page) and press **ENT**. Use the large right knob (⌚) to highlight the zoom field for the desired feature and rotate the small right knob (⌚) to select the maximum scale at which the feature should appear on screen. Or select "Off" to never display the selected feature. Press **ENT** to accept the selected option. Next, rotate the large right knob (⌚) to highlight the text field for the desired feature and rotate the small right knob (⌚) to select the desired text size, or select "None" to disable text descriptions. Press **ENT** to accept the selected option.
6. For airspace boundaries, highways, roads, railroad lines, track log data, active flight plan course lines, and lat/long grid lines: rotate the small right knob (⌚) to select the appropriate "Group" name (per the chart on the previous page) and press **ENT**. Use the large right knob (⌚) to highlight the zoom field for the desired feature and rotate the small right knob (⌚) to select the maximum scale at which the feature should appear on screen. Or select "Off" to never display the selected feature. Press **ENT** to accept the selected option.

Distance Measurements

The “Measure Dist?” option provides a quick, easy method for determining the bearing and distance between any two points on the map display.

To measure bearing and distance between two points:

1. Rotate the large right knob (⊖) to highlight “Measure Dist?” and press **ENT**. An on-screen reference pointer will appear on the map display at your present position.
2. Use the small (⊖) and large (⊖) right knobs to place the reference pointer at the location you wish to measure FROM and press **ENT**.
3. Again, use the small (⊖) and large (⊖) right knobs to place the reference pointer at the location you wish to measure TO. The bearing and distance from the first reference location will appear at the top of the map display.
4. To exit the “Measure Dist?” option, press the small right knob (⊖).

Selecting Full Screen Map

The “Data Fields Off?” option provides a full-screen map display (shown bottom right), without the four data fields along the right-hand side of the screen. Select this option when you wish to display a larger map area. If this option has been selected and the data fields are off, “Data Fields On?” will appear as an option instead.

To turn the data fields off (or on), rotate the large right knob (⊖) to highlight “Data Fields Off?” (or “Data Fields On?”) and press **ENT**.


Selecting Desired On-Screen Data

“Change Fields?” allows you to choose the data displayed on the four user-selectable data fields along the right-hand side of the *map page*. There are fourteen available data types, including bearing to destination, distance to destination, estimated time of arrival, ground speed, minimum safe altitude and track. See pages 171 and 175 for descriptions of these (and other) navigation terms.

NAV PAGES

Map Page Options


2



2

NAV PAGES

Map Page Options



To change a data field:

1. Rotate the large right knob (⦿) to highlight "Change Fields?" and press **ENT**.
2. Rotate the large right knob (⦿) to highlight the data field you wish to change.
3. Rotate the small right knob (⦿) to select the type of data you want to appear on this field and press **ENT**.
4. Press the small right knob (⦿) to remove the cursor.

NOTE

The on-screen traffic information will occupy two data fields, leaving room to display only two additional data types. Traffic information is only available when the GNS 430 installation includes connection to traffic information sources. See 400 Series Pilot's Guide Addendum, part number 190-00140-10.

Restoring Factory Settings

"Restore Defaults?" resets all four user-selectable data fields to their original factory default settings.

To restore the factory default settings, rotate the large right knob (⦿) to highlight "Restore Defaults?" (see bottom left) and press **ENT**.

NAVCOM Page



The third NAV page is the *NAVCOM* (navigation communications) page. The *NAVCOM* page provides a list of the airport communication and navigation frequencies at your departure, enroute and arrival airports. The *NAVCOM* page makes selection of the frequencies you'll need along your flight plan quick and convenient. If you do not have an active flight plan with a departure airport, the *NAVCOM* page will display the frequencies for the airport nearest your departure position.

To select a frequency list for a departure, enroute or arrival airport:

1. Press the small right knob (PUSH CRSR) to activate the cursor.
2. Rotate the large right knob (CURSOR) to place the cursor on the airport identifier field (top line on the NAVCOM page).
3. Rotate the small right knob (PUSH CRSR) to select the desired airport and press ENT.

To scroll through the list of frequencies:

1. Activate the cursor, if not already active, by pressing the small right knob (PUSH CRSR).

{continued}

NAV PAGES NAVCOM Page

2



2



3

2

NAV PAGES

NAVCOM Page

2a

COM	DEPARTURE KABQ Public		
118.000	Approach	Info?	127.400
121.900	Approach	Info?	134.800
VLOC	Class C	Info?	123.900
113.20	Class C	Info?	124.400
111.50	Class C	Info?	127.400
TERM	Class C	Info?	127.400
GPS	HSG	NAV	00 000

scroll bar

3a

COM	DEPARTURE KABQ Public		
118.000	Approach	Info?	134.800
127.400	Class C	Info?	123.900
VLOC	Class C	Info?	124.400
113.20	Class C	Info?	127.400
111.50	Class C	Info?	134.800
TERM	Class C	Info?	134.800
GPS	HSG	NAV	00 000

2b

COM	FREQ	KABQ	127.400	Done?
118.000	BEARING	0 M 0		
127.400	ALTITUDE	0 f 0		
VLOC	NARRATIVE	ON OR N OF V-12 AND E OF SANDIA MTNS		
113.20				
111.50				
TERM				
GPS	HSG	NAV	00 000	

2a. Rotate the large right knob (⊙) to move the cursor through the list of frequencies. If there are more frequencies in the list that can be displayed on the screen, a scroll bar along the right-hand side of the screen will indicate which part of the list is currently being displayed.

3a. To place a frequency in the standby field of the COM or VLOC window, highlight the desired frequency and press **ENT**.

Some listed frequencies may include designations for limited usage, as follows:

“TX” - transmit only

“RX” - receive only

“PT” - part time frequency

If a listed frequency has sector or altitude restrictions, the frequency will be preceded by an “Info?” designation.

To view usage restrictions for a frequency:


1. Rotate the large right knob (⊙) to place the cursor on the “Info?” designation directly in front of the desired frequency.

2b. Press **ENT** to display the restriction information.

3b. To return to the NAVCOM page, press **ENT**.

Position Page

The *position page* (the fourth NAV page) displays your present position (by default, in latitude and longitude) and altitude. The *position page* also displays your current track, ground speed, time and a reference waypoint field. These fields are user-selectable to configure the page to your own preferences and current navigation needs.



The graphic "track" indicator at the top of the page indicates the direction you're heading, or track, only while you're moving. Directly below are three user-selectable fields, which by default, display track, ground speed and altitude. Barometric pressure (BARO) settings and minimum safe altitude (MSA) can also be displayed on these fields. MSA is the recommended minimum altitude within approximately ten miles of your present position. MSA is calculated from the information contained in the database and generally includes mountains, buildings and other permanent features.


NOTE

Do not rely solely on MSA as an absolute measure of safe altitude. Consult current charts and NOTAMs for your area.

NAV PAGES

Position Page

2



The graphic "track" indicator and the TRK indication directly below it provide the same information. Use the graphic "track" indicator for quick at-a-glance ground track information.



2 a




4 a

2


NAV PAGES

Position Page

2b



3b



4b



To change the user-selectable data fields:

1. Press **MENU** to display the position page options menu.
- 2a. Rotate the large right knob (⌚) to highlight "Change Fields?" and press **ENT**.
- 3a. Rotate the large right knob (⌚) to highlight the data field you wish to change.
- 4a. Rotate the small right knob (⌚) to display the list of available data items. Continue rotating the small right knob (⌚) to select the desired data item from the list.
5. Press **ENT** to select the desired data item and return to the position page.
6. Press the small right knob (⌚) momentarily to remove the cursor from the page.

The position page also features a reference waypoint field, located at the bottom of the page, to indicate your bearing and distance to/from a selected waypoint. The reference waypoint field can display bearing and distance information for a nearby airport (default), VOR, NDB, intersection or user waypoint.

To change the reference waypoint information:

1. Press **MENU** to display the position page options menu.
- 2b. Rotate the large right knob (⌚) to highlight "Change Fields?" and press **ENT**.
- 3b. Rotate the large right knob (⌚) to highlight the waypoint type field (bottom left corner of the page; default setting will show "APT").
- 4b. Rotate the small right knob (⌚) to display the list of available waypoint types. Continue rotating the small right knob (⌚) to select the desired data item from the list.
5. Press **ENT** to select the desired type and return to the position page.

{continued}

6. To select between "bearing FROM" or "bearing TO" to the reference waypoint, rotate the small right knob (PUSH CRSEL) to select the desired bearing reference and press ENT.
7. Press the small right knob (PUSH CRSEL) momentarily to remove the cursor from the page.
8. If "WPT" is selected as the waypoint type, you can designate any airport, NAVAID or user waypoint as a reference waypoint. Press the small right knob (PUSH CRSEL), rotate the large right knob (PUSH CRSEL) to highlight the waypoint identifier field, then use the small (PUSH CRSEL) and large (PUSH CRSEL) right knobs to enter the identifier of the desired waypoint. Press ENT to confirm the selected waypoints. Press the small right knob (PUSH CRSEL) to remove the cursor.

Restoring Factory Settings

A "Restore Defaults?" option allows you to reset all data fields to their original factory default settings. This will return the three user-selectable fields at the top of the page AND the reference waypoint fields to default settings.

To restore the factory default settings:

1. Press MENU to display the position page options menu.
2. Rotate the large right knob (PUSH CRSEL) to highlight "Restore Defaults?" and press ENT.

NAV PAGES

Position Page




2



2


NAV PAGES

Satellite Status Page



Satellite Status Page

The *satellite status page* (the fifth NAV page) provides a visual reference of GPS receiver functions, including current satellite coverage, GPS receiver status and position accuracy. The *satellite status page* is helpful in troubleshooting weak (or missing) signal levels due to poor satellite coverage or installation problems.



As the GPS receiver locks onto satellites, a signal strength bar will appear for each satellite in view, with the appropriate satellite number (01-32) underneath each bar. The progress of satellite acquisition is shown in three stages:

- No signal strength bars— the receiver is looking for the satellites indicated.
- Hollow signal strength bars— the receiver has found the satellite(s) and is collecting data (see illustration at center left).
- Solid signal strength bars— the receiver has collected the necessary data and the satellite(s) is ready for use (see illustration at bottom left).

The sky view display (at top left corner of the page) shows which satellites are currently in view, and where they are. The outer circle of the sky view represents the horizon (with north at top of the page); the inner circle 45° above the horizon; and the center point directly overhead.


Each satellite has a 30-second data transmission that must be collected (hollow signal strength bar) before the satellite may be used for navigation (solid signal strength bar). Once the GPS receiver has determined your position, the GNS 430 will indicate your position, track and ground speed on the other navigation pages. The GPS receiver status field (see preceding page) will also display the following messages under the appropriate conditions:

- **Searching Sky**— The GPS receiver is searching the sky for ANY visible satellites. You will also be informed of this status with a “Searching the Sky” message.
- **Acquiring Sat**— The GPS receiver is acquiring satellites for navigation. In this mode, the receiver uses satellite orbital data (collected continuously from the satellites) and last known position to determine which satellites should be in view.
- **2D Navigation**— The GPS receiver is in 2D navigation mode. Altitude data will be provided by an altitude serializer.
- **3D Navigation**— The GPS receiver is in 3D navigation mode and will compute altitude using satellite data.
- **Poor Coverg**— The GPS receiver cannot acquire sufficient satellites for navigation.
- **Rcvr Not Usbl**— The GPS receiver is unusable due to incorrect initialization or abnormal satellite conditions. Turn the unit off and on again.
- **AutoLocate**— The GPS receiver is looking for any available satellite. This process can take up to five minutes to determine a position.

NAV PAGES

Satellite Status Page


2



2

NAV PAGES


Vertical Navigation (VNAV)



The *satellite status* page also indicates the accuracy of the position fix, using Estimated Position Error (EPE) and Dilution of Precision (DOP) figures. DOP measures satellite geometry quality (i.e., number of satellites received and where they are relative to each other) on a scale from one to ten. The lowest numbers are the best accuracy and the highest numbers are the worst. EPE uses DOP and other factors to calculate a horizontal position error, in feet or meters.


Vertical Navigation Page

The GNS 430's vertical navigation page (the last NAV page) allows you to create a three-dimensional profile which guides you from your present position and altitude to a final (target) altitude at a specified location. This is helpful when you'd like to descend to a certain altitude near an airport or climb to an altitude before reaching a route or direct-to waypoint. Once the profile is defined, message alerts and additional data on the default NAV and map pages will keep you informed of your progress.



NOTE

To use the vertical navigation features, your ground speed must be greater than 35 knots and you must be navigating to a direct-to destination or using a flight plan.



To create a vertical navigation profile:

1. Press the small right knob (PUSH) to activate the cursor.
2. Rotate the large right knob (PUSH) to highlight the target altitude field.
3. Rotate the small (PUSH) and large (PUSH) right knobs to select the target altitude and press **ENT**.
4. Rotate the small right knob (PUSH) to select "Above Wpt" (AGL) or "MSL", and press **ENT**. "Above Wpt" will use the altitude of a destination airport as stored in the Jeppesen NavData card. "MSL" lets you set a specific target altitude for any waypoint category: airport, VOR, NDB, intersection or user waypoint.
5. Rotate the small (PUSH) and large (PUSH) right knobs to select a distance from the target reference waypoint and press **ENT**. If the target altitude should occur at the target reference waypoint, enter a distance of zero.
6. Rotate the small right knob (PUSH) to select "Before" or "After", and press **ENT**. This setting designates whether the offset distance defines a point before you reach the target reference waypoint or after you reach the waypoint.
7. When using a flight plan, the target reference waypoint itself can be specified from the waypoints contained in the flight plan. By default, the last waypoint in the flight plan will be selected. To select a different waypoint, rotate the small right knob (PUSH) to select the desired waypoint and press **ENT**.

{continued}

NAV PAGES

Vertical Navigation (VNAV)

2




2

3




4



5

2 NAV PAGES

Vertical Navigation (VNAV)



GPS accuracy may be degraded by the U.S. Department of Defense-imposed Selective Availability (SA) program. With "SA" on, GPS altitude may be in error by several hundred meters. Errors of this magnitude may result in fluctuations in the VSR readout on the default NAV page.

8. The default profile utilizes a 400 foot-per-minute descent rate. To change the rate, rotate the large right knob (⦿) to highlight the "VS Profile" field and use the small (⦿) and large (⦿) right knobs to enter a new rate. Press **ENT** when finished.

With the profile set, the vertical speed required (VSR) is displayed on the *vertical navigation page*. Expect the following to occur when using the vertical navigation feature:

- At one minute prior to reaching the initial descent point, a message "Approaching VNAV Profile" occurs. The descent (or climb) angle will also lock to prevent changes in speed from altering the profile.
- If selected, the vertical speed required (VSR) readout on the *default NAV* and *map pages* will show the desired vertical speed to maintain the proper descent (or climb) angle.
- At 500 feet above (or below, for a climb) the target altitude, an "Approaching Target Altitude" message is provided. The VSR readout on the *default NAV* and *map pages* is blanked out, at this point.

Vertical navigation messages can be turned on or off. (By default the messages are off.) Turning the messages off allows you to keep the profile settings you've entered previously, without having them generate messages when the feature isn't needed.

To disable/enable the vertical navigation (VNAV) messages:

1. Press **MENU** to display the vertical navigation page options menu.
2. With "VNAV Messages On?" highlighted, press **ENT**. Or, if the messages are already on and you wish to turn them off, make sure "VNAV Messages Off?" is highlighted and press **ENT**.

Section 3

Direct-To Navigation

The GNS 430's direct-to function provides a quick method of setting a course to a destination waypoint. Once a direct-to is activated, the GNS 430 will establish a point-to-point course line (great circle) from your present position to the selected direct-to destination. Navigation data on the various NAV pages will provide steering guidance until the direct-to is cancelled or replaced by a new destination.

To select a direct-to destination:

- 1a. Press the **→** key. The select direct-to waypoint page will appear, with the waypoint identifier field highlighted.
2. Use the small **ENTER** and large **ENTER** right knobs to enter the identifier of the desired destination waypoint.
3. Press **ENT** to confirm the selected waypoint, and **ENT** to activate the direct-to function.

If you're navigating to a waypoint and get off course, the direct-to function may also be used to re-center the CDI (HSI) needle and proceed to the same waypoint.

To re-center the CDI (HSI) needle to the same destination waypoint:

- 1b. Press the **→** key, followed by **ENT** twice.

NOTE

*If you're navigating an approach with the missed approach point (MAP) as the current destination, re-centering the CDI (HSI) needle with the **→** key will cancel the approach.*

DIRECT-TO

Selecting a Destination

3



3

DIRECT-TO**Selecting by
Facility or City**

To select the direct-to destination by facility name (shown above) or city location (shown below), highlight the second or third line on the direct-to waypoint page. Use the small (PUSH ORN) and large (PUSH ORN) right knobs to enter the facility name or city. The identifier(s) for any matching entries will appear on the top line of the page.

**Selecting a Destination by Facility Name or City**

In addition to selecting a destination by identifier, the *select direct-to waypoint* page also allows you to select airports, VORs and NDBs by facility name or city location. If duplicate entries exist for the entered facility name or city, additional entries may be viewed by continuing to rotate the small right knob (PUSH ORN) during the selection process. (See page 96 for more information on duplicate waypoints.)



To select a direct-to destination by facility name or city:

1. Press the $\rightarrow$ key. The select direct-to waypoint page will appear, with the waypoint identifier field highlighted.
2. Rotate the large (PUSH ORN) right knob to highlight the facility name (second line; see above) or the city (third line; see above) field.
3. Use the small (PUSH ORN) and large (PUSH ORN) right knobs to enter the facility name or city location of the desired destination waypoint. As you spell the facility name or city, the GNS 430's Spell'N'Find feature will select the first entry in the database based upon the characters you have entered up to that point.
4. Continue rotating the small right knob (PUSH ORN) to scroll through any additional database listings for the selected facility name or city. You can also scroll backwards with the small right knob (PUSH ORN) if you scroll past the desired waypoint.
5. Press $\rightarrow$ to confirm the selected waypoint, and $\rightarrow$ to activate the direct-to function.

Selecting a Destination from the Active Flight Plan

If you're navigating an active flight plan, any waypoint contained in the flight plan may be selected as a direct-to destination from the *select direct-to waypoint page*. (See section 4, beginning on page 54, for more information on flight plans.)

To select a direct-to destination from the active flight plan:

1. Press the **BD>** key. The select direct-to waypoint page will appear, with the waypoint identifier field highlighted.
- 2a. Rotate the large **ENT** right knob to highlight the flight plan (FPL) field.
- 3a. Rotate the small right knob **PUSH CRK** to display a window showing all waypoints in the active flight plan.
4. Continue rotating the small right knob **PUSH CRK** to scroll through the list and highlight the desired waypoint.
5. Press **ENT** to confirm the selected waypoint, and **ENT** to activate the direct-to function.

Selecting the Nearest Airport as a Direct-To Destination

The *select direct-to waypoint page* always displays the nearest airports (from your present position) on the NRST field. Navigating directly to a nearby airport is always just a few simple steps away. (Nearby airports may also be selected as direct-to destinations using the steps described on page 121.)

To select a nearby airport as a direct-to destination:


1. Press the **BD>** key. The select direct-to waypoint page will appear, with the waypoint identifier field highlighted.
- 2b. Rotate the large **ENT** right knob to highlight the nearest airport (NRST) field.
- 3b. Rotate the small right knob **PUSH CRK** to display a window showing up to nine nearby airports.
4. Continue rotating the small right knob **PUSH CRK** to scroll through the list and highlight the desired airport.
5. Press **ENT** to confirm the selected airport, and **ENT** to activate the direct-to function.

DIRECT-TO Flight Plan Waypoints Nearest Airports

3



3 DIRECT-TO Shortcuts



Shortcuts

Shortcuts are available when using the **-B>** key, allowing you to bypass the use of the small (PUSH CRN) and large (PUSH CRN) right knobs to enter the destination waypoint's identifier. A direct-to can be performed from any page displaying a single waypoint identifier (such as the WPT pages for airports and navaids) by simply pressing **-B>** and **ENT**. For pages that display a list of waypoints (e.g., the *nearest airport page*), you must highlight the desired waypoint with the cursor before pressing the **-B>** key.

To select an on-screen waypoint as a direct-to destination:

- 1a. If a single airport, navaid or user waypoint is displayed on-screen: press **-B>**, then press **ENT** twice.
- 2a. If a list of waypoints is displayed on-screen: press the small right knob (PUSH CRN) to activate the cursor, rotate the large right knob (PUSH CRN) to highlight the desired waypoint, then press **-B>** followed by **ENT** twice.

Direct-to destinations may also be selected from the *map page*, by panning to the desired destination location and pressing **-B>** and **ENT** (twice). If no airport, navaid or user waypoint exists at the desired location, a waypoint named "+MAP" will automatically be created at the location of the panning pointer.

To select a direct-to destination from the map page:

- 1b. From the map page, press the small right knob (PUSH CRN) to display a panning pointer.
- 2b. Rotate the small (PUSH CRN) and large (PUSH CRN) right knobs to place the panning pointer at the desired destination location.
3. If the panning pointer is placed on an existing airport, navaid or user waypoint, the waypoint name will be highlighted. Press **-B>** and **ENT** twice to navigate to the waypoint.
4. If the panning pointer is placed on an open location, press **-B>** and **ENT** twice to create a "MAP" waypoint and navigate to it.

Cancelling Direct-To Navigation

Once a direct-to is activated, the GNS 430 will provide navigation guidance to the selected destination until the direct-to is replaced with a new direct-to or flight plan, cancelled, or the unit is turned off.

To cancel a direct-to:

1. Press the **-B->** key to display the select direct-to waypoint page.
- 2a. Press **MENU** to display the direct-to options menu.
- 3a. With "Cancel Direct-To NAV?" highlighted, press **ENT**. If a flight plan is still active, the GNS 430 will resume navigating the flight plan along the closest leg.

Specifying a Course to a Waypoint


Whenever you perform a direct-to, the GNS 430 will set a direct great circle course to your selected destination. You can also manually define the course to your destination, using the "CRS" course field on the *select direct-to waypoint page*.

To manually define the direct-to course:

1. Press the **-B->** key.
- 2b. Use the small (**PUSH ENTER**) and large (**ENT**) right knobs to select the destination waypoint.
- 3b. Press **ENT** to confirm the selected waypoint, then rotate the large right knob (**ENT**) to highlight the course ("CRS") field.
4. Rotate the small (**PUSH ENTER**) and large (**ENT**) right knobs to select the desired course and press **ENT**.
5. Press **ENT** again to begin navigation using the selected destination and course.
6. To reselect a direct course from present position (or select a new manually-defined course), simply press **-B->**, followed by **ENT** twice.

DIRECT TO Cancelling & Manual Course

3



2 a

3 a



3 b



4

4 *FLIGHT PLANS* Creating Flight Plans



Section 4 Flight Plans

The GNS 430 lets you create up to 20 different flight plans, with up to 31 waypoints in each flight plan. The flight plan page group consists of two pages, accessed by pressing the **FPL** key. The flight plan pages allow you to create, edit and copy flight plans.



Active Flight Plan



Flight Plan Catalog

Flight Plan Catalog

The *flight plan catalog* allows you to create, edit, activate, delete and copy flight plans. Flight plans numbered from 1 through 19 are used to save flight plans for future use. "Flight plan 0" is reserved exclusively for the flight plan currently in use for navigation. Any time you activate a flight plan, a copy of the flight plan is automatically transferred to "flight plan 0" and overwrites any previously active flight plan.

To create a new flight plan:

1. Press **FPL** and rotate the small right knob (PUSH) to display the flight plan catalog.
2. Press **MENU** to display the flight plan catalog options.
3. Rotate the large right knob (PUSH) to highlight "Create New Flight Plan?" and press **ENT**.
4. A blank flight plan page will appear for the first empty storage location. Use the small (PUSH) and large (PUSH) right knobs to enter the identifier of the departure waypoint and press **ENT**.
5. Repeat step #3 above to enter the identifier for each additional flight plan waypoint.
6. Once all waypoints have been entered, press the small right knob (PUSH) to return to the flight plan catalog.

Flight Plan Editing

To add a waypoint to an existing flight plan:

1. Press **FPL** and rotate the small right knob (PUSH CLR) to display the flight plan catalog.
2. Press the small right knob (PUSH CLR) to activate the cursor.
3. Rotate the large right knob (PUSH CLR) to highlight the desired flight plan and press **ENT**.
- 4a. Rotate the large right knob (PUSH CLR) to select the point where you wish to add the new waypoint. If an existing waypoint is highlighted, the new waypoint will be placed directly in front of this waypoint.
- 5a. Use the small (PUSH CLR) and large (PUSH CLR) right knobs to enter the identifier of the new waypoint and press **ENT**.
6. Once all changes have been made, press the small right knob (PUSH CLR) to return to the flight plan catalog.

To delete a waypoint from an existing flight plan:


1. Press **FPL** and rotate the small right knob (PUSH CLR) to display the flight plan catalog.
2. Press the small right knob (PUSH CLR) to activate the cursor.
3. Rotate the large right knob (PUSH CLR) to highlight the desired flight plan and press **ENT**.
- 4b. Rotate the large right knob (PUSH CLR) to select the waypoint you wish to delete and press **CLR** to display a "remove waypoint" confirmation window.
- 5b. With "Yes" highlighted, press **ENT** to remove the waypoint.
6. Once all changes have been made, press the small right knob (PUSH CLR) to return to the flight plan catalog.

A one-line user comment may be added to any flight plan, which will be displayed on the flight plan catalog, next to the flight plan's number. By default, as the flight plan is being created, the comment will show the first and last waypoints in the flight plan.

FLIGHT PLANS

Editing Flight Plans

4



4 **FLIGHT PLANS**

Activating/Inverting Flight Plans



To change the comment line for an existing flight plan:

1. From the flight plan catalog, press the small right knob (PUSH CURSR) to activate the cursor.
2. Rotate the large right knob (C) to highlight the desired flight plan and press ENT.
- 3a. Rotate the large right knob (C) to select the comment line at the top of the screen.
4. Use the small (PUSH CURSR) and large (C) right knobs to enter the new comment. Press ENT when finished.
5. Once all changes have been made, press the small right knob (PUSH CURSR) to return to the flight plan catalog.

Activating Flight Plans

Once a flight plan is defined through the *flight plan catalog* (using the steps previously outlined), it may be activated for navigation. Activating the flight plan places it into “flight plan 0” and overwrites any previous information at that location.

To activate an existing flight plan:

1. From the flight plan catalog, press the small right knob (PUSH CURSR) to activate the cursor.
2. Rotate the large right knob to highlight the desired flight plan and press MENU to display the flight plan catalog options.
- 3b. Rotate the large right knob (C) to highlight “Activate Flight Plan?” and press ENT.

Inverting Flight Plans

After travelling along a flight plan, you may wish to reverse the route for navigation guidance back to your original departure point.

To activate an existing flight plan in reverse order:

1. From the flight plan catalog, press the small right knob (PUSH CURSR) to activate the cursor.
2. Rotate the large right knob to highlight the desired flight plan and press MENU to display the flight plan catalog options.
- 3c. Rotate the large right knob to highlight “Invert & Activate FPL?” and press ENT. The original flight plan will remain intact in its flight plan catalog storage location.

Copying Flight Plans

If you want to save a flight plan currently located in “flight plan 0”, be sure to copy it to an open catalog location (1-19) before the flight plan is cancelled, overwritten or erased.

To copy a flight plan to another flight plan catalog location:

- 1a. From the active flight plan page, press **MENU** to display the active flight plan options window.
- 2a. From the flight plan catalog, press the small right knob (PUSH) to activate the cursor, rotate the large right knob (ENT) to highlight the flight plan you wish to copy, then press **MENU** to display the flight plan catalog options.
- 3a. Rotate the large right knob (ENT) to highlight “Copy Flight Plan?” and press **ENT**.
4. By default, the next empty catalog location will be offered. To select a different location, rotate the large right knob (ENT) to select the flight plan number, use the small (PUSH) and large (ENT) right knobs to enter a different number and press **ENT**.
5. With “Yes?” highlighted, press **ENT** to copy the flight plan.

Deleting Flight Plans

Once you are finished with a flight plan, it can easily be deleted from the flight plan catalog or the active flight plan page.

To delete a flight plan:

- 1b. From the active flight plan page, press **MENU** to display the active flight plan options window.
- 2b. From the flight plan catalog, press the small right knob (PUSH) to activate the cursor, rotate the large right knob (ENT) to highlight the flight plan you wish to copy, then press **MENU** to display the flight plan catalog options.
- 3b. Rotate the large right knob (ENT) to highlight “Delete Flight Plan?” and press **ENT**.
4. With “Yes?” highlighted, press **ENT** to delete the flight plan.


FLIGHT PLANS

Copying/Deleting Flight Plans


4



1 a
3 a



2 a
3 a




2 b
3 b

4

FLIGHT PLANS

Flight Plan Catalog Options



Flight Plan Catalog Options

The following options (some covered on the preceding pages) are available for the *flight plan catalog*:

Activate Flight Plan? allows you to select the flight plan for navigation guidance, as described on page 56.

Invert & Activate FPL? allows you to reverse the highlighted flight plan and select it for navigation guidance, as described on page 56.

Create New Flight Plan? allows you to create a new flight plan, as described on page 54.

Crossfill? allows you to transfer a direct-to destination, the active flight plan, any stored flight plan or user waypoints to a second 400-Series or 500-Series GARMIN unit. Some crossfill operations can be done automatically. If both units are set to "auto", a change in the direct-to destination or active flight plan on one unit will also be seen on the other.

To crossfill flight plans between two 400- or 500-Series GARMIN units:

1. Select the "Crossfill?" option from the flight plan catalog options and press **ENT**.
2. Rotate the large right knob (⊖) to select the "Method" field.
3. Rotate the small right knob (⊕) to select "Auto" or "Manual" and press **ENT**. "Auto" will automatically transfer the active flight plan or direct-to selection to another 400- or 500-series GARMIN unit, without user intervention.
4. If "Manual" is selected: Rotate the large right knob (⊖) to select the "Transfer" field, then rotate the small right knob (⊕) to select the type of information to transfer between units (active flight plan, flight plan, all user waypoints or a single user waypoint). When "Flight Plan" or "User Waypoint" is selected, a second field will appear to the immediate right of the "Transfer" field. Use the small (⊕) and large (⊖) right knobs to enter the number of the flight plan or the name of the user waypoint you wish to transfer.
5. The "Cross-Side" field allows you to designate the sending and receiving units in a crossfill operation. Rotate the large right knob to select the "Cross-Side" field, then rotate the small right knob (⊕), to select "To" or "From". Press **ENT** to confirm the selection.
6. Rotate the large right knob (⊖) to highlight "Initiate Transfer?" and press **ENT**.

Copy Flight Plan? allows you to copy the selected flight plan to a new flight plan location, as described on page 57. The copy function is useful for duplicating an existing flight plan before making changes.

Delete Flight Plan? allows you to remove the selected flight plan from memory, as described on page 57. Deleting a flight plan does not delete the individual waypoints contained in the flight plan from the database or user waypoint memory.

Delete All Flight Plans? allows you to remove all flight plans from memory.

To delete all flight plans:

- 1a. Select the "Delete All Flight Plans?" option from the flight plan catalog options and press **ENT**.
2. A confirmation window will appear. With "Yes?" highlighted, press **ENT**.

Sort List By Number?/Sort List by Comment? allows you to select between a flight plan catalog sorted numerically by the flight plan number or sorted alphanumerically based upon the comment assigned to each flight plan. When either option is selected, the other option will appear on the flight plan catalog options window.

To sort the catalog listing by number or comment:

- 1b. Select the "Sort List By Number?" or "Sort List By Comment?" option (whichever is currently displayed) from the flight plan catalog options and press **ENT**.


Active Flight Plan

The active flight plan page provides information and editing functions for "flight plan 0"—the flight plan currently in use for navigation. Once you have activated a direct-to or flight plan, the active flight plan page will show each waypoint for the flight plan (or a single waypoint for a direct-to), along with the desired track (DTK) and distance (DIS) for each leg. The data fields for DTK and DIS are user-selectable and may be changed to display cumulative distance (CUM) to each waypoint, estimated time of arrival (ETA), estimated time enroute (ETE) or enroute safe altitude (ESA).

FLIGHT PLANS

4



Active Flight Plan



4

FLIGHT PLANS

Active Flight Plan Options



To change a data field on the active flight plan page:

1. With the active flight plan page displayed, press **MENU** to display the active flight plan page options window.
- 2a. Rotate the large right knob (⌚) to highlight "Change Fields?" and press **ENT**.
3. Rotate the large right knob (⌚) to highlight the field you wish to change.
4. Rotate the small right knob (⌚) to select the desired data item and press **ENT**.
5. Press the small right knob (⌚) to remove the cursor.

To restore factory default settings for data fields on the active flight plan page:

1. With the active flight plan page displayed, press **MENU** to display the active flight plan page options window.
- 2b. Rotate the large right knob (⌚) to highlight "Restore Defaults?" and press **ENT**.

Active Flight Plan Options

The following options (some covered on the preceding pages) are available for the *flight plan catalog*:

Activate Leg? activates/reactivates the flight plan and selects the highlighted leg as the "active leg" (the leg which will currently be used for navigation guidance).

To activate a flight plan along a specific leg:

1. Press the small right knob (⌚) to activate the cursor and rotate the large right knob (⌚) to highlight the desired destination waypoint.
- 2c. Select the "Activate Leg?" option from the active flight plan page options and press **ENT**.
3. A confirmation window will appear. With "Activate?" highlighted, press **ENT**.

Crossfill? allows you to transfer the active flight plan between two 400- or 500-series GARMIN units in a dual unit installation. See pages 58 and 142 for additional information on this feature.

Copy Flight Plan? copies the active flight plan to a flight plan catalog location, as described on page 57. The copy function is useful for duplicating the active flight plan before making changes.

Invert Flight Plan? reverses the active flight plan. See description of “Invert & Activate FPL” option on page 56.

Delete Flight Plan? allows you to remove all waypoints from the selected flight plan, as described on page 57. Deleting a flight plan does not delete the waypoints contained in the flight plan from the database or user waypoint memory.

Select Approach? allows you to select a published instrument approach for the destination airport, or replace the current approach with a new selection. (In many cases, you’ll find it more convenient to select approaches using the **PROC** key—as described on page 66.)


To select an approach for a direct-to or flight plan destination airport:

1. Choose the “Select Approach?” option from the active flight plan page options and press **ENT**.
2. A window will appear listing the available approaches for your destination airport. Rotate the small right knob (**PUSH CRCL**) to highlight the desired approach and press **ENT**.
3. A second window will appear listing available transitions for the approach. Rotate the small right knob (**PUSH CRCL**) to highlight the desired transition waypoint and press **ENT**. (The “Vectors” option assumes you will receive vectors to the final course segment of the approach and will provide navigation guidance to intercept this final course.)
4. Rotate the large right knob (**CRCL**) to highlight “Load?” or “Activate?” and press **ENT**. “Load?” will add the approach to the flight plan without immediately using the approach for navigation guidance. This allows you to continue navigating the original flight plan until cleared for the approach—but, keeps the approach available for quick activation when needed.
5. For precision approaches, a reminder window will appear indicating that GPS guidance on such approaches is strictly for monitoring only. To confirm this reminder, highlight “Yes?” and press **ENT**.

FLIGHT PLANS


Active Flight Plan Options

4



4 FLIGHT PLANS

Active Flight Plan Options



Select Arrival? allows you to select a published standard terminal arrival route (STAR) for the destination airport, or replace the current arrival with a new selection. (See page 66 for information on selecting arrivals using the **PROC** key.)

To select an arrival for a direct-to or flight plan destination airport:

- 1a. Select the "Select Arrival?" option from the active flight plan page options and press **ENT**.
- 2a. A window will appear listing the available arrivals for your destination airport. Rotate the small right knob (**PUSH**) to select the desired arrival and press **ENT**.
- 3a. A second window will appear listing available transitions for the arrival. Rotate the small right knob (**PUSH**) to highlight the desired transition waypoint and press **ENT**.
4. With "Load?" highlighted, press **ENT**.

Select Departure? allows you to select a published standard instrument departure (SID) for the departure airport, or replace the current departure with a new selection. When using a direct-to, the GNS 430 will use the nearest airport as a reference when displaying available departures. See page 66 for information on selecting departures using the **PROC** key.

To select a departure for the departure airport:

- 1b. Select the "Select Departure?" option from the active flight plan page options and press **ENT**.
- 2b. A window will appear listing the available departures for your departure airport. Rotate the small right knob (**PUSH**) to select the desired departure and press **ENT**.
- 3b. A second window will appear listing available transitions for the departure. Rotate the small right knob (**PUSH**) to highlight the desired transition waypoint and press **ENT**.
4. With "Load?" highlighted, press **ENT**.

Remove Approach? deletes the currently selected approach from the active flight plan.

Remove Arrival? deletes the current STAR from the active flight plan.

Remove Departure? deletes the current SID from the active flight plan.

To remove an approach, arrival or departure from the active flight plan:

- 1a. Select the "Remove Approach?", "Remove Arrival?" or "Remove Departure?" option from the active flight plan page options and press **ENT**.
2. A confirmation window will appear listing the procedure you are about to remove. With "Yes?" highlighted, press **ENT**.

Closest Point of FPL? calculates the bearing and closest distance that a flight plan will pass from a reference waypoint. May also be used to create a new user waypoint along the flight plan at the location closest to the reference waypoint.

To determine the closest point, along the active flight plan, to a selected waypoint:

- 1b. Select the "Closest Point of FPL?" option from the active flight plan page options and press **ENT**.
2. A window will appear with the reference waypoint field highlighted. Use the small (⊖) and large (⊕) right knobs to enter the identifier of the reference waypoint and press **ENT**.
3. A confirmation window will appear for the selected reference waypoint. Press **ENT** to accept the waypoint.
4. The GNS 430 will display the bearing (BRG) and distance (DIST) to the closest point along the flight plan, from the selected reference waypoint. To create a user waypoint at this location and add it to the flight plan, highlight "Load?" and press **ENT**. The name for the new user waypoint will be derived from the identifier of the reference waypoint.



Change Fields? allows you to select the desired data items to display on the active flight plan page, as described on page 60.

Restore Defaults? returns the data items to factory defaults. See page 60.

FLIGHT PLANS

Active Flight Plan Options

4



4

FLIGHT PLANS**Active Flight
Plan Editing****Shortcuts**

A number of shortcuts are available to save time when using the active flight plan page. These shortcuts speed the process of removing approaches, departures and arrivals, and aid in selecting a specific flight plan leg for navigation guidance.

On the preceding page, options to remove approaches, departures and arrivals were introduced. This process may also be completed using the **CLR** key, as described below and illustrated at left.

To remove an approach, departure or arrival using the **CLR** key:

1. With the active flight plan page displayed, press the small right knob (PUSH CRK) to activate the cursor.
- 2a. Rotate the large right knob (C) to highlight the title for the approach, departure or arrival you wish to delete. Titles will appear in light blue directly above the procedure's waypoints.
- 3a. Press **CLR** to display a confirmation window.
4. With "Yes?" highlighted, press **ENT** to remove the selected procedure.

This same process may also be used to remove individual waypoints from the active flight plan.

To remove a waypoint using the **CLR** key:

1. With the active flight plan page displayed, press the small right knob (PUSH CRK) to activate the cursor.
- 2b. Rotate the large right knob (C) to highlight the identifier for the waypoint you wish to delete. Identifiers will appear in green text.
- 3b. Press **CLR** to display a confirmation window.
4. With "Yes?" highlighted, press **ENT** to remove the selected procedure.

On page 60 the “Activate Leg?” option is discussed, which allows you to specify which leg of the flight plan will currently be used for navigation guidance. A shortcut also exists for this operation, using the **-B->** key.

To activate a specific leg of the active flight plan:

1. Press the small right knob (Ⓜ) to activate the cursor and rotate the large right knob (Ⓢ) to highlight the desired destination waypoint.
- 2a. Press **-B->** twice to display an “Activate Leg” confirmation window.
3. With “Activate?” highlighted, press **ENT**.

When using instrument procedures, this feature can be used not only to activate a specific point-to-point leg, but to also activate the procedure turn portion of an approach, follow a DME arc or activate a holding pattern.

Any approach, departure or arrival can be reviewed on the appropriate airport page in the Waypoint page group. See page 94.

To review a procedure while viewing a flight plan page:

1. With a flight plan page displayed, press the small right knob (Ⓜ) to activate the cursor.
- 2b. Rotate the large right knob (Ⓢ) to highlight the procedure header and press **ENT** to select the WPT page group.

FLIGHT PLANS


Active Flight Plan Leg Selection

4



5 PROCEDURES

Approaches, Departures & Arrivals



Section 5

Approaches, Departures & Arrivals

The GNS 430 allows you to fly non-precision and precision approaches to airports with published instrument approach procedures. All available approaches are stored on your Jeppesen NavData® card, and are automatically updated when you replace the card with a new one. Subscription information for NavData cards is included in your GNS 430 package.

The *procedures page* (shown at top left) is displayed by pressing the **PROC** key. The *procedures page* provides direct access to approaches, departures and arrivals—based upon the active flight plan or direct-to destination. In either case, the departure and destination airports must have published procedures associated with them.

To select an approach, departure or arrival:

1. Press the **PROC** key to display the procedures page.
2. Rotate the large right knob (⊖) to highlight “Select Approach?”, “Select Departure?” or “Select Arrival?” and press **ENT**.
3. A window will appear listing the available procedures. Rotate the large right knob (⊖) to highlight the desired procedure and press **ENT**. (When a direct-to destination is selected, departures are offered for the nearest airport.)
4. A second window will appear listing the available transitions. Rotate the large right knob (⊖) to highlight the desired transition waypoint and press **ENT**. (The approach “Vectors” option assumes you will receive vectors to the final course segment of the approach and will provide navigation guidance relative to the final approach course.)
5. Rotate the large right knob (⊖) to highlight “Load?” or “Activate?” (approaches only) and press **ENT**. (“Load?” will add the procedure to the flight plan without immediately using it for navigation guidance. This allows you to continue navigating the original flight plan, but keeps the procedure available on the active flight plan page for quick activation when needed.)
6. For precision approaches and some non-precision approaches, a reminder window will appear indicating that GPS guidance on such approaches is strictly for monitoring only — use the VLOC receivers and external CDI (or HSI) for primary navigation. To confirm this reminder, highlight “Yes?” and press **ENT**.



Not all approaches in the database are approved for GPS use. As you select an approach, a “GPS” designation to the right of the procedure name indicates the procedure can be flown using the GPS receiver. Some procedures will not have this designation, meaning the GPS receiver may be used for supplemental navigation guidance only. ILS approaches, for example, must be flown by tuning the VLOC receiver to the proper frequency and coupling the VLOC receiver to the external CDI (or HSI).

Once an approach is selected, it may be activated for navigation from the *procedures page*. Activating the approach overrides the “enroute” portion of the active flight plan, proceeding directly to the “approach” portion (for a full approach, directly to the initial approach fix). Activating the approach also initiates automatic CDI scaling transition as the approach progresses.

To activate an approach:

1. Press the **PROC** key to display the procedures page.
- 2a. Rotate the large right knob (⊙) to highlight “Activate Approach?” and press **ENT**.

Another procedures page option allows you to activate the final course segment of the approach. This option assumes you will receive vectors to the final approach fix (FAF) and guides you to intercept the final course, before reaching the FAF.

To activate the approach, with vectors to final:



1. Press the **PROC** key to display the procedures page.
- 2b. Rotate the large right knob (⊙) to highlight “Activate Vector-To-Final?” and press **ENT**.

In many cases, it may be easiest to “Load” the full approach while still some distance away, enroute to the destination airport. Later, if vectored to final, use the steps above to select “Activate Vector-To-Final”—which makes the inbound course to the FAF waypoint active. Otherwise, activate the full approach using the “Activate Approach?” option.

PROCEDURES

Activating Approaches


5



PROCEDURES

5

Basic Approach Operations



Basic Approach Operations

The GNS 430 provides non-precision approach guidance using its built-in GPS receiver. The GPS receiver can also be used as a supplemental aid for precision approaches, but the localizer and glideslope receivers **MUST** be used for primary approach course guidance.

Approaches designed specifically for GPS are often very simple and don't require overflying a VOR or NDB. Currently, many non-precision approaches have "GPS overlays" to let you fly an existing procedure (VOR, VOR/DME, NDB, RNAV, etc.) more accurately using GPS. To date, there are over 2,400 GPS-only approaches and over 2,900 GPS overlay approaches.


Many overlay approaches are complex (in comparison to GPS-only approaches). The GNS 430 displays and guides you through each leg of the approach—automatically sequencing through each of these legs, up to the missed approach point (MAP). Approaches may be flown "as published" with the full transition — using any published feeder route or initial approach fix (IAF) — or may be flown with a vectors-to-final transition.

Approach operations on the GNS 430 will typically begin with the same basic steps:

1. Select the destination airport using the **⏮** key, or as the last waypoint in the active flight plan.
2. Choose the "Select Approach?" option from the procedures page (see page 66) or from the active flight plan options (see page 61).
3. "Load" the approach (often while enroute) in anticipation of its future use. This places the approach in the active flight plan, but retains course guidance in the enroute section until the approach is "activated".
4. "Activate" the full approach or vectors-to-final, as appropriate. In some scenarios, you may find it more convenient to immediately activate the approach and skip the "Load" process outlined above in step #3. The GNS 430 provides both options.

Approaches with Procedure Turns

The procedure turn portion of an approach is stored as one of the legs of the approach. For this reason, the GNS 430 requires no special operations from the pilot — other than flying the procedure turn itself — beyond what is required for any other type of approach.




This example uses the VOR Runway 03 approach for Lynchburg (Virginia) Regional Airport, KLYH, and assumes a departure from Frederick (Maryland) Municipal Airport, KFDK. The steps required to set up and fly the approach are detailed below:

1. Prior to departing KFDK, the destination (KLYH) is selected using the **→** key or by creating a flight plan terminating at Lynchburg Regional.
2. While enroute to KLYH, some 40-50 nautical miles away, you select the ATIS frequency to monitor airport conditions and runway usage. This is accomplished by selecting the NAV-COM page (see page 39) and selecting the ATIS frequency from the list. This places the frequency on standby. Use the **ⓘ** key to make the ATIS frequency active.
3. From ATIS you learn that runway 03 is in use and plan your approach accordingly. Press the **PROC** key and select the "VOR 03" approach using the steps outlined on page 66. From the transitions window, select LYH VOR (the IAF). Also, select "Load?" to load (but not activate) the approach.
4. Once you are cleared for the approach, press the **PROC** key, select "Activate Approach?" and press **ENT**.

PROCEDURES

Procedure Turn Approach Example


5




5

PROCEDURES

Procedure Turn
Approach Example



-



6. Turn left to a heading of 160° to initiate the procedure turn. Course guidance is provided relative to the outbound leg from the FAF. No guidance through the procedure turn itself is given. (The procedure turn is displayed on the map page and indicated as the active leg on the default NAV and active flight plan pages.) The CDI needle will start moving to the right.
7. After approximately one minute, make a 180° right turn to a heading of 340° to intercept the inbound course. The GNS 430 will sequence to the inbound leg to the FAF, the CDI needle will swing to the opposite side to provide proper sensing along the final course segment and "NEXT DTK 025°" will appear in the lower right corner of the screen.
8. As the CDI needle starts to center, make a right turn to 025°—the final approach course.
9. Within 2.0 nautical miles of the FAF (LYH), the GNS 430 will switch from terminal mode to "approach" mode. CDI scaling will be tightened from 1.0 to 0.3 nautical mile, full scale deflection.
10. As you approach the FAF, a waypoint alert in the lower right corner ("NEXT DTK 026°") will appear. Make any course adjustments necessary for the final course segment (FAF to MAP).

11. As you cross the FAF, the destination sequences to the MAP ("RW03", the runway threshold). With the needle centered, fly toward the MAP, observing the altitude minimums dictated by the approach plate.

NOTE

When viewing the map page, note that the final course segment is displayed in magenta (the active leg of the flight plan always appears in magenta) and a dashed line extends the course beyond the MAP. The dashed line is provided for situational awareness only and should NOT be used for navigation. Follow the published missed approach procedures.

12. As you approach the MAP, a waypoint alert ("APPRCHING WPT") will appear in the lower right corner.
13. As you cross the MAP, "SUSP" will appear above the **OBS** key, indicating that automatic sequencing of approach waypoints will be suspended at the MAP. A "from" indication will be displayed on the CDI and default NAV page, but course guidance along the final approach course will continue. If a missed approach is required, use the **OBS** key to initiate the missed approach sequence, as outlined on the following page.

PROCEDURES

Procedure Turn Approach Example

5




NOTE

13

5

PROCEDURES**Missed Approach Example****Flying the Missed Approach**

After you pass the MAP, if the runway isn't in sight you must execute a missed approach. The GNS 430 continues to give guidance along an extension of the final course segment (FAF to MAP) until you manually initiate the missed approach procedure (as mentioned previously in reference to the "SUSP" advisory). The **OBS** key is used to initiate the missed approach, as follows:



1. Press the **OBS** key. The missed approach holding point (MAHP; in this case "SWARM" intersection) is automatically offered as the destination waypoint.

NOTE

In some cases, an additional hold waypoint is added to the missed approach sequence. This additional waypoint is used as an aid in establishing the holding pattern—especially where the MAP and MAHP are the same waypoint.

2. Follow the missed approach procedures, as published on your approach plate, for proper climb and heading instructions. The GNS 430 will guide you to the holding pattern, along the 053° radial from LYH VOR.


{continued}

3a. An alert message in the lower right hand corner of the screen will recommend entry procedures for the holding pattern (i.e., "HOLD DIRECT", "HOLD PARALLEL", or "HOLD TEARDROP"). As you fly the holding pattern, a timer appears on the default NAV page. The timer automatically resets on the outbound side of the hold when you are abeam the hold waypoint. The timer again resets as you turn inbound (within approximately 30° of the inbound course). This allows you to use standard timing (typically one minute) to fly the inbound and outbound legs of the hold.

4a. The GNS 430 will provide course guidance only on the inbound side of the holding pattern. When leaving the holding pattern to re-fly the approach (or another approach) press the **PROC** key to "Select Approach?" or "Activate Approach?" as previously described. (Or, use the **→** key to select another destination.)

Flying an Approach with a Hold

Starting where the previous example left off, we'll assume weather conditions resulted in a missed approach at Lynchburg Regional. Now, you've decided to divert to Farmville Regional (KFVX) instead.



1. Press **→**.
2. Use the small (⏻) and large (⏻) right knobs to enter the destination airport's identifier (KFVX).

3b. Press **ENT** twice.

This time, you select the GPS runway 21 approach into Farmville Regional. The GPS runway 21 approach begins with a holding pattern at the IAF BODRY intersection.




- 4b. Press **PROC** and select the "GPS 21" approach. (See page 66 for additional instructions.)

{continued}

PROCEDURES

Approach with Hold Example

5



5

PROCEDURES**Approach with Hold Example**

6

COH 127.650	ACTIVE FLIGHT PLAN		
VLOC 109.00	00 KFDK / KFBX		
109.20	WAYPOINT	DTK	DIS
TERM	Approach GPS 21		
	→ BODRY IA	087° _M	23.4 _N _M
	hold	209° _M	01:00
	DEPOY FA	209° _M	5.0 _N _M
GPS	HSG	FPL	0

8

COH 132.725	1.0 1.0		
VLOC 113.30	→ BODRY IA		
109.00	DIS	DTK	BRG
TERM	0.36 _N _M	093° _M	093° _M
	143 _K _t	093° _M	00:08
GPS	GS	TRK	ETE
	HSG	HOLD TEARDROP	

9

10

COH 135.400	1.0 1.0		
VLOC 113.30	00:15 BODRY		
109.00	DIS	DTK	BRG
TERM	0.50 _N _M	209° _M	354° _M
	143 _K _t	211° _M	--:--
GPS	GS	TRK	ETE
	SUSP	HSG	NAV 00000

5. From the transitions window, select BODRY intersection as the IAF. Also, select "Activate?" to load and activate the approach.


6. Once you activate the approach, the active flight plan page will appear. You may review the approach sequence by pressing the small right knob (PUSH CLR) and rotating the large right knob (ENTR). Press FPL to return to the navigation pages.

7. As in the last example, within 30 nautical miles of the airport, the GNS 430 will switch from enroute mode to terminal mode, and the CDI scale will transition from 5.0 to 1.0 nautical miles, full scale deflection.


8. Just prior to crossing BODRY intersection, an alert—"HOLD TEARDROP"—will appear in the lower right corner of the screen to suggest the proper holding pattern entry. ("HOLD DIRECT" or "HOLD PARALLEL" may be offered on other similar approaches.)

9. As mentioned in the missed approach example, the default NAV page will display a timer during the holding pattern. Use this timer to fly the one minute outbound portion of the holding pattern. (The holding pattern is displayed on the map page and indicated as the active leg on the default NAV and active flight plan pages.)

10. When crossing the IAF, "SUSP" will appear above the OBS key, indicating that automatic sequencing of approach waypoints is temporarily suspended. As you make the turn inbound, "SUSP" will be cancelled and the GNS 430 will return to automatic sequencing.

**NOTE**

If you need to lose extra altitude or speed by going around the holding pattern again, press **OBS** to manually suspend waypoint sequencing BEFORE crossing the holding waypoint the second time. If you've already passed this waypoint, re-activate the holding pattern using the steps described on page 65.





11. Also as you approach BODRY intersection, a waypoint alert ("NEXT DTK 209°") will appear in the lower right corner of the screen.
12. At 2.0 nautical miles from the FAF (DEPOY intersection), the GNS 430 will switch from terminal mode to approach mode. CDI scaling will be tightened from 1.0 to 0.3 nautical mile, full scale deflection.
13. As you approach the FAF, a waypoint alert in the lower right corner ("NEXT DTK 209°") will appear. Make any course adjustments necessary for the final course segment (FAF to MAP).
14. As you cross the FAF, the destination sequences to the MAP ("RW21", the runway threshold). With the needle centered, fly toward the MAP, observing the altitude minimums dictated by the approach plate. (When viewing the map page, you'll note that the final course segment is displayed in magenta—the active leg of the flight plan always appears in magenta—and a dashed line extends the course beyond the MAP. Do NOT follow this extended course. Instead, follow published missed approach procedures.)

15. As you approach the MAP, a waypoint alert ("APPRCHING WPT") will appear in the lower right corner.
16. As you cross the MAP, "SUSP" will appear above the **OBS** key, indicating that automatic sequencing of approach waypoints will be suspended at the MAP. A "from" indication will be displayed on the CDI and default NAV page, but course guidance along the final approach course will continue. If a missed approach is required, use the **OBS** key to initiate the missed approach sequence, as outlined on page 72.


PROCEDURES

Approach with Hold Example


5



5

PROCEDURES**DME Arc
Approach Example****Flying a DME Arc
Approach**

The GPS overlay for a DME arc approach uses additional Jeppesen-provided waypoints to define the arc. These waypoints are indicated by “D” as the first letter in the waypoint name. This is followed by three numbers which indicate the radial the waypoint lies on. The last letter indicates the radius of the arc.

**NOTE**

As this manual was being written, the letter/number DME arc names were being replaced with standard five-letter intersection names. You may encounter either naming convention for an approach you select.


When you are cleared for a DME arc approach, you may do either of the following to intercept the arc:

- Follow a specified radial inbound to intercept the IAF.
- Follow ATC vectors which allow you to intercept the arc at any point along the arc.

This example is based upon a flight from Hutchinson (Kansas) Municipal (KHUT) to Billard Municipal (KTOP) in Topeka, Kansas. The VOR/DME runway 22 approach will be selected, along with “D258G” as the IAF.

1. Select Billard Muni (KTOP) as your destination, via the **-B>** key or as the last waypoint in a flight plan.

(continued)

**DO NOT USE FOR
NAVIGATION**


2. Press the **PROC** key and select the "VOR 22" approach using the steps outlined on page 64. From the transitions window, select "D258G" as the IAF. Also, select "Load?" (or "Activate?", if already cleared for the approach).
3. Within 30 nautical miles of KTOP, the GNS 430 will switch from enroute mode to terminal mode and the CDI scale will transition from 5.0 to 1.0 nautical miles, full scale deflection.
4. If you haven't already activated the approach (in step #2 above), be sure to do so when cleared for the approach. See page 69, step #4 for a description of this operation.
5. As you approach the IAF (D258G), a waypoint alert ("NEXT DTK 353°") will appear in the lower right corner of the screen. As the distance (DIS) to the IAF approaches zero, the alert is replaced by a turn advisory ("TURN TO 353°").
6. Follow the arc, keeping the CDI needle centered. When using an autopilot, the course select on the CDI (or HSI) must be periodically updated with the desired track (DTK) to ensure proper tracking through the arc. Whenever the course select setting and desired track differ by more than 10°, a "Set course to ### °" message will appear on the message page.
7. The next point in the approach is an intermediate fix, labeled "D025G". As you approach this intermediate fix, a waypoint alert ("NEXT DTK 205°") will appear in the lower right corner of the screen. As the distance to this fix approaches zero, the alert is replaced by a turn advisory ("TURN TO 205°"). Dial this course into the CDI (or HSI) using the OBS knob and initiate a standard rate turn to this course heading.
8. At 2.0 nautical miles from the FAF (TOP VOR), the GNS 430 will switch from terminal mode to approach mode. CDI scaling will be tightened from 1.0 to 0.3 nautical mile, full scale deflection.

{continued}

PROCEDURES

DME Arc Approach Example

5



4



5



7

5


PROCEDURES**DME Arc
Approach Example**

9. As you approach the FAF, "NEXT DTK 214°" will appear in the lower right corner of the screen. Select this course on the CDI (or HSI) using the OBS knob and turn to the final course segment (FAF to MAP) heading.

10. As you cross the FAF, the destination sequences to the MAP ("RW22", the runway threshold). With the needle centered, fly toward the MAP, observing the altitude minimums dictated by the approach plate. When viewing the map page, you'll note that the final course segment is displayed in magenta (the active leg of the flight plan always appears in magenta) and a dashed line extends the course beyond the MAP.

11. As you approach the MAP, a waypoint alert ("APPRCHING WPT") will appear in the lower right corner.

12. As you cross the MAP, "SUSP" will appear above the **OBS** key, indicating that automatic sequencing of approach waypoints will be suspended at the MAP. A "from" indication will be displayed on the CDI and default NAV page, but course guidance along the final approach course will continue. Do NOT follow this extended course. Follow published missed approach procedures using the **OBS** key to initiate the missed approach sequence, as outlined on page 72.

**DO NOT USE FOR
NAVIGATION**

Vectors to Final

Let's take a second look at the "VOR 22" approach into Billard Municipal. Instead of following the DME arc, ATC tells you to expect vectors onto the final approach course. There are several ways to select "vectors to final" with the GNS 430. The first two options below will normally require the least workload to accomplish:

- When the approach is first selected, choose "VECTORS" from the transitions window.
- Load a full approach — including the IAF from the transitions window — as described on page 66. When cleared, press **PROC** and select "Activate Vectors-To-Final?". (See page 67.)
- Load the full approach as described on page 66. Use the **-B>** key (by pressing it twice) from the active flight plan page to select the desired leg of the approach. (See page 65.)

To select "VECTORS" from the transitions window:

1. Select Billard Municipal (KTOP) as your destination, using the **-B>** key, or as the last waypoint in a flight plan.
2. Press the **PROC** key and select the "VOR 22" approach using the steps outlined on page 66.
- 3a. From the transitions window, select "VECTORS".
- 4a. Select "Load?" (or "Activate?", if already cleared for the approach).


To activate vectors-to-final from the procedures page:

1. Select Billard Municipal (KTOP) as your destination, using the **-B>** key or as the last waypoint in a flight plan.
2. Press the **PROC** key and select the "VOR 22" approach using the steps outlined on page 66.
- 3b. From the transitions window, select "D258G" as the IAF. Also, select "Load?".
- 4b. When cleared, press the **PROC** key and select "Activate Vector-To-Final?".

PROCEDURES

Vectors-To-Final Approach Example

5




5


PROCEDURES**Vectors-To-Final
Approach Example****Flying the Vectors Approach**

With “vectors to final” selected, the CDI needle will remain off center until you’re established on the final approach course. With the approach activated, the *map page* will display an extension of the final approach course in magenta (remember, magenta is used to depict the active leg of the flight plan) and “VTF” will appear as part of the active leg on the *default NAV page* (as a reminder that the approach was activated with vectors-to-final). In this example, we’ll assume ATC vectors result in a rectangular course to intercept final, as follows:

1. Within 30 nautical miles of KTOP, the GNS 430 will switch from enroute mode to terminal mode and the CDI scale will transition from 5.0 to 1.0 nautical miles, full scale deflection.
2. If you haven’t already done so, activate the approach (with vectors-to-final). This allows the GNS 430 to guide you to the final approach course. (See page 79.)
3. ATC instructs you to turn left to a heading of 025°. This places you parallel to the final approach course in the opposite direction. CDI needle deflection is to the left.
4. ATC instructs you to turn right to a heading of 115°.
5. ATC instructs you to turn right to a heading of 175° to intercept the final approach course. As you converge with the final approach course the needle moves toward the center. (In the illustration at left, the needle has not yet returned to the on-screen CDI, since your current position is still 1.7 nm right of the final approach course.)

**DO NOT USE FOR
NAVIGATION**

{continued}



6. As the CDI needle centers, make any remaining course corrections to establish yourself on the final approach course. At 2.0 nautical miles from the FAF (TOP VOR), the GNS 430 will switch from terminal mode to approach mode. CDI scaling will be tightened from 1.0 to 0.3 nautical mile, full scale deflection.

7. As you approach the FAF, a waypoint alert in the lower right corner ("NEXT DTK 214°") will appear. Make any course adjustments necessary for the final course segment (FAF to MAP).

8. As you cross the FAF, the destination sequences to the MAP ("RW22"). With the needle centered, fly toward the MAP, observing the altitude minimums dictated by the approach plate.


9. As you approach the MAP, a waypoint alert ("APPRCHING WPT") will appear in the lower right corner.

10. As you cross the MAP, "SUSP" will appear above the **OBS** key, indicating that automatic sequencing of approach waypoints will be suspended at the MAP. A "from" indication will be displayed on the CDI and default NAV page, but course guidance along the final approach course will continue. Do NOT follow this extended course. Follow published missed approach procedures using the **OBS** key to initiate the missed approach sequence, as outlined on page 72.

PROCEDURES


Vectors-To-Final Approach Example

5



5

PROCEDURES

Course From Fix
Approach Examples


Course From Fix Flight Plan Legs

Certain approach, departure, and arrival procedures in the Jeppesen database contain *course from fix* flight plan legs. The GNS 430 is able to load these legs into the flight plan along with the rest of the procedure data, and to provide navigation along these legs.

There are three different types of course from fix legs:

TYPE 1: Course from fix to distance, or Course from fix to DME distance

Course from fix to distance legs will appear in the flight plan like normal waypoints, but the destination name will always begin with a "D", followed by a distance in tenths of nautical miles from the waypoint fix. This example uses the VOR/DME RWY 25 approach into Palmdale, California (KPMD) and includes a teardrop course reversal.



1. As you reach the initial approach fix (PMD), a waypoint alert ("NEXT DTK 070°") will appear in the lower right corner of the screen. As the distance to the IAF approaches zero, the alert is replaced by a turn advisory ("TURN TO 070°"). Dial the outbound course into the CDI (or HSI) using the OBS knob and initiate a standard rate turn to this course heading.
2. Fly the outbound course, keeping the CDI needle centered. You are now on the 'course from fix to distance' leg, as shown on the active flight plan and default NAV pages. Note the magenta line in the bottom figure, which represents the currently active leg of the approach. The distance (DIS) displayed on the above screens is TO the "D13.0" point. The flight plan will automatically sequence to the next leg upon reaching "D13.0".
3. At 13.0 nm from the FAF, a waypoint alert ("NEXT DTK 265°") will appear in the lower right corner of the screen. Make a standard rate turn to the right to intercept the final approach course and watch for the CDI needle to begin to center.

{continued}

4. As you approach the intermediate fix (CF25), a waypoint alert ("NEXT DTK 265°") will appear. Make any necessary course adjustments.
5. Within 2.0 nautical miles of the FAF (THERO), the GNS 430 will switch from terminal mode to approach mode. ("APR" will appear in the lower left corner of the screen—replacing "TERM".) CDI scaling will be tightened from 1.0 to 0.3 nautical mile, full scale deflection.
6. As you approach the FAF, "NEXT DTK 265°" will appear in the lower right corner of the screen.
7. As you cross the FAF, the destination sequences to the MAP (MA25). With the CDI needle centered, fly toward the MAP, observing the altitude minimums dictated by the approach plate.
8. As you approach the MAP, a waypoint alert ("APPRCHING WPT") will appear in the lower right corner of the screen.
9. As you cross the MAP, "SUSP" will appear above the **OBS** key, indicating that automatic sequencing of approach waypoints is suspended at the MAP. If a missed approach is required, use the **OBS** key to initiate the missed approach sequence, as outlined below.

TYPE 2: Course from fix to altitude

Course from fix to altitude legs will show the specific target altitude on the active flight plan and default NAV pages. The missed approach sequence for the Palmdale VOR/DME RWY 25 approach includes a *course from fix to altitude* leg. In this instance, the leg corresponds to the initial phase of the missed approach, which reads "Climb to 5000' outbound via PMD VOR R-282".


1. After crossing the MAP, press the **OBS** key. The missed approach sequence is automatically offered, starting with the course from fix to altitude leg. The "NEXT DTK 282°" alert appears in the lower right corner of the screen. Follow the missed approach procedures, as published on your approach plate, for proper climb and heading instructions.
2. Note that within a few seconds of pressing **OBS** to release suspend mode and start the approach sequence, "SUSP" re-appears above the **OBS** key as the GNS 430 returns to suspend mode. This is normal when flying a course from fix to altitude leg and indicates that automatic leg sequencing is suspended.

{continued}

PROCEDURES

Course From Fix Approach Examples


5



5

PROCEDURES


Course From Fix Approach Examples



3. Fly the outbound course keeping the CDI needle centered. The map page will depict the flight path extending indefinitely from PMD VOR. The distance (DIS) on the default NAV, map and active flight plan pages will increase—and indicates the distance back to PMD VOR.

4. Upon reaching the desired altitude (5000'), press **OBS** to return to automatic leg sequencing. Confirm that "SUSP" no longer appears directly above the **OBS** key.


5. An alert ("NEXT DTK 126°") will appear guiding you to the inbound course. The actual desired track (DTK) will depend on your ground speed and distance from PMD VOR. Intercept and fly the inbound course, keeping the CDI needle centered.
6. As you approach PMD VOR (the missed approach holding point), an alert message in the lower right hand corner of the screen will recommend the holding pattern entry procedure ("HOLD PARALLEL"). As you fly the holding pattern, a timer appears on the default NAV page. The timer automatically resets on each outbound and inbound portion of the holding pattern.
7. Note that the GNS 430 again displays "SUSP" above the **OBS** key. Automatic waypoint sequencing is suspended at the missed approach holding point. A waypoint alert ("APPROCHING WPT") appears in the lower right corner of the screen each time you approach PMD VOR in the holding pattern.
8. When leaving the holding pattern, press the **PROC** key to reactivate the approach or select a different approach, or press **▷◁** to select another destination.



TYPE 3: Course from fix to manual sequence

Course from fix to manual sequence legs will appear on the active flight plan and map pages with “man seq” in place of a waypoint identifier. An example of this type of course leg appears in the COASTAL ONE DEPARTURE from Westfield, Massachusetts (Barnes Muni). The example leg corresponds to the departure leg from Barnes Municipal and appears as follows on the active flight plan and default NAV pages:


1. Select the departure (CSTL1) from the procedures page. Then select the departure runway (RW02, in this example) and transition (GEDIC). Refer to page 66 for instructions on selecting departures.
2. As you depart the airfield, “NEXT DTK 026°” appears in the lower right corner of the screen and “SUSP” appears directly above the **OBS** key. You are now on the ‘course from fix to manual sequence’ leg. The distance displayed on the active flight plan, default NAV and map pages is FROM the waypoint fix (the departure runway, in this example).
3. Fly the outbound course keeping the CDI needle centered. Once you are cleared to sequence to the next leg, press the **OBS** key. Confirm that “SUSP” no longer appears directly above the **OBS** key. An alert (“NEXT DTK 186°”) will appear in the lower right corner of the screen to guide you to the next waypoint (HFD VOR). The actual desired track (DTK) will depend on your ground speed and distance from HFD VOR.
4. Once the **OBS** key is pressed, the GNS 430 will automatically sequence to each waypoint along the remainder of the departure route, including the selected transition.



PROCEDURES

Course From Fix Approach Examples


5



5

PROCEDURES

ILS Approach Example



ILS Approaches

Precision approaches can be performed with the GNS 430's built-in VLOC (VOR/localizer/glideslope) receivers. The GPS receiver can be used for guidance prior to reaching the final approach fix, but once there, the proper frequency must be selected on the VLOC window (left side of screen) and the CDI output set to "VLOC".


The GNS 430 can be set to automatically switch the external CDI output from GPS to VLOC as you intercept the final approach course. When the ILS approach is activated, the GNS 430 will automatically switch within 1.2 nautical miles left or right of the final approach course. This switch can take place anywhere from 2.0 to 15.0 nautical miles from the FAF.

The illustration at left shows multiple locations along the approach path and which CDI selection you can expect: GPS or VLOC. Within the area of the shaded box, the automatic switch from GPS to VLOC should occur.

NOTE

If you attempt to intercept the approach course at a distance less than 2.0 nautical miles from the FAF, the GNS 430 will not automatically switch the CDI to VLOC. In this case, press the CDI key to manually switch from GPS to VLOC.

The automatic switch from GPS to VLOC is not immediate, but instead occurs gradually to prevent abrupt CDI changes when coupled to an autopilot. The CDI selection can also be changed manually by pressing the **CDI** key. Once the switch from GPS to VLOC has occurred, either automatically or manually, it will not automatically switch again until the approach is reactivated or another approach is selected. To prevent automatic ILS CDI selection, choose the "Manual" ILS CDI setting, as described on page 155. (The factory default setting is "Auto", which enables the automatic switch to VLOC.)



Selecting an ILS Approach

For this example, we'll use a flight from Laughlin Bullhead (Arizona) International to Flagstaff Pulliam (KFLG) and select the ILS runway 21 approach. "SHUTR" intersection will be selected as the IAF, which will include an outbound leg and a procedure turn. Of course, vectors-to-final could also be selected, as previously described for the non-precision approach examples.

1. Select Flagstaff Pulliam (KFLG) as your destination, via the **-B>** key or as the last waypoint in a flight plan.


2. Press the **PROC** key and select the "ILS 21" approach using the steps outlined on page 66.
3. From the transitions window, select "SHUTR" as the IAF. Also, select "Load?" (or "Activate?", if already cleared for the approach).
4. A reminder message appears, indicating that GPS can only be used for approach monitoring. As mentioned, you will need to use the VLOC receiver for this approach. Press ENT to acknowledge the message.

When you "Load?" (or "Activate?") an ILS approach, the ILS frequency is automatically placed in the standby field of the VLOC window. To use this frequency, simply press the **V** key to place it in the active frequency field.

PROCEDURES



ILS Approach Example

5



5 PROCEDURES


ILS Approach Example




Flying the ILS Approach

When you “Activate?” an ILS approach, automatic switching of the external CDI is enabled (unless turned off from the CDI/Alarms Page). When you are established on the inbound course to the FAF, the external CDI guidance will automatically switch from “GPS” (shown in green text) to “VLOC” (shown in white text). If you have forgotten to activate the ILS frequency (step #4 below), automatic selection of “VLOC” will not occur.

1. Within 30 nautical miles of KFLG, the GNS 430 will switch from enroute mode to terminal mode and the CDI scale will transition from 5.0 to 1.0 nautical miles, full scale deflection.
2. If you haven't already activated the approach (in steps on previous page), be sure to do so when cleared for the approach. See page 69, step #4 for a description of this operation.
3. As you approach the IAF (SHUTR), a waypoint alert (“NEXT DTK 030°”) will appear in the lower right corner of the screen.
4. If you haven't already done so, press  to activate the ILS frequency. If you forget this step, the GNS 430 will display a reminder message (within 3 nm of the FAF) to activate the ILS frequency.
5. As the distance (DIS) to the IAF approaches zero, the alert is replaced by a turn advisory (“TURN TO 030°”).
6. Fly the outbound course (030°), keeping the needle centered on the external CDI (or HSI).
7. Once you have flown approximately one minute past SHUTR intersection, the alert message “START PROC TRN” will appear in the lower right corner of the screen (if you haven't already begun the procedure turn).



{continued}



8. Turn right to a heading of 075° to initiate the procedure turn. The GNS 430 will not guide you through the turn. (The procedure turn is displayed on the map page and indicated as the active leg on the default NAV and active flight plan pages.) The external CDI needle will start moving to the left.
9. After approximately one minute, make a 180° left turn to a heading of 255° to intercept the ILS. The GNS 430 will sequence to the inbound leg and "NEXT DTK 210°" will appear in the lower right corner of the screen. CDI coupling will automatically switch from the "GPS" receiver to the "VLOC" receiver as you complete the inbound turn. (If the ILS frequency has not been activated, per step #4, this automatic CDI switch will not occur.)
10. As the CDI needle starts to center, make a left turn to 210° to track the ILS approach course.

NOTE

From this point on, primary navigation is provided by the VLOC receiver. You may continue to use the GPS receiver for supplemental navigation guidance only. ALSO, when using an external CDI (not an HSI), expect reverse sensing when flying outbound on the approach course or when flying a back course approach.

11. As you approach the FAF (SHUTR), "0.30nm" will appear in the lower left corner of the screen — indicating a CDI scale transition from 1.0 to 0.3 nautical miles, full scale deflection. (This scale transition applies only to the default NAV page's on-screen CDI, since the external CDI or HSI is now coupled to the VLOC receiver. GPS approach mode will NOT be activated for precision approaches, since the VLOC receiver MUST be used for primary navigation.)

{continued}

PROCEDURES

ILS Approach Example

5



5

PROCEDURES

ILS Approach
Example


12. Also as you approach SHUTR, a waypoint alert ("NEXT DTK 210°") will appear in the lower right corner of the screen.

13. As you cross SHUTR, the destination sequences to the MAP ("RW21", the runway threshold). With the needle on the external CDI (or HSI) centered, fly toward the MAP, observing the altitude minimums dictated by the approach plate. (When viewing the map page, you'll note that the final course segment is displayed in magenta — the active leg of the flight plan always appears in magenta — and a dashed line extends the course beyond the MAP.)

14. As you approach the MAP, a waypoint alert ("APPRCHING WPT") will appear in the lower right corner.

15. As you cross the MAP, "SUSP" will appear above the **OBS** key, indicating that automatic sequencing of approach waypoints will be suspended at the MAP. A "from" indication will be displayed on the CDI and default NAV page, but course guidance along the final approach course will continue. Do NOT follow this extended course. Follow published missed approach procedures using the **OBS** key to initiate the missed approach sequence, as outlined on page 72.

DO NOT USE FOR
NAVIGATION



NOTE


In addition to using the **OBS** key to initiate the missed approach sequence, you may wish to press the **CDI** key to manually switch external CDI output to the GPS receiver. "GPS" will be indicated above the **CDI** key. If you leave the external CDI output on "VLOC" and are using an external CDI (not an HSI), expect reverse sensing on the back course of the ILS.

Points to Remember for ALL Approaches

- The GNS 430 is designed to complement your printed approach plates and vastly improve situational awareness throughout the approach. However, *you must always fly an approach as it appears on the approach plate.*
- The active leg (or the portion of the approach currently in use) is depicted in magenta on the Map Page. As you fly the approach, the GNS 430 will automatically sequence through each leg of the approach unless "SUSP" appears above the OBS key. "SUSP" indicates that automatic sequencing of approach waypoints is suspended on the current leg and normally appears at holding patterns and upon crossing the missed approach point (MAP).

Points to Remember for Localizer-based Approaches

- The default factory setting will allow the CDI output to automatically switch from the GPS receiver to the VLOC receiver. If the "ILS CDI Capture" setting is changed to "Manual", you must determine when to select "GPS" or "VLOC" guidance during the approach. Remember, "VLOC" is required for the final course segment from final approach fix (FAF) to MAP.
- If the CDI output has not automatically switched from GPS to ILS by 2.0 nautical miles prior to the FAF, you must manually switch to the VLOC receiver by pressing **CDI**. Verify that "VLOC" is displayed directly above the **CDI** key.
- Automatic switching of CDI output is available for ILS, localizer, SDF and LDA approaches. Automatic CDI switching is *not* available for backcourse approaches.
- When flying an approach with the autopilot coupled, you must monitor system functions at all times and verify that the autopilot and external CDI (or HSI) switches to the VLOC receiver with sufficient time to capture and track the approach course. Switching to "VLOC" late in the approach may not provide the autopilot enough time to respond and intercept the approach course prior to the FAF (depending upon the performance characteristics of your autopilot and aircraft). In such cases, you should manually fly the approach or refer to the documentation provided with your autopilot.



5

PROCEDURES**Additional Approach
Information**

- When an ILS approach is first selected and "loaded" (or "activated"), the ILS frequency is automatically placed in the standby field. *In order to fly the final course segment of the ILS approach, you must place the ILS frequency in the active frequency field by pressing .* If you forget to do this, a "Select appropriate frequency for approach" message will appear within 3.0 nautical miles of the FAF.
- When flying a localizer-based approach (other than backcourse) with automatic CDI switching enabled:
 1. "GPS" guidance is used while flying outbound and on the initial portion of the procedure turn.
 2. "VLOC" guidance is used on the remainder of the approach from the time you turn inbound on the procedure turn.
 3. The localizer frequency must be active to use "VLOC" guidance.
- When flying a localizer-based approach with automatic CDI switching disabled:
 1. You may select "VLOC" guidance at any point on the approach prior to reaching the FAF.
 2. The localizer frequency must be active to use "VLOC" guidance.



PROCEDURES

**Additional Approach
Information**

5

This page intentionally blank.

6

WPT PAGES
WPT Page Group

Please note that your GNS 430 uses ICAO identifiers for all airports. All U.S. airport identifiers which contain only letters use the prefix 'K'. For example, Los Angeles International is KLAX under the ICAO standard. Other airports, such as Otten Memorial (3VS), that contain numbers in the identifier, do not require the 'K' prefix. Many foreign countries use two letter prefixes. For more information on ICAO identifiers, contact:


Document Sales Unit
International Civil Aviation Organization
999 University Street
Montreal, Quebec
Canada H3C 5H7

Section 6

WPT Pages

WPT Page Group

Section 2 introduced the GNS 430's main page groups—NAV, WPT, AUX, NRST—and described each page in the NAV group. This second page group (WPT) provides information for the thousands of airports, VORs, NDBs, intersections, runways, frequencies and procedures stored on your Jeppesen NavData® card. A WPT page is also provided to display information for up to 1,000 user-created waypoints.



To quickly select a WPT page:

1. From any page, press and hold **CLR** to select the default NAV page. (You may skip this step if you are already viewing any of the main pages. See page 27.)
2. Rotate the large right knob (⊙) to select the WPT page group. "WPT" will appear in the lower right corner of the screen.
3. Rotate the small right knob (⊙) to select the desired WPT page.

The WPT page group includes ten pages. While viewing any WPT page, rotate the small right knob (PUSH CRB) to select a different WPT page. The first six pages provide detailed information for the selected airport: location, runways, frequencies, approaches, arrivals, and departures. The last four pages provide information for intersections, NDBs, VORs and user-created waypoints.

After a WPT page is selected, information for a waypoint may be viewed by entering the identifier (or name) of the desired waypoint. Airports, NDBs and VORs may be selected by identifier, facility name or location (city).

To enter a waypoint identifier:

1. Select the desired WPT page and press the small right knob (PUSH CRB) to activate the cursor.
2. Rotate the small right knob (PUSH CRB) to select the first character of the waypoint's identifier.
3. Rotate the large right knob (CRB) to select the next character field.
- 4a. Rotate the small right knob (PUSH CRB) to select the desired character.
5. Repeat steps 3 and 4 until the identifier is selected, then press **ENT**.
- 6a. To remove the flashing cursor, press the small right knob (PUSH CRB).

To enter a waypoint facility name or city location:

1. Select the airport location page, NDB page or VOR page from the WPT page group. (See page 94.)
2. Press the small right knob (PUSH CRB) to activate the cursor.
3. Rotate the large right knob (CRB) to select the facility name or location (city) field.
- 4b. Rotate the small right knob (PUSH CRB) to select the desired character.
5. Rotate the large right knob (CRB) to select the next character field.
- 6b. Repeat steps 4 and 5 until the facility name or location is selected, then press **ENT**.
7. To remove the flashing cursor, press the small right knob (PUSH CRB).

WPT PAGES

Waypoint Identifier, Facility, Location

6

4 b

COM 118.000	APT MYAW Private
119.200	FACILITY & CITY NAME
	WALKER S CAY
	BACO_BAHAMAS
VLOC 111.50	POSITION ELEV FUEL
111.90	N 27°16.00' 10% Jet
ENR	APR VFR RADAR No ARSPC
GPS	HSG WPT 000000000




6 b

COM 118.000	APT KABQ Public
119.200	FACILITY & CITY NAME
	ALBUQUERQUE INTL SUNPOR
	ALBUQUERQUE_NM
VLOC 111.50	POSITION ELEV FUEL
111.90	N 35°02.42' 5350' Avgas Jet
ENR	APR ILS RADAR Yes ARSPC C
GPS	HSG WPT 000000000

6 b

COM 118.000	VOR ABQ Hi Alt.
119.200	FACILITY, CITY & REGION
	ALBUQUERQUE
	ALBUQUERQUE_NM
VLOC 111.50	SW USA VAR E013°
111.90	POSITION FREQ
ENR	N 35°02.63' 113.20
GPS	HSG WPT 000000000

6

WPT PAGES**Duplicate Waypoints****Duplicate Waypoints**

Once the identifier, facility name or location is entered, all six airport pages will display information for the selected airport. As you enter an identifier, facility name or location, the GNS 430's Spell'N'Find™ feature will scroll through the database, displaying those waypoints matching the characters you have entered to that point. If duplicate entries exist for the entered facility name or location, additional entries may be viewed by continuing to rotate the small right knob (PUSH CRN) during the selection process (see page 95). If duplicate entries exist for an entered identifier, a *duplicate waypoint page* will appear once you select the identifier (by pressing ENT).

To select a facility name or location, where duplicate entries exist:

1. Select the desired facility name or location, following the steps on page 95.
- 2a. As you spell the facility name or location, using the small (PUSH CRN) and large (PUSH CRN) right knobs, the GNS 430's Spell'N'Find feature will select the first entry in the database based upon the characters you have entered up to that point.
- 3a. Continue rotating the small right knob (PUSH CRN) to scroll through any additional database listings for the selected facility name or location. You can scroll backwards with the small right knob (PUSH CRN) if you scroll past the desired facility name or location.
4. Press ENT to select the desired facility name or location.
5. To remove the flashing cursor, press the small right knob (PUSH CRN).

To select a waypoint identifier from a list of duplicates:

1. Select the desired airport or navaid identifier following the steps on page 95.
- 2b. A duplicate waypoints window will appear. Rotate the large right knob (PUSH CRN) to select the desired waypoint and press ENT.
- 3b. To remove the flashing cursor, press the small right knob (PUSH CRN).

Airport Location Page

Airport Identifier, Symbol and Type

Latitude/Longitude

Best Available Approach and Radar Coverage

Facility Name and Location (city)

Field Elevation, Available Fuels and Airspace Type

First Page in WPT group

COM	APT	KPHX	Public
121.200	FACILITY & CITY NAME		
119.750	PHOENIX SKY HARBOR INTL		
	PHOENIX AZ		
VLOC	POSITION	ELEV	FUEL
111.50	N 33°26.16'	1130'	Avgas
111.75	W112°00.57'		Jet
TERM	APR	ILS	RADAR Yes ARSPC B
GPS	HSG	HPT	0000000000

The *airport location page* displays the latitude, longitude, and elevation of the selected airport. The *airport location page* also displays facility name and location, as well as fuel availability, available approaches, radar coverage and airspace type. The following descriptions and abbreviations are used:

- Type— Usage type: Public, Military or Private
- Position— Latitude/Longitude (degrees/minutes or degrees/minutes/seconds), MGRS or UTM/UPS
- Elevation— In feet or meters
- Fuel— For public-use airports, the available fuel type(s) are: Avgas (80-87/100LL/100-130/Mogas), Jet, or None
- Approach— Best available approach: ILS, MLS, LOC, LDA, SDF, GPS, VOR, RNAV ("RNV"), LORAN ("LOR"), NDB, TACAN ("TCN"), Helicopter ("HEL"), or VFR
- Radar— Radar coverage: Yes or No
- Airspace— Control environment: Class C, CTA, TMA, TRSA, Class B or none

WPT PAGES

Airport Location

6


COM	APT	KDVT	Public
121.200	FACILITY & CITY NAME		
119.750	PHOENIX DEER VALLEY MUN		
	PHOENIX AZ		
VLOC	POSITION	ELEV	FUEL
111.50	N 33°41.30'	1480'	Avgas
111.75	W112°04.95'		Jet
ENR	APR	GPS	RADAR Yes ARSPC B
GPS	HSG	HPT	0000000000

COM	APT	P18	Military
121.200	FACILITY & CITY NAME		
119.750	PAPAGO AAF		
	PHOENIX AZ		
VLOC	POSITION	ELEV	FUEL
111.50	N 33°28.31'	1250'	Jet
111.75	W111°57.82'		
ENR	APR	VFR	RADAR No ARSPC B
GPS	HSG	HPT	0000000000

6

WPT PAGES

Airport Runways



Airport Runway Page

Airport Identifier,
Symbol and Type

Map Image

Runway Surface
and Lighting



Runway
Designations

Runway Length
and Width

Second Page
in WPT group

The *airport runway page* displays runway designations, length, surface type and lighting for the selected airport. A map image of the runway layout and surrounding area is also displayed on the *airport runway page*. The map image scale appears in the lower left corner and is adjustable using the **▽ RNG △** key. For airports with multiple runways, information for each runway is available.

To display information for each additional runway:

1. Press the small right knob (PUSH CURSR) to activate the cursor.
- 2a. Rotate the large right knob (RNG) to place the cursor on the runway designation field.
3. Rotate the small right knob (PUSH CURSR) to display a window listing all runways for the selected airport.
4. Continue rotating the small right knob (PUSH CURSR) to select the desired runway.
5. Press **ENT** to display information for the selected runway on the airport runway page.
6. To remove the flashing cursor, press the small right knob (PUSH CURSR).

To adjust the scale of the map image:

1. Press the down arrow side of the **▽ RNG △** key to display a smaller map area.
- 2b. Press the up arrow side of the **▽ RNG △** key to display a larger map area.

The following descriptions and abbreviations are used on the airport runway page:

- Type— Usage type: Public, Military or Private
- Surface— Runway surface types include: Hard, Turf, Sealed, Gravel, Dirt, Soft, Unknown or Water
- Lighting— Runway lighting types include: No Lights, Part Time, Full Time, Unknown or Frequency (for pilot-controlled lighting)

Airport Frequency Page




The *airport frequency page* displays radio frequencies and frequency types for the selected airport, as well as sector and altitude restrictions (where applicable). If the selected airport has a localizer-based approach, the localizer frequency(s) is also listed on the *airport frequency page*. The *airport frequency page* may be used to quickly select and tune a COM or VLOC frequency.

To scroll through the frequency list and tune to a desired frequency on the list:

1. Press the small right knob (PUSH) to activate the cursor.


{continued}



6

WPT PAGES

Airport Frequencies



2a. Rotate the large right knob (⦿) to scroll through the list, placing the cursor on the desired frequency. If there are more frequencies in the list than can be displayed on the screen, a scroll bar along the right-hand side of the screen will indicate where you are within the list.

3a. Press **ENT** to place the selected frequency in the standby field of the COM or VLOC window.

4. To remove the flashing cursor, press the small right knob (⦿).

Some listed frequencies may include designations for limited usage, as follows:

“TX” - transmit only

“RX” - receive only

“PT” - part time frequency

If a listed frequency has sector or altitude restrictions, the frequency will be preceded by an “Info?” designation.

To view usage restrictions for a frequency:

1. Rotate the large right knob (⦿) to place the cursor on the “Info?” designation directly to the left of the desired frequency.

2b. Press **ENT** to display the restriction information.

3b. To return to the airport frequency page, press **ENT**.

The following descriptions and abbreviations are used on the airport frequency page:

- Type— Usage type: Public, Military or Private
- Frequency— Communication frequencies which may include restrictions:

Approach	Arrival	Class B
Class C	CTA	Departure
TMA	Terminal	TRSA

Communication frequencies without restrictions:

ATIS	ASOS	AWOS
Center	Clearance	Gate
Control	Ground	Helicopter
Multicom	Pre-taxi	Radar
Ramp	Other	Tower
	Unicom	

Navigation frequencies:

ILS	LOC
-----	-----

WPT PAGES Airport Frequencies

6


COM	APT	KPHX	Public
121.200			
118.700	ATIS	121.200	
	ATIS	124.300	
VLOC	Clearance	118.100	
111.50	Ground	119.750	
111.75	Ground	132.550	
TERH			
GPS	MSG	HPT	00000000

COM	APT	KPHX	Public
121.200			
118.700	Class B	Info?	120.700
	Class B	Info?	123.700
VLOC	Class B	Info?	124.100
111.50	ILS 08R		111.500
111.75	ILS 26R		111.750
TERH			
GPS	MSG	HPT	00000000

6

WPT PAGES

Airport Approaches



Airport Approach Page

Airport Identifier,
Symbol and Type

Map Image



Approach
Procedure Name

Transitions: IAFs,
Feeder Routes and
Vectors-to-Final

Fourth Page
in WPT group

The *airport approach page* shows the available approach procedures for the selected airport. Where multiple initial approach fixes (IAFs) and feeder routes are available, that information may also be displayed. A map image provides a layout diagram for each approach and transition.

To scroll through the available approaches and transitions:

1. Press the small right knob (PUSH) to activate the cursor.
2. Rotate the large right knob (ROT) to place the cursor on the approach (APR) procedure name field.
3. Rotate the small right knob (PUSH) to display a window of available approaches for the selected airport. Continue rotating the small right knob (PUSH) to select the desired approach.
4. Press **ENT**. The cursor moves to the transitions (TRANS) field.
5. Rotate the small right knob (PUSH) to display a window of available transitions. Continue rotating the small right knob (PUSH) to select the desired transition or select "VECTORS" for guidance only along the final course segment of the approach.
6. Press **ENT**. To remove the flashing cursor, press the small right knob (PUSH).

NOTE

Not all approaches in the database are approved for GPS use. As you select an approach, a “GPS” designation to the right of the procedure name indicates the procedure can be flown using the GPS receiver. Some procedures will not have this designation, meaning the GPS receiver may be used for supplemental navigation guidance only. ILS approaches, for example, must be flown by tuning the VLOC receiver to the proper frequency and coupling the VLOC receiver to the external CDI (or HSI).

Airport Approach Page Options

The following options are available for the *airport approach page*, by pressing the **MENU** key:

Load into Active FPL? allows you to load the selected approach into the active flight plan—without activating it. This performs the same operation as selecting “Load?” from the *procedures page* “Select Approach?” option. See page 66.

To load an approach from the airport approach page:


1. Select the desired approach and transition using the steps outlined on page 66.
2. Press **MENU** to display the airport approach page options.
3. Rotate the large right knob (⊖) to highlight “Load into Active FPL?” and press **ENT**.
4. The active flight plan page will appear. Press **FPL** to return to the airport procedures page.

Load and Activate? allows you to load the selected approach into the active flight plan and activate navigation guidance to the approach transition. See page 67.


To load and activate an approach from the airport approach page, follow the steps above, but select “Load and Activate?” in step #3.

WPT PAGES

Airport Approaches

6**1****3**

6

WPT PAGES**Airport Arrivals****Airport Arrival Page**

Airport Identifier,
Symbol and Type

Map Image



Arrival Procedure
Name

Transitions

Runways Associated
with Arrival

Fifth Page
in WPT group

The *airport arrival* page shows the available Airport Standard Terminal Arrival (STAR) procedures for the selected airport. Where multiple transitions or runways are associated with the arrival procedure, that information may also be displayed. A map image provides a layout diagram for each arrival, transition and runway.

To scroll through the available arrivals:

1. Press the small right knob (PUSH) to activate the cursor.
2. Rotate the large right knob (PUSH) to place the cursor on the arrival (ARVL) procedure name field.
3. Rotate the small right knob (PUSH) to display a window of available arrivals for the selected airport. Continue rotating the small right knob (PUSH) to select the desired arrival.
4. Press **ENT**. The cursor moves to the transitions (TRANS) field.
5. Rotate the small right knob (PUSH) to display a window of available transitions. Continue rotating the small right knob (PUSH) to select the desired transition.
6. Press **ENT**. The cursor moves to the runway field.

{continued}

7. Rotate the small right knob (PUSH CRSB) to display a window of available runways. Continue rotating the small right knob (PUSH CRSB) to select the desired runway. ("ALL" may appear in the runway field, indicating the arrival procedure applies to all runways. For airports with parallel runways, "B" may appear at the end of the runway designation to indicate the arrival procedure applies to both runways.)

8. Press **ENT**. To remove the flashing cursor, press the small right knob (PUSH CRSB).

Airport Arrival Page Options

The following option is available for the *airport arrival page*, by pressing the **MENU** key:

Load into Active FPL² allows you to load the selected arrival into the active flight plan. This is identical to loading an arrival procedure from the *procedures page*, as described on page 66.

To load an arrival procedure from the airport arrival page:

1. Select the desired arrival, transition and runway using the steps above.
2. Press **MENU** to display the airport arrival page options.
3. Press **ENT** to select the "Load into Active FPL?" option.
4. The active flight plan page will appear. Press **FPL** to return to the airport arrival page.


WPT PAGES

Airport Arrivals

6



6 *WPT PAGES* Airport Departures



Airport Departure Page

Airport Identifier,
Symbol and Type

Map Image



Departure

Procedure Name

Runways Associated
with Departure

Transitions

Sixth Page
in WPT group

The *airport departure page* shows the available Airport Standard Instrument Departure (SID) procedures for the selected airport. Where multiple runways or transitions are associated with the departure procedure, that information may also be displayed. A map image provides a layout diagram for each departure, runway and transition.

To scroll through the available departures:

1. Press the small right knob (PUSH ORP) to activate the cursor.
2. Rotate the large right knob (PUSH ORP) to place the cursor on the departure (DEP) procedure name field.
3. Rotate the small right knob (PUSH ORP) to display a window of available departures for the selected airport. Continue rotating the small right knob (PUSH ORP) to select the desired departure.
4. Press ENT. The cursor moves to the runway field.

{continued}

5. Rotate the small right knob (PUSH CRB) to display a window of available runways. Continue rotating the small right knob (PUSH CRB) to select the desired runway. ("ALL" may appear in the runway field, indicating the departure procedure applies to all runways. For airports with parallel runways, "B" may appear at the end of the runway designation to indicate the departure procedure applies to both runways.)
6. Press **ENT**. The cursor moves to the transitions (TRANS) field.
7. Rotate the small right knob (PUSH CRB) to display a window of available transitions. Continue rotating the small right knob (PUSH CRB) to select the desired transition.
8. Press **ENT**. To remove the flashing cursor, press the small right knob (PUSH CRB).

Airport Departure Page Options

The following option is available for the *airport departure page*, by pressing the **MENU** key:

Load into Active FPL? allows you to load the selected departure into the active flight plan. This is identical to loading a departure procedure from the *procedures page*, as described on page 66.

To load a departure procedure from the airport departure page:

1. Select the desired departure, runway and transition using the steps above.
2. Press **MENU** to display the airport departure page options.
3. Press **ENT** to select the "Load into Active FPL?" option.
4. The active flight plan page will appear. Press **FPL** to return to the airport departure page.


WPT PAGES

Airport Departures

6



5



3

6

WPT PAGES

Intersections

COH 118.550	INT CATTS ▲		
VLOC 119.075	REGION N CEN USA	NEAREST VOR MHK	
VLOC 111.30	POSITION N 39°18.07'	RAD 062°	DIS 24.3 ⁿ
VLOC 110.20	W096°11.24'		
ENR			
VLOC	HPT 000000 000		

COH 123.000	INT SUEEY ▲	Done?	
VLOC 122.950	REGION N CEN USA	NEAREST VOR RZC	
VLOC 116.40	POSITION N 36°36.17'	RAD 026°	DIS 24.5 ⁿ
VLOC 108.80	W093°52.28'		
ENR			
VLOC	HPT 000000 000		

COH 122.900	INT HAWGG ▲		
VLOC 127.200	REGION ALASKA	NEAREST VOR BIG	
VLOC 114.90	POSITION N 64°22.04'	RAD 282°	DIS 35.6 ⁿ
VLOC 115.10	W146°47.16'		
ENR			
VLOC	HPT 000000 000		

Intersection Page

Intersection Identifier and Symbol 120.800	INT OTTER ▲	Nearest VOR and Symbol TOP
Region/Country 128.250	REGION N CEN USA	Radial and Distance from Nearest VOR RAD 173° DIS 16.7 ⁿ
Latitude/Longitude Position 111.60	POSITION N 38°51.50'	
117.80	W095°32.01'	
ENR		
GPS	HSG	HPT 000000 000

Seventh Page in WPT group


The *intersection page* displays the latitude, longitude, region and country for the selected intersection. The *intersection page* also displays the identifier, radial and distance from the nearest VOR, VORTAC or VOR/DME. The following descriptions and abbreviations are used:

- Position— Latitude/Longitude (degrees/minutes or degrees/minutes/seconds), MGRS or UTM/UPS
- RAD— Radial from nearest VOR in degrees magnetic or degrees true (depending upon unit configuration)
- DIS— Distance from nearest VOR, in nautical miles/statute miles/kilometers (depending upon unit configuration)

NOTE

The VOR displayed on the intersection page is the nearest VOR, not necessarily the VOR used to define the intersection.

Intersections may only be selected by identifier, as described on page 95.

NDB Page

The *NDB page* displays the facility name, city, region/country, latitude and longitude for the selected NDB. The *NDB page* also displays the frequency and a weather broadcast indication (if applicable). The following descriptions and abbreviations are used:

- **Symbol**— See page 31 for a graphic illustration of available NDB symbols
- **Position**— Latitude/Longitude (degrees/minutes or degrees/minutes/seconds), MGRS or UTM/UPS
- **FREQ**— Frequency in kilohertz (kHz)
- **Wx Brdcast**— Weather information is broadcast on the selected facility's frequency

As mentioned on page 95, NDBs may be selected by identifier, facility name or location (city).

WPT PAGES

NDBs

6



6 *WPT PAGES* VORs

COM	VOR FMG	Hi Alt.
118.700	FACILITY, CITY & REGION	
122.900	MUSTANG	
VLOC	RENO NV	
117.90	SW USA	
114.10	POSITION	FREQ
ENR	N 39°31.87'	117.90
	W119°39.36'	Wx Brdcst
GPS	HSG	HPT 00000000

COM	VOR WTN	Hi Alt.
118.700	FACILITY, CITY & REGION	
122.900	WARTON	
VLOC	U KINGDOM	
117.90	VAR W006°	
114.10	POSITION	FREQ
ENR	N 53°44.41'	113.20
	W002°53.57'	
GPS	HSG	HPT 00000000

VOR Page

VOR Identifier
and Symbol

Facility Name,
City and
Region/Country

Latitude/Longitude
Position

COM	VOR POM	Low Alt.
118.200	FACILITY, CITY & REGION	
123.000	POMONA	
VLOC	POMONA CA	
112.20	SW USA	
110.40	POSITION	FREQ
ENR	N 34°04.70'	110.40
	W117°47.22'	Wx Brdcst
GPS	HSG	HPT 00000000

Magnetic
Variation

Frequency and
Weather Broadcast
Indication

Ninth Page
in WPT group

The *VOR page* displays the facility name, city, region/country, magnetic variation, latitude and longitude for the selected VOR. The *VOR page* also displays the frequency and a weather broadcast indication (if applicable). The following descriptions and abbreviations are used:


- Symbol— See page 31 for a graphic illustration of available VOR symbols
- VAR— Magnetic variation in degrees
- Position— Latitude/Longitude (degrees/minutes or degrees/minutes/seconds), MGRS or UTM/UPS
- FREQ— Frequency in megahertz (MHz)
- Wx Brdcst— Weather information is broadcast on the selected facility's frequency

As mentioned on page 95, VORs may be selected by identifier, facility name or location (city). The *VOR page* may also be used to quickly tune the VLOC receiver to the selected VOR's frequency.

To select a VOR frequency from the VOR page:

1. Select the VOR page from the WPT page group, as described on page 94.
2. Press the small right knob (PUSH) momentarily to place the cursor on the VOR identifier field. If you wish to select another VOR, use the small (PUSH) and large (PUSH) right knobs and press **ENT** when finished.
3. Rotate the large right knob (PUSH) to highlight the frequency field and press **ENT** to place the frequency in the standby field of the VLOC window.
4. To activate the standby VLOC frequency, press **V**.

User Waypoint Page



In addition to the airport, VOR, NDB and intersection information contained in your Jeppesen NavData® card, the GNS 430 allows you to store up to 1,000 user-defined waypoints. The user waypoint page displays the waypoint name (up to five characters long), identifier and radial from two reference waypoints, distance from one reference waypoint, along with the user waypoint's latitude/longitude position.


WPT PAGES

User Waypoints

6



6

WPT PAGES**Creating
User Waypoints**

The following descriptions and abbreviations appear on the *user waypoint page*:

- REF WPT— Reference waypoint identifier (name)
- RAD— Radial from reference waypoint, in degrees magnetic or degrees true (depending upon unit configuration)
- DIS— Distance from reference waypoint, in nautical miles/statute miles/kilometers (depending upon unit configuration)
- Position— Latitude/Longitude (degrees/minutes or degrees/minutes/seconds), MGRS or UTM/UPS

User waypoints may only be selected by name (identifier), as described on page 95.

Creating User Waypoints

User waypoints may be created from the *user waypoint page* or the *map page*. To create a new user waypoint, simply enter its name (identifier) and position, or reference another waypoint by radial and distance.

To create a new user waypoint by entering its latitude/longitude position:

1. With the user waypoint page displayed, press the small right knob (PUSH CRSEL) to activate the cursor.
2. Use the small (PUSH CRSEL) and large (PUSH CRSEL) right knobs to enter a name for the new waypoint and press ENT. Your present position appears in the position field at the bottom of the page. To create a waypoint at your present position, rotate the large right knob (PUSH CRSEL) to highlight "Create?" and skip to step #6.
3. Rotate the large right knob (PUSH CRSEL) to highlight the position field at the bottom of the page.
4. Use the small (PUSH CRSEL) and large (PUSH CRSEL) right knobs to enter the position coordinates for the new waypoint.
5. Press ENT to accept the selected position.
6. The cursor moves to "Create?". Press ENT to add the new waypoint to memory.
7. Press the small right knob (PUSH CRSEL) to remove the flashing cursor.

To create a new user waypoint by referencing an existing waypoint:

1. With the user waypoint page displayed, press the small right knob (PUSH) to activate the cursor.
2. Use the small (PUSH) and large (PUSH) right knobs to enter a name for the new waypoint and press **ENT**.
3. Rotate the large right knob (PUSH) to highlight the first reference waypoint (REF WPT) field.
4. Use the small (PUSH) and large (PUSH) right knobs to enter the identifier of the reference waypoint. The reference waypoint can be an airport, VOR, NDB, intersection or another user waypoint. Press **ENT** to accept the selected identifier.
5. The cursor moves to the radial (RAD) field. Use the small (PUSH) and large (PUSH) right knobs to enter the radial from the reference waypoint to the new user waypoint. Press **ENT** to accept the selected radial.
6. The cursor moves to the distance (DIS) field. Use the small (PUSH) and large (PUSH) right knobs to enter the distance from the reference waypoint to the new user waypoint. Press **ENT** to accept the selected distance.
7. Rotate the large right knob (PUSH) to highlight "Create?" and press **ENT**.
8. Press the small right knob (PUSH) to remove the flashing cursor.

NOTE

The GNS 430 allows you to create a new user waypoint at a defined radial and distance from your present position. To reference your present position, follow the steps above, but press **CLR** in step #4. "PPOS" will appear in the reference waypoint (REF WPT) field to indicate that radial and distance information will reference your present position.

The second reference waypoint field (REF WPT) is a temporary reference only—not a reference that will be stored with the user waypoint. By default, this field will display a radial from the nearest VOR. However, you can select any waypoint—by identifier—to use as a reference in this field.

Your GNS 430 can store user-defined waypoints which are generated from other equipment in your panel. For example, an EFIS equipped with joystick inputs can be used to create user waypoints which will (if your installation supports this) automatically transfer to your GNS 430.

WPT PAGES

Creating User Waypoints

6

5


COH 123.000 122.950	USR HOGSC	REF WPT BVDAM	RAD 160.3°	DIS 6.8 ⁿ _m
VLOC 116.40 108.80	DAK	042.3°	POSITION N 36°19.01' W093°48.10'	
ENR	Create?			
GPS	HSG	HPT	000000000	

7

COH 123.000 122.950	USR HOGSC	REF WPT BVDAM	RAD 160.0°	DIS 7.0 ⁿ _m
VLOC 116.40 108.80	DAK	042.8°	POSITION N 36°18.81' W093°47.98'	
ENR	Create?			
GPS	HSG	HPT	000000000	

6 *WPT PAGES*

Creating / Modifying User Waypoints



Creating User Waypoints from the Map Page

The *map page* and panning target pointer (see page 33) provide a quick means of saving your present position as a user-defined waypoint.

To capture and save your present position as a user waypoint:

- 1a. With the map page displayed, press the small right knob (PUSH ORB) to activate the panning function. The target pointer will appear at your present position.
- 2a. Press ENT to capture the position and display the user waypoint page.
3. A four-digit name is automatically assigned to the waypoint. To change this name, rotate the large right knob (PUSH ORB) to highlight the name field, then use the small (PUSH ORB) and large (PUSH ORB) right knobs to select a new name. Press ENT to accept the selected name.
- 4a. The cursor moves to the "Create?" action field. Press ENT to save the new waypoint.

Modifying User Waypoints

To modify an existing waypoint, select that waypoint on the user waypoint page and enter the new position information directly over the old information.

To modify a user waypoint by changing its latitude/longitude position:

- 1b. With the user waypoint page displayed, press the small right knob (PUSH ORB) to activate the cursor.
- 2b. Use the small (PUSH ORB) and large (PUSH ORB) right knobs to enter the name of the desired waypoint and press ENT.
3. Rotate the large right knob (PUSH ORB) to highlight the position field at the bottom of the page.
- 4b. Use the small (PUSH ORB) and large (PUSH ORB) right knobs to enter the new position coordinates and press ENT to accept the selected position.
5. The cursor moves to the "Modify?" action field. Press ENT to modify the waypoint.
6. Press the small right knob (PUSH ORB) to remove the flashing cursor.

To modify a user waypoint by changing reference waypoint information:

1. With the user waypoint page displayed, press the small right knob (PUSH CRN) to activate the cursor.
2. Use the small (PUSH CRN) and large (PUSH CRN) right knobs to enter the name of the desired waypoint and press ENT.
3. Rotate the large right knob (PUSH CRN) to highlight the first reference waypoint (REF WPT) field, if you wish to change the reference waypoint. Otherwise, continue rotating the large right knob (PUSH CRN) to highlight the radial (RAD) or distance (DIS) field, as desired.
4. Use the small (PUSH CRN) and large (PUSH CRN) right knobs to change the identifier — if desired — of the reference waypoint. The reference waypoint can be an airport, VOR, NDB, intersection or another user waypoint. Press ENT to accept the selected identifier.
5. The cursor moves to the radial (RAD) field. Use the small (PUSH CRN) and large (PUSH CRN) right knobs to change the radial from the reference waypoint, if desired. Press ENT to accept the selected radial.
6. The cursor moves to the distance (DIS) field. Use the small (PUSH CRN) and large (PUSH CRN) right knobs to change the distance from the reference waypoint to the new user waypoint, if desired. Press ENT to accept the selected distance.
7. The cursor moves to the "Modify?" action field. Press ENT to modify the waypoint.
8. Press the small right knob (PUSH CRN) to remove the flashing cursor.

NOTE

If you attempt to modify or delete a waypoint which is currently a direct-to waypoint or the current "from" or "to" waypoint in the active flight plan, the GNS 430 will alert you with the "Can't change an active waypoint" or "Waypoint is active and can't be deleted" message. You must first cancel the direct-to or remove the waypoint(s) from the active flight plan before modifying or deleting the waypoint(s).

WPT PAGES

Modifying User Waypoints

6

4

COM 123.000	USR HOGSC	REF WPT 4M1	RAD 241.4°	DIS 9.8 ⁿ _m
VLOC 116.40	RZC 071.4°	POSITION N 36°18.81' W093°47.98'		
ENR	Modify?			
GPS HSG WPT 000000000				

5

COM 123.000	USR HOGSC	REF WPT 4M1	RAD 241.6°	DIS 9.8 ⁿ _m
VLOC 116.40	RZC 071.4°	POSITION N 36°18.82' W093°47.99'		
ENR	Modify?			
GPS HSG WPT 000000000				

6

COM 123.000	USR HOGSC	REF WPT 4M1	RAD 241.9°	DIS 009.9 ⁿ _m
VLOC 116.40	RZC 071.2°	POSITION N 36°18.84' W093°48.14'		
ENR	Modify?			
GPS HSG WPT 000000000				

6

WPT PAGES**Deleting Waypoints
User Waypoint List****User Waypoint Page Options**

The following *user waypoint page* options are available by pressing the **MENU** key:

View User Waypoint List? displays a list of all user waypoints currently stored in memory.

To view a list of all user waypoints:

1. From the user waypoint page, press **MENU** to display the user waypoint page options.
- 2a. Rotate the large right knob (⊖) to highlight "View User Waypoint List?" and press **ENT**.
3. The top of the user waypoint list will indicate the total number of user waypoints currently used and available memory. If more user waypoints are stored than can be displayed on a single screen, rotate the large right knob (⊖) to scroll through the user waypoint list.
4. Press the small right knob (⊕) to return to the user waypoint page.

Delete User Waypoint? allows you to delete the selected waypoint from memory.

To delete a user waypoint:

1. Select the desired waypoint on the user waypoint page and press **MENU** to display the user waypoint page options.
- 2b. Rotate the large right knob (⊖) to highlight "Delete User Waypoint?" and press **ENT**.

**User Waypoint List**

The user waypoint list allows you to review, modify, rename or delete a selected user waypoint, or to delete all user waypoints currently stored in memory. At the top of the page are indications for number of waypoint locations used and available memory.

To review and/or modify a user waypoint from the user waypoint list:

1. Select the user waypoint list, as described on page 116.
2. Rotate the large right knob (⊖) to highlight the desired user waypoint.
- 3a. Press **ENT** to display the user waypoint page for the selected waypoint. From this page you may review all information defining the waypoint and its position.
- 4a. To modify the waypoint's position or reference waypoint information, follow the steps described on page 114 and 115. (Keep in mind that you've already selected a user waypoint page which displays the desired user waypoint, so you may skip the first two steps of the procedure on page 114 or 115.)
5. To exit the user waypoint page, rotate the large right knob (⊖) to highlight "Done?" and press **ENT**.

To rename a user waypoint from the user waypoint list:

1. Select the user waypoint list, as described on page 116.
2. Rotate the large right knob (⊖) to highlight the desired user waypoint.
- 3b. Use the small (⊖) and large (⊖) right knobs to change the name of the user waypoint. (Enter the new name directly over the old name.) Press **ENT** to accept the new name.
- 4b. A "rename waypoint" confirmation window is displayed. With "Yes?" highlighted, press **ENT** to rename the selected user waypoint.

To delete a user waypoint from the user waypoint list:

1. Select the user waypoint list, as described on page 116.
2. Rotate the large right knob (⊖) to highlight the desired user waypoint.
- 3c. Press **CLR** to display a "delete waypoint" confirmation window.
- 4c. With "Yes?" highlighted, press **ENT** to delete the selected user waypoint.

WPT PAGES

Modifying / Deleting User Waypoints

6



3b




4b



3c

6

WPT PAGES**Deleting All
User Waypoints**

To delete all user waypoints from memory:

1. Select the user waypoint list, as described on page 116.
2. Press **MENU** to display an options window for the user waypoint list.
3. With "Delete All User Waypoints" highlighted, press **ENT**.
4. A "delete all waypoints" confirmation window is displayed. With "Yes?" highlighted, press **ENT** to delete all user waypoints from memory.

Section 7 NRST Pages

NRST Page Group

Section 2 introduced the GNS 430's main page groups—NAV, WPT, AUX, NRST—and described each page in the NAV group. This fourth page group (NRST) provides detailed information for the nine nearest airports, VORs, NDBs, intersections and user waypoints within 200 nm of your current position. In addition, the NRST pages include the five nearest Flight Service Station (FSS) and center (ARTCC/FIR) points of communication, plus alerts you to any Special Use (SUA) or Controlled Airspace you may be in or near.

NAV	WPT	AUX	NRST
6 available pages (see list on pg. 27)	10 available pages (see list on pg. 94)	4 available pages (see list on pg. 135)	8 available pages (see list below)

					
Nearest Airport	Nearest Intersection	Nearest NDB	Nearest VOR	Nearest User	Nearest Center

	
Nearest Flight Service	Nearest Airspace


To quickly select a NRST page:

1. From any page, press and hold **CLR** to select the default NAV page. (You may skip this step if you are already viewing any of the main pages. See page 27.)
2. Rotate the large right knob (⦿) to select the NRST page group. "NRST" will appear in the lower right corner of the screen.
3. Rotate the small right knob (⦿) to select the desired NRST page.

NRST PAGES
NRST Page Group

7

CLR



7

NRST PAGES

Scrolling Through Nearest Lists



Not all nine nearest airports, VORs, NDBs, intersections or user waypoints can be displayed on the corresponding NRST page at one time. The *nearest airport page* displays detailed information for three nearest airports, with a scroll bar along the right-hand side of the page indicating which part of the list is currently being viewed. The *nearest airspace page* displays detailed information for up to three special use or controlled airspace alerts. The NRST pages for VORs, NDBs, intersections, and user waypoints will display five waypoints at a time. The flashing cursor and large right knob (⦿) are used to scroll and view the rest of the waypoints or airspaces in the list.

To scroll through the list of nearest airports, VORs, NDBs, intersections, user waypoints or SUAs:

1. Select the desired NRST page, using the steps outlined on page 119.
2. Press the small right knob (⦿) to activate the cursor.
- 3a. Rotate the large right knob (⦿) to scroll through the list. The scroll bar along the right-hand side of the page will indicate which part of the list is currently being viewed.
4. Press the small right knob (⦿) to remove the flashing cursor.

The *nearest ARTCC* and *nearest FSS* pages present detailed information for up to five nearby facilities—displaying only one facility at a time. Again, the additional information is viewed using the flashing cursor and large right knob (⦿) to scroll through the list.

To scroll through the list of nearest flight service station or center points of communication:

1. Select the desired NRST page, using the steps outlined on page 119.
2. Press the small right knob (⦿) to activate the cursor.
- 3b. Rotate the small right knob (⦿) to scroll through the list.
4. Press the small right knob (⦿) to remove the flashing cursor.

Navigating to a Nearby Waypoint

The NRST pages can be used in conjunction with the GNS 430's direct-to function to quickly set a course to a nearby facility. This feature can be a real time saver compared to retrieving information from the database using the WPT pages. More importantly, it instantly provides navigation to the nearest airport in case of an in-flight emergency.

To select a nearby airport, VOR, NDB, intersection or user waypoint as a direct-to destination:

1. Use the flashing cursor to scroll through a NRST page list and highlight the desired nearest waypoint, as outlined on page 120.
2. Press **[->]** to display the select direct-to waypoint page.
3. Press **[ENT]** to accept the selected waypoint's identifier and press **[ENT]** a second time (with "Activate?" highlighted) to begin navigating to the selected waypoint.

Nearest Airport Page

The *nearest airport page* displays the identifier, symbol, bearing and distance to the nine nearest airports (within 200 nautical miles of your present position). For each airport listed, the *nearest airport page* also indicates the best available approach, common traffic advisory frequency (CTAF) and the length of the longest runway.

Diagram illustrating the Nearest Airport page layout with callouts:

- Airport Identifier, Symbol, Bearing To and Distance To:** Points to the first column of data (e.g., 51K, KLWC, KIXD).
- Best Available Approach:** Points to the 'APR' column (e.g., VFR, ILS).
- Scroll Bar:** Points to the vertical bar on the right side of the airport list.
- Tower or CTAF Frequency and Longest Runway:** Points to the 'twr' and 'rwy' columns (e.g., 118.300, 7300).
- First Page in NRST group:** Points to the bottom of the screen where 'NRST' is displayed.

NRST PAGES Nearest Airports

7


Three screenshots illustrating the steps to select a nearest airport:

- Step 1:** The 'NEAREST VOR' page displays a list of nearby airports (ATL, PDK, DOB, RMG, LGC) with their bearing, distance, and frequency. The 'NRST' indicator is at the bottom.
- Step 2:** The 'SELECT WAYPOINT' page shows the selected airport (PDK) and its details (SE USA, PEACHTREE, ATLANTA GA). The 'Activate?' prompt is visible.
- Step 3:** The 'SELECT WAYPOINT' page shows the selected airport (PDK) and its details (SE USA, PEACHTREE, ATLANTA GA). The 'Activate?' prompt is visible.

7

NRST PAGES

Nearest Airports



The *nearest airport page* can be configured to exclude shorter runways or undesirable runway surface types, so that the corresponding airports do not appear on the list. You may wish to use this feature to exclude seaplane bases or runway lengths which would be difficult or impossible to land upon. See page 160 for additional details.

The *nearest airport page* may be used to quickly tune the COM transceiver to a nearby airport. The selected frequency is placed in the standby field of the COM window and activated using the **ENT** key.

To quickly tune the common traffic advisory frequency (CTAF) from the nearest airport page:

1. Select the nearest airport page, using the steps outlined on page 119.
2. Press the small right knob (**PUSH CRN**) to activate the cursor.
3. Rotate the large right knob (**CRN**) to scroll through the list, highlighting the COM frequency associated with the desired airport.
4. Press **ENT** to place the selected frequency in the standby field of the COM window.
5. Press **CRN** to activate the selected frequency.
6. Press the small right knob (**PUSH CRN**) to remove the flashing cursor.

Additional communication frequencies, runway information and more is available from the *nearest airport page* by highlighting the identifier of the desired airport and pressing **ENT**.

To view additional information for a nearby airport:

1. Select the nearest airport page, using the steps outlined on page 119.
2. Press the small right knob (PUSH CRSR) to activate the cursor.
3. Rotate the large right knob (PUSH CRSR) to scroll through the list, highlighting the identifier of the desired airport.
4. Press **ENT** to display the airport location page for the selected airport.
5. To view additional WPT pages for the selected airport (including the airport runway and airport frequency pages) press the small right knob (PUSH CRSR) to remove the flashing cursor. Rotate the small right knob (PUSH CRSR) to display the additional WPT pages. When finished, press the small right knob (PUSH CRSR) to return the flashing cursor to the screen.
6. To return to the nearest airport page, verify that "Done?" is highlighted by the flashing cursor and press **ENT** (or press **CLR**).

Nearest Intersection Page

The *nearest intersection page* displays the identifier, symbol, bearing and distance to the nine nearest intersections (within 200 nautical miles of your present position).

To view additional information for a nearby intersection, start from the nearest intersection page and follow steps 2 through 4 above.

Nearest NDB Page

The *nearest NDB page* displays the identifier, symbol, bearing, distance and frequency to the nine nearest NDBs (within 200 nautical miles of your present position).

To view additional information for a nearby NDB, start from the nearest NDB page and follow steps 2 through 4 above.

Nearest VOR Page

The *nearest VOR page* displays the identifier, symbol, bearing and distance to the nine nearest VORs (within 200 nautical miles of your present position). For each VOR listed, the *nearest VOR page* also indicates the frequency and may be used to quickly tune the VLOC receiver to the nearby VOR. The selected frequency is placed in the standby field of the VLOC window and activated using the **V** key.

NRST PAGES

Nearest VORs, NDBs and Intersections

7

3

NEAREST AIRPORT			
COM	APT	BRG	DIS
118.500	KATL	003°	0.0m
119.400	twr	119.100	11800%
VLOC	KFTY	334°	9.6m
109.90	twr	118.500	5700%
116.90	8A9	243°	12.3m
ENR	uni	123.000	2600%
GPS HSG NRST 00000000			

4

COM	APT	Public Done?	
118.500	KFTY	FACILITY & CITY NAME	
119.400	FULTON CO BROWN		
VLOC	ATLANTA GA		
109.90	POSITION	ELEV	FUEL
116.90	N 33°46.75'	840'	Avgas
ENR	W084°31.29'		Jet
APR ILS		RADAR Yes	ARSPC B
GPS HSG HPT 00000000			

5

COM	APT	Public Done?	
118.500	KFTY	RUNWAY	
119.400	08-26		
VLOC	INFO		
109.90	5700%		
116.90	x100%		
ENR	Hard Srfc		
Full Time			
GPS HSG HPT 00000000			

7

NRST PAGES

Nearest VORs

3 a

COH	VOR	BRG	DIS	FREQ
118.500	ATL	214°	0.8 ⁿ	116.90
119.100	PDK	028°	15.5 ⁿ	116.60
VLOC	DOB	345°	17.7 ⁿ	113.00
109.90	RMG	316°	46.7 ⁿ	115.40
116.90	LGC	231°	52.9 ⁿ	115.60
ENR				

GPS HSG NRST 0000 0000

4 a

COH	VOR	BRG	DIS	FREQ
118.500	ATL	214°	0.8 ⁿ	116.90
119.100	PDK	028°	15.5 ⁿ	116.60
VLOC	DOB	345°	17.7 ⁿ	113.00
109.90	RMG	316°	46.7 ⁿ	115.40
116.60	LGC	231°	52.9 ⁿ	115.60
ENR				

GPS HSG NRST 0000 0000

4 b

COH	VOR	BRG	DIS	FREQ
118.500	PDK	028°	15.5 ⁿ	116.60
119.100	ATL	214°	0.8 ⁿ	116.90
VLOC	DOB	345°	17.7 ⁿ	113.00
109.90	RMG	316°	46.7 ⁿ	115.40
116.60	LGC	231°	52.9 ⁿ	115.60
ENR				

GPS HSG NRST 0000 0000

VOR Identifier and Symbol

Bearing To and Distance To

VOR Frequency

Scroll Bar

Fourth Page in NRST group

COH	VOR	BRG	DIS	FREQ
122.800	OJC	124°	15.6 ⁿ	113.00
125.325	RIS	065°	20.2 ⁿ	111.40
VLOC	MKC	044°	25.4 ⁿ	112.60
113.00	TUP	284°	26.9 ⁿ	117.80
117.95	FOE	260°	31.1 ⁿ	111.60
ENR				

GPS HSG NRST 0000 0000

To quickly tune a VOR's frequency from the nearest VOR page:

1. Select the nearest VOR page, using the steps outlined on page 119.
2. Press the small right knob (PUSH CLR) to activate the cursor.
- 3a. Rotate the large right knob (PUSH CLR) to scroll through the list, highlighting the frequency associated with the desired VOR.
- 4a. Press ENT to place the selected frequency in the standby field of the VLOC window.
5. Press V to activate the selected frequency.
6. Press the small right knob (PUSH CLR) to remove the flashing cursor.

To view additional information for a nearby VOR:


1. Select the nearest VOR page, using the steps outlined on page 119.
2. Press the small right knob (PUSH CLR) to activate the cursor.
- 3b. Rotate the large right knob (PUSH CLR) to scroll through the list, highlighting the identifier of the desired VOR.
- 4b. Press ENT to display the VOR page for the selected VOR.
5. To return to the nearest VOR page, verify that "Done?" is highlighted by the flashing cursor and press ENT (or press CLR).
6. Press the small right knob (PUSH CLR) to remove the flashing cursor.

Nearest User Waypoint Page

The *nearest user waypoint page* displays the name, bearing and distance to the nine nearest user waypoints (within 200 nautical miles of your present position).

Nearest Center (ARTCC) Page

The *nearest center page* displays the facility name, bearing to and distance to the five nearest ARTCC points of communication (within 200 nautical miles of your present position). For each ARTCC listed, the *nearest center page* also indicates the frequency(s) and may be used to quickly tune the COM transceiver to the center's frequency. The selected frequency is placed in the standby field of the COM window and activated using the  key.



To quickly tune an ARTCC's frequency from the nearest center page:

1. Select the nearest center page, using the steps outlined on page 119.
2. Press the small right knob () to activate the cursor.
3. Rotate the large right knob () to scroll through the list, selecting the desired ARTCC.
4. Rotate the large right knob () to scroll down the page, highlighting the desired frequency.
5. Press **ENT** to place the selected frequency in the standby field of the COM window.
6. Press  to activate the selected frequency.
7. Press the small right knob () to remove the flashing cursor.


NRST PAGES

Nearest ARTCC

7




7

NRST PAGES**Nearest FSS****Nearest Flight Service Station (FSS) Page**

The *nearest flight service station page* displays the facility name, bearing to and distance to the five nearest FSS points of communication (within 200 nautical miles of your present position). For each FSS listed, the *nearest flight service station page* also indicates the frequency(s) and may be used to quickly tune the COM transceiver to the FSS's frequency. The selected frequency is placed in the standby field of the COM window and activated using the **C** key.

For duplex operations, "RX" and "TX" indications will appear beside the listed frequencies—indicating "receive only" or "transmit only" frequencies. The associated VOR is also provided for reference.



To quickly tune an FSS's frequency from the nearest flight service station page:

1. Select the nearest flight service station page, using the steps outlined on page 119.
2. Press the small right knob (PUSH) to activate the cursor.
3. Rotate the small right knob (TURN) to scroll through the list, selecting the desired FSS.
4. Rotate the large right knob (TURN) to scroll down the page, highlighting the desired frequency (COM frequency[s] or VOR frequency for duplex operation).

{continued}



5. Press **ENT** to place the selected frequency in the standby field of the COM or VLOC window.
6. Press **C** or **V**, as appropriate, to activate the selected frequency.
7. Press the small right knob (**PUSH**) to remove the flashing cursor.

Nearest Airspace Page

The last page in the NRST group, the *nearest airspace page*, will alert you to as many as nine controlled or special use airspaces near or in your flight path. Alerts are provided according to the following conditions:

- If your projected course will take you inside an airspace within the next ten minutes, the alert message “**Airspace ahead -- less than 10 minutes**” will appear. The *nearest airspace page* will show the airspace as “**Ahead**”.
- If you are within two nautical miles of an airspace and your current course will take you inside, the message “**Airspace near and ahead**” will appear. The *nearest airspace page* will show “**Within 2nm of airspace**”.
- If you are within two nautical miles of an airspace and your current course will **not** take you inside, the message “**Near airspace less than 2nm**” will appear. The *nearest airspace page* will show the airspace as “**Ahead < 2nm**”.
- If you have entered an airspace, the message “**Inside Airspace**” will appear. The *nearest airspace page* will show “**Inside of airspace**”.

Note that the airspace alerts are based on three-dimensional data (latitude, longitude and altitude) to avoid nuisance alerts. The alert boundaries for controlled airspace are also sectorized to provide complete information on any nearby airspace. Once one of the described conditions exists, the message annunciator will flash, alerting you of an airspace message.



7

NRST PAGES

Nearest Airspaces

1b

NEAREST AIRSPACE		
COH 118.900 124.700	KANSAS CITY Inside of airspace	
VLOC 113.00 117.95	KANSAS CITY Ahead < 2nm 00:48	
TERM	KANSAS CITY Ahead 03:32	
GPS	MSG NRST 0000000	

3

NEAREST AIRSPACE		
COH 118.900 124.700	KANSAS CITY Inside of airspace	
VLOC 113.00 117.95	KANSAS CITY Ahead < 2nm 00:48	
TERM	KANSAS CITY Ahead 02:29	
GPS	MSG NRST 0000000	

4

CLASS B Done?		
COH 118.900 124.700	KANSAS CITY	
VLOC 113.00 117.95	KANSAS CITY APP	
TERM	Frequencies?	
GPS	STATUS VERT LIMITS	
	Ahead 02:01	8000' msl Surface
	MSG NRST 0000000	

To view an airspace alert message:

- 1a. When the message annunciator above the **MSG** key flashes, press **MSG**.
2. Press **MSG** again to return to the previous page.

Once you have been provided an airspace alert message, detailed information concerning the specific airspace is provided on the *nearest airspace page*. The *nearest airspace page* displays the airspace name, status ("Ahead", "Ahead < 2nm", etc. as described on the previous page), and a time to entry (if applicable). By selecting any airspace name listed on the *nearest airspace page*, additional details will be provided—including controlling agency, communication frequencies and floor/ceiling limits.

Airspace Name

Message Annunciator


Status and Time to Entry

Eighth Page in NRST group

NEAREST AIRSPACE		
COH 122.800 123.825	KANSAS CITY Ahead 03:15	
VLOC 113.00 117.95	-----	
TERM	-----	
GPS	MSG NRST 0000000	

To view additional details for an airspace listed on the nearest airspace page:

- 1b. Select the nearest airspace page, using the steps outlined on page 119.
2. Press the small right knob (PUSH CREW) to activate the cursor.
3. Rotate the large right knob (PUSH CREW) to scroll through the list, highlighting the desired airspace.
4. Press **ENT** to display the airspace page for the selected nearby airspace.
5. To return to the nearest airspace page, verify that "Done?" is highlighted by the flashing cursor and press **ENT**.
6. Press the small right knob (PUSH CREW) to remove the flashing cursor.






To view and quickly tune the frequency for a controlling agency:

1. Follow steps #1 through #4 on the previous page to display the airspace page for the desired controlled or special use airspace.
2. Rotate the large right knob (⊖) to highlight "Frequencies?" and press **ENT**.
3. Rotate the large right knob (⊖) to scroll through the list, highlighting the desired frequency.
4. Press **ENT** to place the selected frequency in the standby field of the COM window.
5. Press **C** to activate the selected frequency.
6. To return to the airspace page, rotate the large right knob (⊖) to highlight "Done?" and press **ENT** (or press **CLR**).
7. To return to the nearest airspace page, rotate the large right knob (⊖) to highlight "Done?" and press **ENT** (or press **CLR**).
8. Press the small right knob (⊖) to remove the flashing cursor.

NRST PAGES Nearest Airspaces

7



7

NRST PAGES

Nearest Airspaces

COH 124.900 119.100	CLASS C TULSA CONTROLLING AGENCY TULSA APP Frequencies? STATUS Inside VERT LIMITS 4700' msl Surface	Done?
VLOC 111.10 109.70		
ENR		
GPS	MSG	NRST 00000000

COH 126.200 122.300	MOA CAMPBELL ONE CONTROLLING AGENCY FAA MEMPHIS ARTCC STATUS Inside VERT LIMITS 10000' msl 500' agl	Done?
VLOC 110.60 114.90		
ENR		
GPS	MSG	NRST 00000000

COH 126.200 122.300	PROHIBITED AREA P-56 CONTROLLING AGENCY ----- STATUS Ahead < 2nm 00:52 VERT LIMITS 18000' msl Surface	Done?
VLOC 110.60 114.90		
ENR		
GPS	MSG	NRST 00000000

The *airspace page* displays (and airspace alert messages are provided for) the following airspace types:

- Alert
- Class B
- CTA
- MOA
- Restricted
- Training
- Unspecified
- Caution
- Class C
- Danger
- Prohibited
- TMA
- TRSA
- Warning

The bottom right-hand corner of the *airspace page* displays the floor and ceiling limits of the airspace. The following are examples of what may appear as vertical limits for an airspace:

- 5000^ft msl (5000 feet mean sea level)
- 5000^ft agl (5000 feet above ground level)
- MSL (at mean sea level)
- Notam (see Notice to Airmen)
- Unknown
- See Chart
- Unlimited
- Surface

All airspace alert messages, except for prohibited areas, may be turned on or off from the *airspace alarms page*. An altitude buffer is also provided on the *airspace alarms page* to provide an extra margin of safety above/below the published limits. See page 152 for additional details.

Section 8

VLOC (VOR/Localizer/Glideslope) Receiver Operations



The GNS 430 includes digitally-tuned VOR/localizer and glideslope receivers with the desired frequency selected on a *VLOC window*, along the left-hand side of the display. Frequency selection is performed by pressing the small left knob (PUSH C/V) and rotating the small (V) and large (C/V) left knobs to select the desired frequency.

Ident Audio and Volume



VLOC ident is enabled by pressing the (V) knob. When VLOC ident is enabled, an "ID" indication appears in the upper right corner of the VLOC window — to the immediate right of "VLOC".

VLOC audio volume is adjusted using the (V) knob. Rotate the (V) knob clockwise to increase volume, or counterclockwise to decrease volume.

VLOC Window and Tuning

VLOC frequencies are selected with the tuning cursor in the *standby* VLOC frequency field, and using the small (PUSH C/V) and large (C/V) left knobs to dial in the desired frequency. The standby frequency always appears below the *active* frequency. The active frequency is the frequency currently in use.

The tuning cursor will remain in the COM window. If you wish to select a VOR/localizer/ILS frequency, press the small left knob (PUSH C/V) momentarily to place the cursor in the VLOC window.

VLOC RECEIVER

Ident, Volume and Tuning

8



Push for ident audio. Rotate to adjust audio volume.



Push to toggle tuning cursor between COM and VLOC windows. Rotate to adjust the kHz value (the portion after the decimal point) of standby VLOC frequency.




Rotate to adjust the MHz value (the portion before the decimal point) of the standby VLOC frequency.

8

VLOC RECEIVER

Auto-tuning



NOTE

The tuning cursor will normally appear in the COM window, unless placed in the VLOC window by pressing . When the tuning cursor is in the VLOC window, it will automatically return to the COM window after 30 seconds of inactivity.

The active frequency in either window cannot be accessed directly—only the standby frequency will be highlighted by the tuning cursor.

To select a VOR/localizer/ILS frequency:

1. If the tuning cursor is not currently in the VLOC window, press the small left knob () momentarily.
2. Rotate the large left knob () to select the desired megahertz (MHz) value. For example, the "117" portion of the frequency "117.80".
3. Rotate the small left knob () to select the desired kilohertz (kHz) value. For example, the ".80" portion of the frequency "117.80".

To make the standby frequency the active frequency, press the (flip flop) key.

Auto-Tuning

A frequency may also be quickly selected from the database by simply highlighting the desired frequency on the *VOR page* (see page 110) or the *nearest VOR page* (see page 123) and pressing the key. This process is referred to as *auto-tuning*. Once a frequency is selected in the standby field, it may be transferred to the active frequency by pressing the key. (Auto-tuning can also be performed from VLOC frequencies listed on the NAVCOM, *airport frequency*, and *nearest flight service station pages*.)

To select a VLOC frequency from the VOR or nearest VOR pages:

1. Select the desired page from the main pages. (See page references on the preceding page.)
2. Press the small right knob (PUSH CURS) momentarily to activate the flashing cursor
- 3a. Rotate the large right knob (PUSH CURS) to highlight the frequency for the desired VOR.
4. Press **ENT** to place the frequency in the standby field of the VLOC window.
5. Press **V** to activate the selected frequency.
6. Press the small right knob (PUSH CURS) to remove the flashing cursor.

NOTE

For duplex COM operations, the VLOC receiver may be auto-tuned from the nearest flight service station page. See page 126 for more info.

When selecting a VOR or ILS approach, manual tuning of the VLOC receiver is not required. Once the approach procedure is “Loaded” or “Activated”, the GNS 430 will automatically place the proper frequency in the standby field of the VLOC window. If you wish to use this frequency, simply press **V** to activate the frequency. Additional information on approach procedures is provided in Section 5, beginning on page 66.

To select an approach and automatically tune the proper VLOC frequency:

1. Select the destination airport using the **-B>** key or as the last waypoint in the active flight plan.
2. Press the **PROC** key to display the procedures page.
- 3b. Rotate the large right knob (PUSH CURS) to highlight “Select Approach?” and press **ENT**.

{continued}

VLOC RECEIVER
Auto-tuning

8

3 a

COM	VOR	NEAREST VOR	BRG	DIS	FREQ
118.300	OTO	089°	4.3 ⁿ	114.00	
121.900	SAF	345°	27.5 ⁿ	110.60	
VLOC	ABQ	256°	39.2 ⁿ	113.20	
114.00	CNX	148°	46.3 ⁿ	115.50	
117.80	ACH	078°	48.3 ⁿ	117.80	
ENR					
GPS	HSG	NRST	000	0000	

4

COM	VOR	NEAREST VOR	BRG	DIS	FREQ
118.300	OTO	091°	3.8 ⁿ	114.00	
121.900	SAF	344°	27.5 ⁿ	110.60	
VLOC	ABQ	256°	39.7 ⁿ	113.20	
114.00	CNX	149°	46.2 ⁿ	115.50	
110.60	ACH	078°	47.8 ⁿ	117.80	
ENR					
GPS	HSG	NRST	000	0000	

3 b

COM	PROCEDURES
118.300	Activate Vector-To-Final?
121.900	Activate Approach?
VLOC	Select Approach?
114.00	Select Arrival?
110.60	Select Departure?
ENR	
GPS	HSG PROC

8

VLOC RECEIVER**CDI Key**

4. A window will appear listing the available procedures. Rotate the small right knob (PUSH CDI) to highlight the desired procedure and press ENT. (When a direct-to destination is selected, departures are offered for the nearest airport.)
5. A second window will appear listing available transitions. Rotate the small right knob (PUSH CDI) to highlight the desired transition waypoint and press ENT. (The approach "Vectors" option assumes you will receive vectors to the final course segment of the approach and will provide navigation guidance to intercept this final course.)
6. Rotate the large right knob (PUSH CDI) to highlight "Load?" or "Activate?" and press ENT. ("Load?" will add the procedure to the flight plan without immediately using it for navigation guidance. This allows you to continue navigating the original flight plan, but keeps the procedure available on the active flight plan page for quick activation when needed.)
7. For VOR and ILS approaches, the standby field of the VLOC window is automatically tuned to the proper frequency. To activate the frequency press V. To display VLOC course information on the external CDI (or HSI) press CDI and verify that "VLOC" is displayed at the bottom left corner of the screen, directly above the CDI key.
8. For precision approaches and some non-precision approaches, a reminder window will appear indicating that GPS guidance on such approaches is strictly for monitoring only—use the VLOC receivers and external CDI (or HSI) for primary navigation. To confirm this reminder, highlight "Yes?" and press ENT.

CDI Key

The GNS 430's CDI key is used to couple the GPS or VLOC receiver to the external CDI (or HSI). When the external CDI (or HSI) is being driven by the GPS receiver, "GPS" will appear at the bottom left corner of the page, directly above the CDI key. When the external CDI (or HSI) is being driven by the VLOC receiver, "VLOC" will appear instead.

To couple the external CDI (or HSI) to the GPS receiver or VLOC receiver, press CDI to display "GPS" or "VLOC", as desired.

NOTE


The external CDI (or HSI) must be coupled to the VLOC receiver for approaches which are not approved for GPS. See ILS example on page 86.

Section 9

AUX Pages

AUX Page Group

Section 2 introduced the GNS 430's main page groups—NAV, WPT, AUX, NRST—and described each page in the NAV group. The third page group (AUX) allows you to change unit settings, customizing operation to your preferences. The AUX pages also provide E6B functions—such as trip planning, fuel planning, density altitude, true airspeed and winds aloft calculations.



To quickly select an AUX page:


1. From any page, press and hold **CLR** to select the default NAV page. (You may skip this step if you are already viewing any of the main pages. See page 27.)
2. Rotate the large right knob (⌚) to select the AUX page group. "AUX" will appear in the lower right corner of the screen.
3. Rotate the small right knob (⌚) to select the desired AUX page.



9

AUX PAGES

Flight Planning

**Flight Planning Page**

Menu Options: to select, highlight with cursor and press **ENT**.



First Page
in AUX group

The *flight planning page* provides access (via “menu options”) to E6B functions for fuel planning, trip planning, density altitude/true airspeed/winds aloft calculations and a “Crossfill” function to transfer flight plans/user waypoints to a second GNS 430. When a menu option is selected, the corresponding page will appear providing additional information and features.

To select a menu option from the flight planning page:

1. Press the small right knob (Ⓢ) momentarily, to activate the flashing cursor.
2. Rotate the large right knob (Ⓢ) to select the desired menu option, and press **ENT**.

The following menu options are available:

Fuel Planning—when equipped with fuel flow (FF) and/or fuel on board (FOB) sensors, this option displays current fuel conditions along the active direct-to or flight plan. You may also manually enter fuel flow, ground speed (GS) and (in some instances) fuel on board figures for planning purposes. Fuel planning figures can be displayed not only for the currently active flight plan or direct-to, but also point-to-point between two specified waypoints and for any programmed flight plan.

Trip Planning— allows the pilot to view desired track (DTK), distance (DIS), estimated time en route (ETE), enroute safe altitude (ESA) and estimated time of arrival (ETA) information for a direct-to, point-to-point between two specified waypoints or for any programmed flight plan.

NOTE

Point-to-point waypoints, flight plans and/or ground speed (default is current GPS-calculated ground speed) entered on the fuel planning page will automatically transfer to the trip planning page, and vice versa.

Density Alt / TAS / Winds— indicates the theoretical altitude at which your aircraft will perform depending upon several environmental conditions, including indicated altitude (IND ALT), barometric pressure (BARO) and total air temperature (TAT; the temperature, including the heating effect of speed, read on a standard outside temperature gauge). This menu option computes true airspeed (TAS), based upon the factors above and the calibrated airspeed (CAS). Also, this menu option determines winds aloft—the wind direction and speed—and a head wind/tail wind component, based upon the calculated density altitude (DEN ALT), true airspeed, aircraft heading (HDG) and ground speed.

Crossfill— allows the pilot to transfer the active flight plan, any stored flight plan, a user waypoint or all user waypoints between two 400-Series GARMIN units (GNS 430/GNC 420/GPS 400) in a dual-unit installation.

Scheduler— displays reminder messages (such as “Change oil”, “Switch fuel tanks”, “Overhaul”, etc.). One-time, periodic, and event-based messages are allowed. One-time messages will appear once the timer expires and will reappear each time the GNS 430 is powered on, until the message is deleted. Periodic messages will automatically reset to the original timer value, once the message is displayed. Event-based messages do not use a timer, but rather a specific date and time.

AUX PAGES

Flight Planning

9

FUEL PLANNING

COM 118.300 121.900	FPL LEG 00 Cum KPHX → KSGF 0.0 0.0 164k
VLOC 113.20 111.50	FOB FF REQ LF0B LRES 0.0 0.0 00:00 0.0 0.00m 00:00
ENR	EFF RNG ENDUR
VLOC	HSG AUX 000

FUEL PLANNING
POINT TO POINT

COM 126.500 125.700	PAGE MENU Flight Plan? Change Fields? Restore Defaults?
VLOC 111.80 117.30	18.3 0.00 00:00 EFF RNG ENDUR
ENR	
GPS	AUX 000

The "Flight Plan?" option allows you to select the numbered flight plan for fuel planning. The "Change Fields?" option allows you to select fuel information for each field as desired.

9

AUX PAGES

Flight Planning

3 a

COH	FUEL PLANNING		
126.500	POINT TO POINT		
125.700	93%	11.5%	174%
VLOC	FOB	FLOH	GS
111.80	REQ	LF0H	LRES
117.30	56.4%	36.4%	03:10
ENR	15.1	1404 ^m	08:04
	EFF	RNG	ENDUR
GPS	AUX 000		

3 b

COH	FUEL PLANNING		
126.500	FPL LEG		
125.700	00 Cum KIXD	→ KMIC	
VLOC	FOB	FLOH	GS
111.80	L.FLOH	R.FLOH	LRES
113.50	5.4%	6.0%	08:15
ENR	08:40	1508 ^m	4.8%
	ENDUR	RNG	REQ
GPS	AUX 000		

4

COH	FUEL PLANNING		
126.500	FPL LEG		
125.700	02 Cum KIXD	→ KMIC	
VLOC	FOB	FLOH	GS
111.80	L.FLOH	R.FLOH	LRES
117.30	5.5%	6.0%	03:06
ENR	15.1	935 ^m	05:22
	EFF	RNG	ENDUR
GPS	AUX 000		

Flight Planning Page: Fuel Planning

To perform fuel planning operations:

1. Select "Fuel Planning" from the flight planning page, using the steps described on page 136.
2. The current fuel planning "mode" is displayed at the top of the page: "POINT TO POINT" or "FPL" (for a flight plan). To change the mode, press **MENU** to display an options window for the other mode, then press **ENT** to accept the other mode.
- 3a. For point-to-point fuel planning, rotate the small (PUSH CRN) and large (PUSH CRN) right knobs to enter the identifier of the "from" waypoint. Once the waypoint's identifier is entered, press **ENT** to accept the waypoint. The flashing cursor moves to the "to" waypoint. Again, rotate the small (PUSH CRN) and large (PUSH CRN) right knobs to enter the identifier of the "to" waypoint and press **ENT** to accept the waypoint. **OR**,
- 3b. For flight plan fuel planning, rotate the small right knob (PUSH CRN) to select the desired flight plan by number (already stored in memory. 00 is the active flight plan). Rotate the large right knob (PUSH CRN) to highlight the "LEG" field and rotate the small right knob (PUSH CRN) to select the desired leg of the flight plan, or select "Cum" to apply fuel planning calculations to the entire flight plan.
4. If your fuel management system does not enter the data automatically, rotate the large right knob (PUSH CRN) to highlight the fuel on board (FOB) field.
5. Use the small (PUSH CRN) and large (PUSH CRN) right knobs to enter the amount of fuel on board. Press **ENT** when finished.
6. The flashing cursor moves to the fuel flow (FF) field. Use the small (PUSH CRN) and large (PUSH CRN) right knobs to enter the fuel flow rate. Press **ENT** when finished. Note that if a fuel system is providing current fuel flow, the fuel flow field will default to this value.
7. The flashing cursor moves to the ground speed (GS) field. Use the small (PUSH CRN) and large (PUSH CRN) right knobs to enter the ground speed. Press **ENT** when finished.

8. With all variables entered, the following information will be provided:

- REQ— Quantity of fuel required
- LFOB— Left-over fuel on board
- L.FLOW— Left engine fuel flow
- R.FLOW— Right engine fuel flow
- LRES— Left-over fuel reserve time
- EFF— Efficiency, expressed in distance per fuel units (e.g. nautical miles per gallon)
- RNG— Range (distance)
- ENDUR— Flight endurance, or total available flight time

9. To reconfigure the data fields press **MENU** to display the options window. Rotate the small right knob (⌚) to highlight the "change fields?" option. Press **ENT** to reconfigure the data fields. Rotate the large right knob (⌚) to select the desired field. Rotate the small right knob (⌚) to highlight the desired data. Press **ENT** to select the data configuration.

NOTE

Fuel planning figures can be entered and displayed based upon one of three possible configurations:

- 1) No fuel sensors connected—In this instance fuel flow is manually entered and is used to calculate fuel on board. When fuel flow or fuel on board is manually entered, the figures are retained the next time you view the page (with fuel on board continuously recalculated).
- 2) Fuel flow sensor installed, but no fuel on board sensor—Fuel on board is manually entered. Fuel flow is automatically provided by sensor. If fuel flow is manually entered (to override the sensor), it will not affect the FOB figure and is not retained the next time you view the page.
- 3) Fuel flow and fuel on board sensors installed—Fuel flow and fuel on board are automatically provided by sensors. Fuel on board can NOT be entered manually. Fuel flow can be entered manually, but will not affect the FOB figure and is not retained the next time you view the page.

AUX PAGES Flight Planning

9

FUEL PLANNING	
COH 133.000 124.300	FPL LEG 07 Cum KIXD → KCHS 99% 11.5% 175%
VLOC 117.80 110.90	FOB FLOW GS L.FLOW R.FLOW REQ 5.5% 6.0% 84.6%
ENR 15.2	RNG ENDUR 1503" 08:35
GPS	MSG AUX 000

8

SELECT FIELD TYPE	
COH 126.500 125.700	EFF - Efficiency
VLOC 111.80 113.50	ENDUR - Endurance
ENR	L.FLOW - Left Fuel Flow
GPS	R.FLOW - Right Fuel Flow
	LFOB - Landing FOB
	LRES - Landing Reserv
	AUX 000

9

SELECT FIELD TYPE	
COH 126.500 125.700	L.FLOW - Left Fuel Flow
VLOC 111.80 113.50	R.FLOW - Right Fuel Flow
ENR	LFOB - Landing FOB
GPS	LRES - Landing Reserv
	REQ - Fuel Required
	RNG - Range
	AUX 000

9

9

AUX PAGES

Flight Planning

3 a

COH 118.300 121.900		TRIP PLANNING POINT TO POINT KABQ → KOKC 19:24 ^h 162 ^k	
VLOC 113.20 111.50	DEP TIME DTK	DIS	GS ETE
ENR	074°	443 ⁿ	02:44
	15500 ^{ft}		22:08 ^h
VLOC	ESA	ETA	
HSG AUX 000			

3 b

COH 118.300 121.900		TRIP PLANNING FPL LEG 00 02 KABQ → KOKC 19:24 ^h 162 ^k	
VLOC 113.20 111.50	DEP TIME DTK	DIS	GS ETE
ENR	074°	443 ⁿ	02:44
	15500 ^{ft}		23:54 ^h
VLOC	ESA	ETA	
HSG AUX 000			

7

COH 118.300 121.900		TRIP PLANNING FPL LEG 00 02 KABQ → KOKC 19:30 ^h 162 ^k	
VLOC 113.20 111.50	DEP TIME DTK	DIS	GS ETE
ENR	074°	443 ⁿ	02:44
	15500 ^{ft}		00:00 ^h
VLOC	ESA	ETA	
HSG AUX 000			

Flight Planning Page: Trip Planning

To perform trip planning operations:

1. Select "Trip Planning" from the flight planning page, using the steps described on page 136.
2. The current trip planning "leg mode" is displayed at the top of the page: "POINT TO POINT" or "FPL LEG" (for a flight plan leg). To change the leg mode, press **MENU** to display an options window for the other leg mode, then press **ENT** to accept the other leg mode.
- 3a. For point-to-point trip planning, rotate the small () and large () right knobs to enter the identifier of the "from" waypoint. Once the waypoint's identifier is entered, press **ENT** to accept the waypoint. The flashing cursor moves to the "to" waypoint. Again, rotate the small () and large () right knobs to enter the identifier of the "to" waypoint and press **ENT** to accept the waypoint. **OR**,
- 3b. For "flight plan leg" trip planning, rotate the small right knob () to select the desired flight plan (already stored in memory), by number. Rotate the large right knob () to highlight the "LEG" field and rotate the small right knob () to select the desired leg of the flight plan, or select "Cum" to apply trip planning calculations to the entire flight plan.
4. Rotate the large right knob () to highlight the departure time (DEP TIME) field.
5. Use the small () and large () right knobs to enter the departure time. Press **ENT** when finished. (Departure time may be entered in local or UTC time, depending upon unit settings. See page 158.)
6. The flashing cursor moves to the ground speed (GS) field. Use the small () and large () right knobs to enter the ground speed. Press **ENT** when finished.
7. With all variables entered, the following information will be provided:
 - DTK— Desired track, or desired course
 - DIS— Distance
 - ETE— Estimated time en route
 - ESA— En route safe altitude
 - ETA— Estimated time of arrival

Flight Planning Page: Density Alt / TAS / Winds

To calculate density altitude, true airspeed, winds aloft:

1. Select "Density Alt / TAS / Winds" from the flight planning page, using the steps described on page 136.
2. The flashing cursor highlights the indicated altitude (IND ALT) field. Use the small (⊖) and large (⊕) right knobs to enter the altitude indicated on your altimeter. Press **ENT** when finished.
3. The flashing cursor moves to the calibrated airspeed (CAS) field. Use the small (⊖) and large (⊕) right knobs to enter the airspeed from your airspeed indicator. Press **ENT** when finished.
4. The flashing cursor moves to the barometric pressure (BARO) field. Use the small (⊖) and large (⊕) right knobs to enter the barometric pressure (altimeter setting). Press **ENT** when finished.
5. The flashing cursor moves to the total air temperature (TAT) field. Use the small (⊖) and large (⊕) right knobs to enter the temperature. Press **ENT** when finished.
6. The flashing cursor moves to the aircraft heading (HDG) field. Use the small (⊖) and large (⊕) right knobs to enter the aircraft heading from the directional gyro or compass. Press **ENT** when finished.
7. With all variables entered, the following information will be provided:

- DEN ALT— Density altitude
- TAS— True airspeed
- WIND— Wind direction and speed
- HEAD/TAIL WIND—Magnitude of head wind or tail wind component

NOTE

If your installation includes components (such as an airdata sensor) to provide any of the variables above, the density alt/tas/winds page data will default to the values provided by these components.

AUX PAGES

Flight Planning

9

FLIGHT PLANNING

COH 118.300	Fuel Planning
121.900	Trip Planning
VLOC 113.20	Density Alt / TAS / Winds
111.50	Crossfill
ENR	Scheduler

VLOC HSG AUX 000

DENSITY ALT / TAS / WINDS

COH 118.300	IND ALT	CAS	BARO
121.900	11000'	160%	30.00"
VLOC 113.20	15%	075%	
111.50	TAT	HDG	
ENR	DEN ALT	TAS	
	+12801'	199%	
	085% at 35%	35%	
	WIND	HEAD WIND	

VLOC HSG AUX 000

DENSITY ALT / TAS / WINDS


COH 118.300	IND ALT	CAS	BARO
121.900	11000'	160%	30.10"
VLOC 113.20	5%	075%	
111.50	TAT	HDG	
ENR	DEN ALT	TAS	
	+11616'	190%	
	085% at 26%	26%	
	WIND	HEAD WIND	

VLOC HSG AUX 000

9

AUX PAGES

Flight Planning

**Flight Planning Page: Crossfill**

Select *Crossfill?* from the Default Nav page or Flight Plan page by pressing the **MENU** key or while on the Flight Planning page by scrolling down to *Crossfill* and pressing **ENT**.

Automatic Operation: If both units are set to automatic, a change in the active flight plan of one unit will also be seen in the other. Initiating a direct-to to a waypoint on one unit will also initiate a direct-to to the same waypoint on the other unit.

If one unit is set for automatic crossfill and the other is set for manual crossfill, then only the auto unit will automatically send data to the manual unit. In this configuration, the auto unit could be thought of as the master unit.

Manual Operation: If manual operation is desired, the pilot must invoke all transfers from that unit. When a unit is configured for automatic transfer, a manual transfer can also be done on command. If either of the messages "data transfer error" or "data transfer cancelled" are received during an automatic or manual transfer, the pilot must force another transfer.

To transfer flight plans or user waypoints to/from a second 400-Series unit:

1. Select "Crossfill" from the flight planning page, using the steps described on page 136.
2. The flashing cursor highlights the method field. Rotate the small right knob (labeled **DATA CHGN**) to select "Auto" or "Manual". "Auto" will automatically transfer any selection of (or any change to) a direct-to destination or active flight plan to a second 400- or 500-series GARMIN unit.


3. The flashing cursor highlights the transfer data option (TRANSFER) field. Rotate the small right knob (PUSH CRN) to display a window of available data options:

- **Active Flight Plan**—transfer the active flight plan to/from a second 400-Series GARMIN unit (GNS 430/GNC 420/GPS 400) in a dual unit installation. This option is the default when selecting “Crossfill” from the *flight planning* page.
 - **Flight Plan**—transfer any stored flight plan to/from a second 400-Series unit, by selecting the flight plan by number. This option is the default when selecting “Crossfill” from the *flight plan catalog*. See page 58.
 - **User Waypoints (all)**—transfer all stored user waypoints to/from a second 400-Series unit.
 - **User Waypoint**—transfer the specified user waypoint to a second 400-Series unit.
4. Continue rotating the small right knob (PUSH CRN) to select the desired data option. Press **ENT** when finished.
5. For a stored flight plan (“Flight Plan” data option), the flight plan number field is highlighted. Rotate the small right knob (PUSH CRN) to select the desired flight plan and press **ENT**.
6. For a specified user waypoint (“User Waypoint” data option), the waypoint identifier field is highlighted. Use the small (PUSH CRN) and large (PUSH CRN) right knobs to enter the identifier of the desired user waypoint. Press **ENT** when finished.
7. The flashing cursor moves to the “CROSS-SIDE” field. Rotate the small right knob (PUSH CRN) to select “To” or “From” and press **ENT**.
8. The flashing cursor moves to the “Initiate Transfer?” confirmation field. Press **ENT** to transfer the selected data.


AUX PAGES

Flight Planning


9



3



3



8

9


AUX PAGES

Flight Planning

4 a



4 a



Flight Planning Page: Scheduler

To enter a scheduled message:

1. Select "Scheduler" from the flight planning page, using the steps described on page 136.
2. The flashing cursor highlights the first message field. If necessary, rotate the large right knob (⊖) to highlight the first blank message field.
3. Use the small (⊖) and large (⊖) right knobs to enter the message text. Press **ENT** when finished. (The GNS 430 will store up to nine scheduled messages holding 20 characters each.)
- 4a. The flashing cursor moves to the type field under the new message. Rotate the small right knob (⊖) to display a window of available options: (Event, One Time, Periodic). Press **ENT** to select.
5. The flashing cursor moves to the time/date field. Use the small (⊖) and large (⊖) right knobs to set the time or date required before the message is displayed. Time is entered as hours/minutes/seconds (hhh:mm:ss). Event-based messages expire at a specific date and time. Press **ENT** when finished.

To edit a scheduled message:


1. Select "Scheduler" from the flight planning page, using the steps described on page 136.
2. The flashing cursor highlights the first message field.
3. To edit the message text, rotate the large right knob (⊖) to highlight the desired message field. Use the small (⊖) and large (⊖) right knobs to edit the message text—entering the new text directly over the old message. Press **ENT** when finished.
- 4b. To edit the time field, rotate the large right knob (⊖) to highlight the field. Use the small (⊖) and large (⊖) right knobs to edit the new date or time—entering the new value directly over the old figure. Press **ENT** when finished.

To delete a scheduled message:

1. Select "Scheduler" from the flight planning page, using the steps described on page 136.
2. The flashing cursor highlights the first message field. Rotate the large right knob (⊖) to highlight the desired message field.
3. Press **CLR** to delete the message text, followed by **ENT** to confirm the deletion.

Utility Page

Menu Options: to select, highlight with cursor and press **ENT**.



Second Page
in AUX group

The *utility page* provides access (via “menu options”) to checklists, a count down/up timer, trip timers, trip statistics, RAIM (Receiver Autonomous Integrity Monitoring) prediction, sunrise/sunset time calculations and software/database version information. When a menu option is selected, the corresponding page will appear providing additional information and features.

To select a menu option from the utility page:

1. Press the small right knob (Ⓜ) momentarily, to activate the flashing cursor.
2. Rotate the large right knob (Ⓢ) to select the desired menu option, and press **ENT**.

The following menu options are available:

Checklists— provides up to nine different user-defined checklists containing up to 30 items each.


Flight Timers— provides count up/down timers, plus automatic recording of departure time and total trip time. Departure and total trip time recording can be configured to run either any time GNS 430 power is on, or only when your ground speed exceeds 30 knots.

Trip Statistics— provides readouts for trip odometers, average speed and maximum speed. These readouts are resettable (individually or all at once) by pressing **MENU** to display an options window.

AUX PAGES

Utility Page

9



9

AUX PAGES

Utility Page



An 'INTEG' annunciation at the bottom left corner of the screen indicates that satellite coverage is insufficient to pass built-in receiver autonomous integrity monitoring (RAIM) tests. When this occurs, the GPS receiver will continue to provide navigation information, but should not be used for primary navigation guidance. Use the GNS 430's VLOC receiver or another suitable navigation source.

If a 'WARN' annunciation appears at the bottom left corner, GPS satellite coverage may be sufficient, but the GNS 430 has detected a position error which exceeds protection limits. In this condition, all GPS navigation data on the GNS 430 will be disabled. Use the GNS 430's VLOC receiver or an alternate navigation source.

RAIM Prediction— predicts if GPS coverage is available for your current location or at a specified waypoint at any time and date. Receiver Autonomous Integrity Monitoring performs checks to ensure that the GNS 430 will have adequate satellite geometry during your flight. RAIM availability will be near 100% in Oceanic, En route and Terminal phases of flight. Because the FAA's TSO requirements for non-precision approaches specify significantly better satellite coverage than other flight phases, RAIM may not be available when flying some approaches. The GNS 430 will automatically monitor RAIM during approach operations and warn you if RAIM is not available. In such cases, use the GNS 430's VLOC receiver instead for many of the non-precision and precision approaches stored on your Jeppesen NavData® card. RAIM prediction will help you plan for a pending flight to confirm GPS operation during an approach.

Sunrise / Sunset— allows you to calculate the time of sunrise and sunset at any waypoint or your present position for a specified date.

Software / Database Ver.— provides software version information for the operating software within the GPS receiver, COM transceiver, VOR/localizer receiver, glideslope receiver and main processor board. The *software / database version page* also displays the current Jeppesen database type and expiration date, along with the version and type of built-in land database.

Utility Page: Checklists

To create a checklist:

- 1a. Select "Checklist" from the utility page, using the steps described on page 145. Press **ENT** to display a list of checklists.
2. Press **MENU** to display an options menu. Rotate the large right knob (⊖) to select "Create New Checklist?" and press **ENT**.
3. Use the small (⊖) and large (⊖) right knobs to enter the name of a checklist. Press **ENT** when finished. (Up to nine different checklists can be created and stored in the GNS 430.)
4. Use the small (⊖) and large (⊖) right knobs to enter each checklist item, followed each time by **ENT**. (Each checklist may contain up to 30 line items of as much as sixteen characters long.)

Utility Page: Checklists (cont.)

To execute a checklist:

- 1b. With the checklists page displayed, rotate the large right knob (⊖) to select the desired checklist and press **ENT**.
- 2b. As you complete each checklist item, press **ENT** to move to the next item on the list.

To edit a checklist:

1. With the checklists page displayed, rotate the large right knob (⊖) to select the desired checklist and press **ENT**.
2. Press **MENU** to display an options menu. Select "Edit Item?" and press **ENT**, then use the small (⊖) and large (⊖) right knobs to edit each checklist item. Press **ENT** when finished.

To insert a checklist step into an existing checklist:

1. With the checklists page displayed, rotate the large right knob (⊖) to select the desired checklist and press **ENT**.
2. Rotate the large right knob (⊖) to highlight the existing checklist entry which will immediately follow the new checklist step.
3. Rotate the small (⊖) and large (⊖) right knobs to enter the new checklist step. Press **ENT** when finished.

To delete a checklist or all checklists:


1. With the checklists page displayed, press **MENU** to display an options menu.
2. Rotate the large right knob (⊖) to select "delete checklist" or "delete all checklists" and press **ENT** to remove the checklist or all checklists from memory.

To copy a checklist:

1. With the checklists page displayed and the desired checklist selected, press **MENU**.
2. Rotate the large right knob (⊖) to select "Copy Checklist?" and press **ENT** to copy the checklist to an empty checklist memory location.

To sort the checklists by name or entry:




1. With the checklists page displayed, press **MENU** to display an options menu.
2. Rotate the large right knob (⊖) to select "Sort List By Entry?" or "Sort List By Name?" and press **ENT**.



9

AUX PAGES

Utility Page



Utility Page: Flight Timers

To view, use or reset the generic timer:

1. Select "Flight Timers" from the utility page, using the steps described on page 145.
2. The flashing cursor highlights "Start?". To start the generic timer, press **ENT**. (You will typically begin with this step for count up timers. However, for count down timers, you may wish to enter a count direction and time before starting the timer. See below.)
- 3a. To change the count direction, rotate the large right knob (⊖) to highlight count direction field: "Down" or "Up". Rotate the small right knob (⊕) to select the desired count direction. Press **ENT** when finished.
4. For a count down timer, rotate the large right knob (⊖) to highlight the time field. Use the small (⊕) and large (⊖) right knobs to enter the count down time—in hours, minutes and seconds. Press **ENT** when finished.
5. To stop the generic timer, rotate the large right knob (⊖) to highlight "Stop?" and press **ENT**.
6. To reset the generic timer, rotate the large right knob (⊖) to highlight the time field. Press **CLR**, followed by **ENT**.

To record or reset the departure time:

1. Select "Flight Timers" from the utility page, using the steps described on page 145.
2. Rotate the large right knob (⊖) to highlight the reset mode field, under "Departure Time". (The reset mode field will indicate "Pwr-on" or "GS>30k".)
- 3b. Rotate the small right knob (⊕) to select the desired reset mode. ("Pwr-on" will record a departure time when the GNS 430 is turned on. "GS>30k" will record a departure time once the GPS-computed ground speed exceeds 30 knots.)
4. Press **ENT** when finished.
5. To reset the departure time, rotate the large right knob (⊖) to highlight "Reset?" and press **ENT**.

Utility Page: Flight Timers (cont.)

To view, use or reset total trip time:

- 1a. Select "Flight Timers" from the utility page, using the steps described on page 145.
- 2a. Rotate the large right knob (⊖) to highlight the reset mode field, under "Total Trip Time". (The reset mode field will indicate "Pwr-on" or "GS>30kt".)
3. Rotate the small right knob (⊕) to select the desired reset mode. ("Pwr-on" will record trip time, in hours/minutes/seconds, any time the GNS 430 is turned on. "GS>30kt" will record trip time any time the GPS-computed ground speed exceeds 30 knots.)
4. Press **ENT** when finished.
5. To reset the total trip time, rotate the large right knob (⊖) to highlight "Reset?" and press **ENT**.

Utility Page: Trip Statistics



To reset trip statistics readouts:

- 1b. Select "Trip Statistics" from the utility page, using the steps described on page 145.
- 2b. Press **MENU** to display an options window with several reset options:
 - **Reset Trip?**— Resets trip odometer and average ground speed readouts
 - **Reset Max Speed?**—Resets maximum speed readout only
 - **Reset Odometer?**— Resets odometer readout only
 - **Reset All?**— Resets all trip statistics readouts
3. Rotate the large right knob (⊖) to select the desired reset option and press **ENT**.

AUX PAGES

Utility Page


9



9

AUX PAGES

Utility Page



Utility Page: RAIM Prediction

To predict RAIM availability:

1. Select "RAIM Prediction" from the utility page, using the steps described on page 145.
2. The flashing cursor highlights the waypoint field. Use the small (PUSH CLR) and large (PUSH ENT) right knobs to enter the identifier of the waypoint at which you wish to determine RAIM availability. Press **ENT** when finished. (To determine RAIM availability for your present position, press **CLR**, followed by **ENT**.)
3. The flashing cursor moves to the arrival date field. Use the small (PUSH CLR) and large (PUSH ENT) right knobs to enter the date for which you wish to determine RAIM availability. Press **ENT** when finished.
4. The flashing cursor moves to the arrival time field. Use the small (PUSH CLR) and large (PUSH ENT) right knobs to enter the time for which you wish to determine RAIM availability. Press **ENT** when finished.
5. The flashing cursor moves to "Compute RAIM?". Press **ENT** to begin RAIM prediction. Once calculations are complete, the GNS 430 will display one of the following in the RAIM status field:

- **RAIM Not Available**— Satellite coverage is predicted to NOT be sufficient for reliable operation during non-precision approaches
- **RAIM Available**— Satellite coverage is predicted to be sufficient for reliable operation during all flight phases, including non-precision approaches

NOTE

RAIM computations predict satellite coverage within +/- 15 minutes of the specified arrival date and time. Refer to page 153 for specific information regarding RAIM protection limits.

Utility Page: Sunrise / Sunset

To calculate sunrise and sunset times at any waypoint or your present position:

1. Select "Sunrise / Sunset" from the utility page, using the steps described on page 145.
2. The flashing cursor highlights the waypoint field. Use the small (⏏) and large (⏏) right knobs to enter the identifier of the waypoint at which you wish to determine sunrise and sunset times. Press **ENT** when finished. (To determine sunrise/sunset times for your present position, press **CLR**, followed by **ENT**.)
3. The flashing cursor moves to the date field. Use the small (⏏) and large (⏏) right knobs to enter the date for which you wish to determine sunrise and sunset times.
4. Press **ENT** to calculate sunrise and sunset times for the selected location and date.

Utility Page: Software / Database Ver.

The *software / database version page* displays software version information for each of the various subsystems contained within the GNS 430, as well as database versions for the Jeppesen NavData® card and built-in land data. This page is for information purposes only—no user functions are available from this page.

SOFTWARE / DATABASE VER			
COH 122.800 135.325	MAIN 2.00	GPS 2.00	COM 1.22
VLOC 113.00 117.95	VOR/LOC 1.25	G/S 2.00	
ENR	AVIATION DB		LAND DB
	Americas (9810) Exp. 08-OCT-98		World 1.00
VLOC	MSG	AUX	000

AUX PAGES

Utility Page

9

UTILITY	
COH 122.800 135.325	Checklists Flight Timers Trip Statistics RAIM Prediction Sunrise / Sunset
VLOC 113.00 117.95	
ENR	
VLOC	MSG AUX 000


SUNRISE / SUNSET	
COH 122.800 135.325	WAYPOINT KIXD
VLOC 113.00 117.95	DATE 22-NOV-98
ENR	SUNRISE 13:08
	SUNSET 23:03
VLOC	MSG AUX 000

SUNRISE / SUNSET	
COH 122.800 135.325	WAYPOINT KIXD
VLOC 113.00 117.95	DATE 22-NOV-98
ENR	SUNRISE 13:09
	SUNSET 23:03
VLOC	MSG AUX 000


9

AUX PAGES

Setup 1



Setup 1 Page



The *setup 1* page provides access (via “menu options”) to airspace alarms, CDI scale adjustment, an arrival alarm, units of measure settings, position formats, map datums and settings for local or UTC time display. When a menu option is selected, the corresponding page will appear providing access to the various unit settings.

To select a menu option from the *setup 1* page:

1. Press the small right knob (Ⓢ) momentarily, to activate the flashing cursor.
2. Rotate the large right knob (Ⓢ) to select the desired menu option, and press **ENT**.

The following menu options are available:

Airspace Alarms— allows you to turn the controlled / special-use airspace message alerts on or off. This will not affect the alerts listed on the *nearest airspace page* or the airspace boundaries depicted on the map page. It will simply turn on/off the warning provided when you are approaching or near an airspace.

An altitude buffer is also provided which “expands” the vertical range above or below an airspace. For example, if the buffer is set at 500 feet, and you are more than 500 feet above or below an airspace, you will not be notified with an alert message; if you are less than 500 feet above or below an airspace and projected to enter it, you will be notified with an alert message. The default is 200 feet.

CDI / Alarms— allows you to define the scale for the GNS 430’s on-screen course deviation indicator. The scale values represent full scale deflection for the CDI to either side. The default setting is “5.0 nm”. At this setting, the CDI scale is set to 5 nm during the enroute phase of flight. Within 30 nm of your destination airport the CDI scale gradually ramps down to 1.0 nm (terminal area). Likewise when leaving your departure airport the CDI scale is set to 1.0 nm and gradually ramps UP to 5 nm beyond 30 nm (from the departure airport).

During approach operations the CDI scale gradually ramps down even further, to 0.3 nm. This transition normally occurs within 2.0 nm of the final approach fix (FAF). If a lower CDI scale setting is selected (i.e., 1.0 nm or 0.3 nm) the higher scale settings will not be selected during ANY phase of flight. For example, if 1.0 nm is selected, the GNS 430 will use this for the enroute and terminal phase and ramp down to 0.3 nm during an approach. Note that the Receiver Autonomous Integrity Monitoring (RAIM) protection limits listed below follow the selected CDI scale and corresponding modes:

CDI Scale	RAIM Protection
+/-5.0 nm or Auto (en route)	2.0 nm
+/-1.0 nm or Auto (terminal)	1.0 nm
+/-0.3 nm or Auto (approach)	0.3 nm

An “auto” ILS CDI selection allows the GNS 430 to automatically switch the external CDI from the GPS receiver to the VLOC receiver, when established on the final approach course. (See page 86.) Or, select “manual” to manually switch the external CDI connection, as needed.

An arrival alarm, provided on the *CDI / alarms page*, may be set to notify you with a message when you have reached a user-defined distance to the final destination (the direct-to waypoint or the last waypoint in a flight plan). Once you have reached the set distance (up to 99.9 units), an “Arrival at [waypoint]” message will be displayed.

Units / Mag Var— allows you to configure the displayed data to standard or metric units of measure. This setting applies to distance, speed, altitude, fuel, pressure and temperature. Also provides three magnetic variation (heading) options: True, Auto or User-defined. If “Auto” is selected, all track, course and heading information will be corrected to the magnetic variation computed by the GPS receiver. The “True” setting will reference all information to true north, and the “User” setting will correct information to an user-entered value.



CDI scales and corresponding modes:



Enroute



Terminal




Approach

9

AUX PAGES

Setup 1



Position / Map Datum— configures position readout information to the desired position format and datum. The NavData® card contains over 100 map datums to adjust your position reading, making it conform to specific paper charts. If you are using a chart based on another datum, you must set the GNS 430 to use the same datum. Using a map datum that does not match the charts you are using can result in significant differences in position information. If you are using the paper charts for reference only, the GNS 430 will still provide correct navigation guidance to the waypoints contained in the database, regardless of the datum selected.

Date / Time— provides settings for time format (local or UTC; 12- or 24-hour) and time offset. The time offset is used to define current local time. UTC (also called “GMT” or “zulu”) date and time are calculated directly from the GPS satellites’ signals and cannot be changed. If you prefer to use local time, simply designate the offset by adding or subtracting the correct number of hours.

Setup 1 Page: Airspace Alarms

To set the airspace warning messages or change the altitude buffer:

1. Select “Airspace Alarms” from the setup 1 page, using the steps described on page 152.
2. Rotate the large right knob (⊖) to highlight the “On”/“Off” field next to the desired airspace type. (“Other SUAs” includes alert, caution, danger, training and warning areas.)
3. Rotate the small right knob (⊕) to select “On” or “Off”, as desired. Press **ENT** to accept the selection.
4. To change the altitude buffer, rotate the large right knob (⊖) to highlight the “Altitude Buffers” field. Use the small (⊕) and large (⊖) right knobs to enter the desired buffer distance. Press **ENT** when finished.

NOTE

When an approach has been loaded into the active flight plan, airspace alert messages will be disabled within 30 nm of the destination airport.

Setup 1 Page: CDI Scale / Alarms

To change the CDI scale:

1. Select "CDI / Alarms" from the setup 1 page, using the steps described on page 152.
2. The flashing cursor highlights the "Selected CDI" field. Rotate the small right knob (PUSH CRN) to select the desired CDI scale. The selected scale and any lower scale settings will be used during the various phases of flight as described on page 153.
- 3a. Press **ENT** to accept the selected scale. The "System CDI" field will display the CDI scale currently in use. The "System CDI" setting may differ from the "Selected CDI" depending upon the current phase of flight. See page 153 for more information.

To change the ILS CDI selection:

1. Select "CDI / Alarms" from the setup 1 page, using the steps described on page 152.
2. Rotate the large right knob (PUSH CRN) to highlight the "Auto"/"Manual" ILS CDI field.
- 3b. Rotate the small right knob (PUSH CRN) to select "Auto" or "Manual", as desired. Press **ENT** to accept the selection.

To set the arrival alarm and alarm distance:

1. Select "CDI / Alarms" from the setup 1 page, using the steps described on page 152.
2. Rotate the large right knob (PUSH CRN) to highlight the "On"/"Off" field (directly below "Arrival Alarm").
- 3c. Rotate the small right knob (PUSH CRN) to select "On" or "Off", as desired. Press **ENT** to accept the selection.
4. The flashing cursor moves to the alarm distance field (to the immediate right of "On" or "Off"). To enter an arrival alarm distance, use the small (PUSH CRN) and large (PUSH CRN) right knobs to enter the desired alarm distance. Press **ENT** when finished.


NOTE

The CDI scale is always measured in nautical miles, regardless of the current distance units of measure selected on the units/mag var page.


AUX PAGES

Setup 1


9



1



3 a




3 b

9

AUX PAGES

Setup 1



Setup 1 Page: Units / Mag Var

To set the magnetic variation:

1. Select "Units / Mag Var" from the setup 1 page, using the steps described on page 152.
- 2a. The flashing cursor highlights the heading mode field. Rotate the small right knob (PUSH CROWN) to select the desired heading mode: Auto, True or User. Press **ENT** to accept the selection. (The heading modes are described on page 153.)
3. If "User" is selected, the flashing cursor moves to the user value field (to the immediate right of "User"). Use the small (PUSH CROWN) and large (PUSH CROWN) right knobs to enter the desired magnetic variation direction and value. Press **ENT** when finished.

To change the units of measure:

1. Select "Units / Mag Var" from the setup 1 page, using the steps described on page 152.
- 2b. Rotate the large right knob (PUSH CROWN) to highlight the desired units of measure category. The following categories, and corresponding units of measure, are available:
 - **DIS, SPD**—distance and speed in Nautical (nautical miles/knots), Statute (miles/miles per hour) or Metric (kilometers/kilometers per hour) terms.
 - **ALT, VS**—altitude and vertical speed in Feet/feet per minute, Meters/meters per minute, or Meters/meters per second.
 - **PRESSURE**—barometric pressure in Inches or Millibars.
 - **TEMP**—temperature in degrees Celsius or Fahrenheit.
 - **FUEL**—fuel units in Gallons, Imperial Gallons, Kilograms, Liters or Pounds.
3. Rotate the small right knob (PUSH CROWN) to select the desired units of measure for the selected category. Press **ENT** to accept the selection.

Setup 1 Page: Position Format / Map Datum

To change the position format:

1. Select "Position Format / Map Datum" from the setup 1 page, using the steps described on page 152.
- 2a. The flashing cursor is on the position format field. Rotate the small right knob (PUSH) to select the desired position format. The following position formats are available:
 - **hddd°mm.mmm'**—latitude and longitude in degrees and decimal minutes
 - **hddd°mm'ss.s"**—latitude and longitude in degrees, minutes and decimal seconds
 - **MGRS**—Military Grid Reference System
 - **UTM/UPS**—Universal Transverse Mercator / Universal Polar Stereographic grids
3. Press **ENT** to accept the selected format.

To change the map datum:

1. Select "Position Format / Map Datum" from the setup 1 page, using the steps described on page 152.
- 2b. Rotate the large right knob (PUSH) to highlight the map datum field.
3. Rotate the small right knob (PUSH) to display a window showing the available map datums.
4. Continue rotating the small right knob (PUSH) to select the desired map datum. (See page 181 for a list of available map datums.)
5. Press **ENT** to accept the selected datum.

NOTE

Per TSO C129a, the WGS-84 map datum should be used in the United States. For use outside the U.S., select the geodetic datum required by that country.

AUX PAGES

Setup 1

9



1



2a




2b

9

AUX PAGES

Setup 1

2 a



2 b



2 c



Setup 1 Page: Date / Time

To display local time or UTC:

1. Select "Date / Time" from the setup 1 page, using the steps described on page 152.
- 2a. The flashing cursor highlights the time format field. Rotate the small right knob (PUSH) to display a window of available time formats: Local 12hr, Local 24hr, or UTC.
3. Continue rotating the small right knob (PUSH) to select the desired time format.
4. Press **ENT** to accept the selection.

To set the local time:

1. Select "Date / Time" from the setup 1 page, using the steps described on page 152.
- 2b. Rotate the large right knob to highlight the time offset field.
3. Use the small (PUSH) and large (PUSH) right knobs to enter the desired offset, beginning by entering a minus (-) or plus (+) sign to indicate whether the offset is behind UTC or ahead of UTC. (In the United States, all local time offsets will use be minus, or behind UTC.)
4. Press **ENT** to accept the selected offset.

Restoring Factory Settings

When making changes to any *setup 1 page* option, a "Restore Defaults?" menu selection allows you to restore the original factory settings (for the selected option only). For example, with the *airspace alarms page* displayed, the "Restore Defaults?" option will restore all *airspace alarms page* settings to the original factory values.

To restore a setup 1 option to the original factory settings:

1. Select the desired menu option from the setup 1 page, using the steps described on page 152.
- 2c. Press **MENU** to display a page options window.
3. With "Restore Defaults?" highlighted, press **ENT**.

Setup 2 Page

Menu Options: to select, highlight with cursor and press **ENT**.



Fourth Page
in AUX group

The *setup 2 page* provides access (via “menu options”) to display adjustments, parameters which define the nearest airport search, and COM transceiver channel spacing. When a menu option is selected, the corresponding page will appear providing access to the various unit settings.

To select a menu option from the setup 2 page:

1. Press the small right knob (Ⓜ) momentarily, to activate the flashing cursor.
2. Rotate the large right knob (Ⓢ) to select the desired menu option, and press **ENT**.

The following menu options are available:

Display— allows you to adjust the display for optimum viewing in any condition. Automatic backlighting is available which uses a built-in photocell (at the top left corner of the display bezel) to make the proper display adjustments without any user intervention. Automatic contrast adjustment varies the screen contrast level based upon current unit temperature. You may also select manual control of the display contrast and backlighting to tailor the GNS 430's display to your needs.

NOTE

Display backlighting changes are not saved when the GNS 430 is turned off. Backlighting will revert to the “Auto” setting the next time the unit is turned on.

AUX PAGES

Setup 2


9



1



2




2

9

AUX PAGES

Setup 2



Nearest Airport Criteria— defines the minimum runway length and surface type used when determining the nine nearest airports to display on the *nearest airport page*. A minimum runway length and/or surface type may be entered to prevent airports with small runways, or runways that are not of appropriate surface, from being displayed. The default settings are “0 feet (or meters)” for runway length and “any” for runway surface type.

COM Configuration— allows you to select 8.33 kHz or 25.0 kHz COM frequency channel spacing.

NOTE

8.33 kHz VHF communication frequency channel spacing is not approved for use in the United States. Select the 25.0 kHz channel spacing option.

Setup 2 Page: Display

To change the backlighting intensity:

1. Select “Display” from the setup 2 page, using the steps described on page 159.
- 2a. The flashing cursor highlights the backlight mode field. Rotate the small right knob (PUSH CROWN) to select the desired mode: Auto or Manual. Press **ENT** to accept the selection.
3. If “Manual” is selected, the flashing cursor moves to the backlight level field. Rotate the small right knob (PUSH CROWN) to select the desired level. Press **ENT** to accept the selection.

To change the display contrast:

1. Select “Display” from the setup 2 page, using the steps described on page 159.
- 2b. Rotate the large right knob to highlight the contrast mode field.
3. Rotate the small right knob (PUSH CROWN) to select the desired mode: Auto or Manual. Press **ENT** to accept the selection.
4. If “Manual” is selected, the flashing cursor moves to the contrast level field. Rotate the small right knob (PUSH CROWN) to select the desired level. Press **ENT** to accept the selection.

Setup 2 Page: Nearest Airport Criteria

To set the minimum runway length and runway surface:

1. Select "Nearest Airport Criteria" from the setup 2 page, using the steps described on page 159.
- 2a. The flashing cursor highlights the runway surface field. Rotate the small right knob (PUSH) to select the desired surface. The following options are available:
 - Any surface
 - Hard surfaces Only
 - Hard / Soft surfaces
 - Water landings only
3. Press **ENT** to accept the runway surface selection.
4. The flashing cursor moves to the minimum runway length field. To enter a different minimum runway length, use the small (PUSH) and large (PUSH) right knobs to enter the desired length. Press **ENT** when finished.

Setup 2 Page: COM Configuration

To set the COM channel spacing:

1. Select "COM Configuration" from the setup 2 page, using the steps described on page 159.
- 2b. The flashing cursor highlights the channel spacing field. Rotate the small right knob (PUSH) to select the desired channel spacing: 8.33 kHz or 25.0 kHz. Press **ENT** when finished.


Restoring Factory Settings

When making changes to any *setup 2 page* option, a "Restore Defaults?" menu selection allows you to restore the original factory settings (for the selected option).

To restore a setup 2 option to the original factory settings:

1. Select the desired menu option from the setup 2 page, using the steps described on page 159.
- 2c. Press **MENU** to display a page options window.
3. With "Restore Defaults?" highlighted, press **ENT**.







9

AUX PAGES

Setup 2

This page intentionally blank.



Section 10

Messages, Abbreviations and Navigation Terminology

Messages

The GNS 430 uses a flashing “MSG” annunciator at the bottom of the screen (directly above the **MSG** key) to alert you of any important information or warnings. While most messages are advisory in nature, warning messages may require your intervention.

Whenever the “MSG” annunciator flashes, press the **MSG** key to display the message. Press **MSG** again to return to the previous page.

The following is a list of available messages and their meanings:

Airspace ahead -- less than 10 minutes—Your GPS-calculated course is projected to enter a special use airspace within 10 minutes. This message is automatically disabled within 30 nautical miles of an arrival airport, when an approach is loaded.

Airspace near and ahead—Your GPS-calculated position is within 2 nautical miles of the boundary of a special use airspace and your course is projected to enter the airspace within 10 minutes. This message is automatically disabled within 30 nautical miles of an arrival airport, when an approach is loaded.

Altitude input failure—The GNS 430 is configured to receive altitude serializer data (Icarus, Rosetta or Shadin) and it is not being received. Or, the data was being received, but has been interrupted. If a grey code altitude input is available, it will be used instead. If the problem persists, contact your GARMIN dealer and check the

installation and installation settings. When this message occurs, no pilot action is required if enough satellites are available for a 3D position fix (provided no RAIM warnings are present). However, if only a 2D position fix is possible, the pilot should maintain the GPS altitude within 1,000 feet of pressure altitude—by entering the altitude on the *position* page.

Approach is not active—The approach could not transition to “active”, at 2 nautical miles or closer to the FAF. Verify that “SUSP” DOES NOT appear directly above the **OBS** key, indicating the auto waypoint sequencing is suspended. This message also appears if Receiver Autonomous Integrity Monitoring (RAIM) has determined that sufficient GPS satellite coverage DOES NOT exist for the phase of flight you are currently in (along with a “RAIM not available from FAF to MAP” message).

Approaching target altitude—The current GPS-computed altitude is within 500 feet of the final Vertical Navigation target altitude.

Approaching VNAV profile—You are within one minute of reaching the initial Vertical Navigation descent, or climb, point.





Arrival at waypoint [waypoint name]—You are within the arrival alarm circle for the indicated waypoint. The size of the arrival alarm circle is defined from the “CDI / alarms” menu option on the *setup 1* page.

Cannot navigate locked FPL—You have attempted to navigate a flight plan (FPL) with one or more locked waypoints. A waypoint can be “locked” when the NavData® card is replaced and the waypoint(s) does not exist in the new database.

Can’t change an active waypoint—An attempt has been made to modify the position of the active “to” or “from” waypoint. The GNS 430 will not allow modifications to user waypoints currently being utilized for navigation guidance.

Can’t delete an active or FPL waypoint—An attempt has been made to delete the active “to” or “from” waypoint. The GNS 430 will not allow you to delete user waypoints currently being utilized for navigation guidance.

CDI key stuck—The  key is stuck in the enabled (or pressed”) state. Try pressing the  key again to cycle its operation. If the message persists, contact your GARMIN dealer for assistance.

Check unit cooling—The GNS 430 has detected excessive display backlighting temperature. The backlighting has been automatically dimmed to reduce the temperature. Check for adequate ventilation or check cooling air flow. Contact your GARMIN dealer for assistance.

COM has failed—The GNS 430 has detected a failure in its communications transceiver. The COM transceiver is not available and the unit should be returned to your GARMIN dealer for service.

COM is not responding—Internal system-to-system communication between the main processor and the COM transceiver has failed. Operational status of the COM transceiver is unknown and the unit should be returned to your GARMIN dealer for service.

COM needs service—The GNS 430 has detected a failure in its communications transceiver. The COM transceiver may still be usable, but the unit should be returned (at your earliest convenience) to your GARMIN dealer for service.

COM push-to-talk key stuck—The external push-to-talk (PTT) switch is stuck in the enabled (or “pressed”) state. Try pressing the PTT switch again to cycle its operation. If the message persists, contact your GARMIN dealer for assistance.

COM remote transfer key is stuck—The remote COM transfer switch is stuck in the enabled (or “pressed”) state. Try pressing the switch again to cycle its operation. If the message persists, contact your GARMIN dealer for assistance.

COM transfer key stuck—The  key is stuck in the enabled (or “pressed”) state. Try pressing the  key again to cycle its operation. If the message persists, contact your GARMIN dealer for assistance.

COM transmitter power has been reduced—The GNS 430 has detected excessive unit temperature and/or an insufficient voltage level. The COM transceiver transmit power has been automatically reduced to compensate for the condition. For excessive temperatures, check for adequate ventilation or check cooling air flow. If the message persists, contact your GARMIN dealer for assistance.

Data card failure—The GNS 430 has detected a problem with the NavData® card. The data is not usable and the card should be returned to Jeppesen or your GARMIN dealer.

Data transfer cancelled (crossfill is busy)—An attempt to transfer flight plan data during a unit-to-unit crossfill was cancelled. The host unit is busy or unable to communicate. Wait until any previous crossfill operation is complete, before re-attempting the transfer.

Data transfer cancelled (data invalid)—An attempt to transfer a single user waypoint during a unit-to-unit crossfill was cancelled. No waypoint was specified on the *crossfill page*. Select a user waypoint and re-attempt the transfer.

Data transfer cancelled (version mismatch)—An attempt to transfer data during a unit-to-unit crossfill was cancelled. The database versions of the two GNS 430s are not identical. If necessary, update the database(s) so they match. Contact Jeppesen or your GARMIN dealer for assistance.

Data transfer error, please re-transmit—An error was detected during unit-to-unit crossfill of user data (user waypoints and/or flight plans). The data transfer should be re-attempted.

Data transfer is complete—The unit-to-unit crossfill of user waypoint data has finished.



Database changed, validate user modified procedures—You have modified one or more approaches, departures or arrivals from their original published form. When the NavData® card is replaced (database update), you must manually verify your changes in the new database. This message will occur each time a flight plan containing a modified procedure (generated from a prior database version) is activated. To eliminate the message, re-create the flight plan from the new database, then make the desired modifications.

Degraded accuracy—GPS position accuracy has been degraded and RAIM is not available. Poor satellite geometry (or coverage) has resulted in a horizontal DOP greater than 4.0. Additional cross-checking using another navigation source is required to verify the integrity of the GPS position.

Display backlight failure—The GNS 430 has detected a failure in the display backlighting. The unit should be taken to your GARMIN dealer for service.

Do not use for navigation—The GNS 430 is in Demo Mode and must not be used for actual navigation.



FPL has been truncated—The flight plan (FPL) was truncated because not enough room existed to insert an approach, departure or arrival. This may occur upon power up when a database change increases the number of waypoints within an instrument procedure.

FPL is full - remove unnecessary waypoints—An attempt has been made to add more than 31 waypoints to a flight plan (FPL). The GNS 430 will not allow more than 31 waypoints per flight plan.

FPL leg will not be smoothed—The upcoming flight plan (FPL) leg is too short for smooth waypoint transitions. Expect a rapid change in the CDI.

FPL waypoint is locked—At least one flight plan (FPL) waypoint is locked because the waypoint has been removed from the current NavData® card (database change), the data card is missing, or the data card has failed.

FPL waypoint moved—The position data for one or more flight plan (FPL) waypoints moved at least 0.33 arc minutes in the current NavData® card (database change).

FPL waypoint was deleted—At least one flight plan (FPL) way-

point is no longer available when a new NavData® card was installed (database change).

G/S has failed—The GNS 430 has detected a failure in its glideslope receiver. The glideslope receiver is not available and the unit should be returned to your GARMIN dealer for service.

G/S is not responding—Internal system-to-system communication between the main processor and the glideslope receiver has failed. Operational status of the glideslope receiver is unknown and the unit should be returned to your GARMIN dealer for service.

G/S needs service—The GNS 430 has detected a failure in its glideslope receiver. The glideslope receiver may still be usable, but the unit should be returned (at your earliest convenience) to your GARMIN dealer for service.

GPS has failed—The GNS 430 has detected a failure in its GPS receiver. The GPS receiver is not available and the unit should be returned to your GARMIN dealer for service.

GPS is not responding—Internal system-to-system communication between the main processor and the GPS receiver has failed. Operational status of the GPS receiver is unknown and the unit should be returned to your GARMIN dealer for service.

GPS needs service—The GNS 430 has detected a failure in its GPS receiver. The GPS receiver may still be usable, but the unit should be returned (at your earliest convenience) to your GARMIN dealer for service.

GPS stored data was lost—Satellite almanac, ephemeris and time data have been lost due to a memory battery failure, system reset or data expiration (data over six months old).

Heading input failure—The heading selection on the external HSI's (or CDI's) OBS course selector cannot be read properly. Your GARMIN dealer may need to check the installation.

Inside airspace—Your GPS-calculated position lies within the boundaries of a special use airspace. This message is automatically disabled within 30 nautical miles of an arrival airport, when an approach is loaded.

Invalid closest pt of FPL—A closest point cannot be created from the waypoint entered on the “Closest point of flight plan” window. This occurs when the selected waypoint is beyond the limits of all legs in the flight plan, too far away, or when a unique waypoint name for the closest point cannot be created.

Invalid FPL modification—An attempt was made to modify the final course segment (FAF to MAP) of an instrument approach. The GNS 430 will not allow the modifications.

Invalid waypoint ident—An attempt was made to create a user waypoint with an invalid name. The GNS 430 will not allow spaces between characters in the waypoint name.

MAIN processor requires service—The GNS 430 has detected a failure in the main system processor. The GNS 430 is not usable and should be taken to your GARMIN dealer for service.

Memory battery low—The internal battery that sustains user memory is low and should be replaced by a GARMIN dealer as soon as possible. Failure to do so may result in loss of stored data, including flight plans, user waypoints, unit settings and satellite data.



Near airspace -- less than 2 nm—Your GPS-calculated position is within 2 nautical miles of a special use airspace boundary, but you are not projected to enter the airspace. This message is automatically disabled within 30 nautical miles of an arrival airport, when an approach is loaded.

Need altitude - display position page—The GPS receiver needs altitude input in order to start and/or continue 2D navigation. Select the position page and verify the altitude reading. If the altitude is in error by more than 500 feet, enter the current altitude as accurately as possible. An inaccurate altitude will directly translate into inaccurate position information.

No altitude input is being received—No altitude data is being received from RS-232 (Serializer: Icarus, Rosetta or Shadin) or grey code inputs. If the problem persists, contact your GARMIN dealer and check the installation and installation settings. When this message occurs, no pilot action is required if enough satellites are available for a 3D position fix (provided no RAIM warnings are present). However, if only a 2D position fix is possible, the pilot should maintain the GPS altitude within 1,000 feet of pressure altitude—by entering the altitude on the *position page*.



No basemap data available—The GNS 430 has detected a failure in the built-in basemap (land data) memory. Land data will not appear on the *map page*. Other unit functions will continue to work normally, however the GNS 430 should be taken to your GARMIN dealer for service at your earliest convenience.

Non-WGS84 wpt navigation—The active “to” and/or “from” waypoints are based upon a map datum other than WGS 84 and cannot be converted from that map datum to WGS 84. Expect some error in the position of the waypoint(s) and cross-check with an alternate means of navigation.

Not receiving input data on 429 Channel #1—No data has been received on the ARINC 429 channel #1 connection for a period exceeding five seconds. If the problem persists, the installation should be checked by your GARMIN dealer.

Not receiving input data on 429 Channel #2—No data has been received on the ARINC 429 channel #2 connection for a period exceeding five seconds. If the problem persists, the installation should be checked by your GARMIN dealer.

Not receiving input data on 232 Channel #1—No data has

been received on the RS-232 channel #1 connection for a period exceeding ten seconds. If the problem persists, the installation should be checked by your GARMIN dealer.

OBS key stuck—The **OBS** key is stuck in the enabled (or pressed) state. Try pressing the **OBS** key again to cycle its operation. If the message persists, contact your GARMIN dealer for assistance.

Poor GPS coverage—The GPS receiver cannot acquire a sufficient number of satellites to compute a position and provide navigation.

Power down and re-initialize—The GNS 430 cannot calculate a position due to abnormal satellite conditions. The unit is unusable until power has been cycled off and back on. Abnormal satellite conditions may exist and you may need to use an alternate means of navigation.

RAIM is not available—Receiver Autonomous Integrity Monitoring (RAIM) has determined that sufficient GPS satellite coverage DOES NOT exist for the phase of flight you are currently in. (The CDI/HSI NAV flag will also appear.) Select an alternate source for navigation guidance, such as the GNS 430's VLOC receiver.

RAIM not available from FAF to MAP waypoints—When performing an instrument approach, Receiver Autonomous Integrity Monitoring (RAIM) has determined that sufficient GPS satellite coverage DOES NOT exist to meet the required protection limits. Select an alternate source for navigation guidance, such as the GNS 430's VLOC receiver (for a VOR or localizer-based approach).

RAIM position warning—Although sufficient GPS satellite coverage may exist, Receiver Autonomous Integrity Monitoring (RAIM) has determined the information from one or more GPS satellites may be in error. The resulting GPS position may be in error beyond the limits allowed for your current phase of flight. Cross-check your position with an alternate navigation source. If the warning occurs during a final approach segment (FAF to MAP), execute the published missed approach.

Scheduler message -- [user entered text]—The user-entered scheduler message time has expired, and the scheduler message is displayed.

Searching the sky—The GNS 430 is searching the sky for GPS satellite almanac data or the GPS receiver is in AutoLocate Mode. Allow the unit to complete data collection (approximately 5 minutes) before turning it off.

Select appropriate frequency for approach—You are inbound and within 3 nautical miles of the FAF; and the active VLOC frequency does not match the published frequency for the approach. Tune the standby VLOC frequency to the proper frequency and press the **V** key to “activate” the frequency.

Select auto sequence mode—The **OBS** key was pressed, disabling auto sequencing of waypoints (in a flight plan or instrument procedure). The **OBS** key should be pressed again to enable auto sequencing, because 1) no destination waypoint has been selected, or 2) the GPS receiver cannot currently determine its position.



Select VLOC on CDI for approach—You are inbound and within 3 nautical miles of the FAF; and the active approach is not a GPS-approved approach. Verify that the VLOC receiver is tuned to the proper frequency and press the **CDI** key to display “VLOC” (directly above the **CDI** key).

Set course to [###]°—The course select for the external CDI (or HSI) should be set to the specified course. The message will only occur when the current selected course is greater than 10° different from the desired track.

Steep turn ahead—This message appears approximately one minute prior to a turn in one of the following three conditions: 1) the turn requires a bank angle in excess of 25° in order to stay on course, 2) the turn requires a course change greater than 175°, or 3) during a DME arc approach the turn anticipation distance exceeds 90 seconds.

Stored data was lost—All user waypoints, flight plans and system settings have been lost due to a memory battery failure or system reset.



Timer has expired—The count down timer has reached zero.

Unit configuration has changed—The GNS 430 has detected a failure (during initial power up) in its system configuration. Some system components may be unusable. Try cycling power off and back on. If the message persists, contact your GARMIN dealer for assistance.

User card format unknown—A data card has been inserted, but the format of the card is not recognized.

VLOC has failed—The GNS 430 has detected a failure in its VLOC receiver. The VLOC receiver is not available and the unit should be returned to your GARMIN dealer for service.

VLOC is not responding—Internal system-to-system communication between the main processor and the VLOC receiver has failed. Operational status of the VLOC receiver is unknown and the unit should be returned to your GARMIN dealer for service.

VLOC needs service—The GNS 430 has detected a failure in its VLOC receiver. The VLOC receiver may still be usable, but the unit should be returned (at your earliest convenience) to your GARMIN dealer for service.

VLOC remote transfer key is stuck—The remote VLOC transfer switch is stuck in the enabled (or “pressed”) state. Try pressing the switch again to cycle its operation. If the message persists, contact your GARMIN dealer for assistance.

VLOC transfer key stuck—The  key is stuck in the enabled (or “pressed”) state. Try pressing the  key again to cycle its operation. If the message persists, contact your GARMIN dealer for assistance.

Waypoint already exists—The name you have entered for a user waypoint already exists in memory.

Waypoint(s) have been replaced—One or more user waypoints were updated during a unit-to-unit crossfill operation.

Waypoint memory is full—You have used all 1000 user waypoint locations in the GNS 430’s memory. Delete unwanted waypoint to make room for new entries.

WGS 84 datum has been selected—The system map datum was changed to WGS 84 because the selected map datum was removed from the current NavData® card (database update), the data card is missing or the data card has failed.

Abbreviations

The following is a list of abbreviations used on the GNS 430 and their meanings:

ACTV— Active

ALT— Altitude

APPRCHING—Approaching

APR— Approach

APT— Airport

ARSPC— Airspace

ARTCC— Air Route Traffic Control Center

ARVL— Arrival

AUX— Auxiliary

AVGAS— Aviation-grade Gasoline

AVTN— Aviation

BARO— Barometric Pressure

BRG— Bearing To

°C— Degree Celsius

C/V— COM/VLOC

CAS— Calibrated Airspeed

CDI— Course Deviation Indicator

CLR— Clear

COM— Communications Transceiver

CRSR— Cursor

CTA— ICAO Control Area

CTAF— Common Traffic Advisory Frequency

CTR— Center (see ARTCC)

CTS— Course To Steer

CUM— Cumulative

DB— Database

DEN— Density

DEP— Departure

DIS— Distance

DME— Distance Measuring Equipment

DOP— Dilution of Precision

DTK— Desired Track



10

**MESSAGES,
ABBREVIATIONS
& NAV TERMS**

EFF— Efficiency
ELEV— Elevation
ENDUR—Endurance
ENR— En Route
ENT— Enter
EPE— Estimated Position Error
ESA— En Route Safe Altitude
ETA— Estimated Time of Arrival
ETE— Estimated Time En Route

°F— Degrees Fahrenheit
FF— Fuel Flow
FOB— Fuel On Board
FPL— Flight Plan
fpm— Feet Per Minute

FREQ— Frequency
FSS— Flight Service Station
ft— Feet

G/S— Glideslope
gl— gallons
GPS— Global Positioning System
GS— Ground Speed

HDG— Heading
hg— Inches of Mercury
HWY— Highway

ID— Identifier
ig— Imperial Gallons
ILS— Instrument Landing System
IND— Indicated
INT— Intersection
INTEG— Integrity

kg— Kilograms
kHz— Kilohertz

km— Kilometers
kph— Kilometers Per Hour
kt— Knots

LAT/LON—Latitude/Longitude
lb— Pounds
LCL— Local
LFOB— Left-over Fuel On Board
LOC— Localizer
LRES— Left-over Fuel Reserve Time
Lrg— Large
lt— Liters

°M— Degrees Magnetic
m— Meters
mb— Millibars of Pressure
Med— Medium
MHz— Megahertz
mi— Statute Miles
MOA— Military Operations Area
mph— Statute Miles Per Hour
mpm— Meters Per Minute

mps— Meters Per Second
MSA— Minimum Safe Altitude
MSG— Message
MSL— Mean Sea Level
mul— Multicom

NATNL— National
NAV— Navigation
NAVAID— Navigational Aid
NDB— Non-Directional Radio Beacon
nm— Nautical Miles
NRST— Nearest
NUM— Number

OBS— Omnibearing Selector

P.POS— Present Position
PROC— Procedure(s)
PROV— Province

PWR— Power

RAD— Radial
RAIM— Receiver Autonomous Integrity Monitoring
REF— Reference
REQ— Required / Requirements
RESTRICTD—Restricted
RNG— Range
RX— Receive

SID— Standard Instrument Departure
Sml— Small
SPD— Speed
SQ— Squelch
SRFC— Surface
STAR— Standard Terminal Arrival Route
SUA— Special Use Airspace

°T— Degree True
TACAN— Tactical Air Navigation
TAS— True Airspeed
TAT— Total Air Temperature
TEMP— Temperature



TERM— Terminal
TKE— Track Angle Error
TMA— ICAO Terminal Control Area
TRANS— Transition
TRK— Track (also Ground Track)
TRSA— Terminal Radar Service Area
twr— Tower
TX— Transmit

uni— Unicom
UTC— Coordinated Universal Time (also GMT or “zulu”)

VAR— Variation
VER— Version




10

MESSAGES, ABBREVIATIONS & NAV TERMS

VFR—	Visual Flight Rules
VLOC—	VOR/Localizer Receiver
VNAV—	Vertical Navigation
VOL—	Volume
VOR—	VHF Omnidirectional Radio Range
VS—	Vertical Speed
VSR—	Vertical Speed Required
WPT—	Waypoint
WX—	Weather
XTK—	Crosstrack Error

Navigation Terms

The following navigation terms are used on the GNS 430:



ALT(altitude)—Height above mean sea level (MSL).

BRG(bearing)—The compass direction from your present position to a destination waypoint.

CAS(calibrated airspeed)—Indicated airspeed corrected for instrument errors.

CTS(course to steer)—The recommended direction to steer in order to reduce

course error or stay on course. Provides the most efficient heading to get back to the desired course and proceed along your flight plan.

CUM(cumulative)—The total of all legs in a flight plan (such as “cumulative distance”).

DIS(distance)—The “great circle” distance from your present position to a destination waypoint.

DOP(dilution of precision)—A measure of satellite geometry quality on a scale of one to ten (lowest numbers are best, highest numbers are worst).

DTK(desired track)—The desired course between the active “from” and “to” waypoints.

EFF(efficiency)—A measure of fuel consumption, expressed in distance per fuel units (e.g., nautical miles per gallon).

ENDUR(endurance)—Flight endurance, or total available flight time based upon available fuel.

EPE(estimated position error)—A measure of satellite geometry quality and additional factors, expressed as a horizontal position error in feet or meters.



ESA(en route safe altitude)—The recommended minimum altitude within ten miles, left or right, of your desired course on an active flight plan or direct-to.

ETA(estimate time of arrival)—The estimated time at which you will reach your destination waypoint, based upon current speed and track.

ETE(estimated time en route)—The time it will take to reach the destination waypoint, from present position, based upon current ground speed.

FF(fuel flow)—The fuel flow rate, expressed in fuel units per time (e.g., gallons per hour).

FOB(fuel on board)—The total amount of usable fuel on board the aircraft.

GS(ground speed)—The velocity you are travelling relative to a ground position.

10

MESSAGES, ABBREVIATIONS & NAV TERMS

HDG(heading)—The direction an aircraft is pointed, based upon indications from a magnetic compass or a properly set directional gyro.

IND(indicated)—Information provided by properly calibrated and set instrumentation in the aircraft panel (e.g., “indicated altitude”).

LFOB(left-over fuel onboard)—The amount of fuel remaining on board after the completion of a one or more legs of a flight plan (or a direct-to).

LRES(left-over fuel reserve)—The amount of fuel remaining on board after the completion of a one or more legs of a flight plan (or a direct-to), expressed in time and based upon a known fuel consumption (flow) rate.


MSA(minimum safe altitude)—Uses Grid Minimum Off-route Altitudes (Grid MORAs) to determine a safe altitude within ten miles of your present position. Grid MORAs are one degree latitude by one degree longitude in size and clear all reference points within the grid by 1000 feet in areas where the highest reference point is 5000 feet MSL or lower. If the highest reference point is above 5000 feet, the Grid MORA will clear the highest reference point by 2000 feet.

TKE(track angle error)—The angle difference between the desired track and your current track. An arrow indicates the proper direction to turn to reduce TKE to zero.

TRK(track)—The direction of movement relative to a ground position. Also referred to as “ground track”.

VSR(vertical speed required)—The vertical speed necessary to descend/climb from current position and altitude to a defined target position and altitude, based upon your current ground speed.

XTK(crosstrack error)—The distance you are off a desired course in either direction, left or right.



Appendix A: NavData Card Use

The Jeppesen NavData® card supplied with your GNS 430 can be installed or removed when the GNS 430 is on or off. Insert the card with the swing arm handle at the bottom and the label facing to the left (see illustration right). If the NavData card is not present when the unit is turned on, you will receive a “No Jeppesen Aviation Database - Limited to user defined waypoints” message on the *database confirmation page*. If the NavData card is removed during operation, a “Data card removed-Unit will restart in 30 seconds” warning. A counter will begin to count down and, if the card is not replaced within 30 seconds, the GNS 430 will automatically reinitialize. You may also reinitialize the unit manually by pressing **ENT**.

To insert the NavData card:

- 1a. Place the card into the NavData card slot, with the label facing to the left and the swing arm handle at the bottom front.



NOTE

There are two data card slots on the face of the GNS 430. The Jeppesen NavData® card should be inserted in the left-most slot. The second slot is provided for future options and expansion capabilities.

- 2a. Press the NavData card into place until it seats on the internal connector and the front of the card is flush with the face of the GNS 430 unit.
- 3a. If the swing arm handle is up, gently lower the handle and push it into place—flush with the face of the GNS 430 unit.

To remove the NavData card:

- 1b. Gently press on the tab—using a slight upward motion—at the front center of the NavData card. This will partially deploy the swing arm handle.
- 2b. Rotate the swing arm handle upward (and outward) until it locks into place, perpendicular to the face of the GNS 430 unit.
- 3b. Grasp the top and bottom surfaces of the swing arm handle, between your thumb and forefinger, and pull directly away from the face of the GNS 430 unit to unseat the connector and remove the NavData card.



APPENDIX
B **SPECIFICATIONS**

Appendix B: Specifications

PHYSICAL

Unit Size:	6.25"W x 11.00"D x 2.65"H (159mm x 279mm x 67mm)
Unit Weight:	6.6 pounds installed (3.0 kg)

POWER

Input:	27.5 Volts DC (-0x version) 13.8/27.5 Volts DC (-1x version)
--------	---

ENVIRONMENTAL

Temperature:	-20°C to +55°C (operating range) (-4°F to +131°F)
Humidity:	95% non-condensing
Altitude:	-1,500 ft to 50,000 ft (-457m to 15,240m)

GPS PERFORMANCE

Receiver:	12 parallel channel PhaseTrac12™
Acquisition Time:	12 seconds (warm) 45 seconds (cold)

Update Rate:	Once per second, continuous
Accuracy:	Position—15 meters (49 ft) RMS* Velocity—0.1 knot RMS steady state
Dynamics:	999 kts maximum velocity 6g maximum acceleration

VHF COM PERFORMANCE

Channels:	760 (25 kHz spacing) or 2280 (8.33 kHz spacing)
Frequency Range:	118.000 MHz to 136.975 MHz
Transmit Power:	10 watts minimum

VOR PERFORMANCE

Frequency Range:	108.00 MHz to 117.95 MHz
------------------	--------------------------

LOCALIZER PERFORMANCE

Frequency Range:	108.10 MHz to 111.95 MHz
------------------	--------------------------

GLIDESLOPE PERFORMANCE

Frequency Range:	329.15 MHz to 335.00 MHz
------------------	--------------------------

INTERFACES

ARINC 429; Aviation RS-232; CDI/HSI; RMI (digital: clock/data); Superflag Out; Altitude (serial: Icarus, Shadin, Rosetta or encoded: Gillham/Greycode); Fuel Sensor; Fuel/Air Data

***MAP
DATUMS***

APPENDIX
C

APPENDIX **C** ***MAP DATUMS***

NAD27 Canada	Canada (including Newfoundland Island)
NAD27 Canal Zone	Canal Zone
NAD27 Caribbean	Caribbean (Barbados, Caicos Islands, Cuba, Dom. Rep., Grd. Cayman, Jamaica, Leeward and Turks Islands)
NAD27 Centrl America	Central America (Belize, Costa Rica, El Salvador, Guatemala, Honduras, Nicaragua)
NAD27 CONUS	Mean Value (Continental U.S.)
NAD27 Cuba	Cuba
NAD27 Greenland	Greenland (Hayes Peninsula)
NAD27 Mexico	Mexico
NAD27 San Salvadr Is	San Salvador Island
NAD83	North American 1983- Alaska, Canada,

Nahrwan Masirah Is	Central America, CONUS, Mexico
Nahrwan Saudi Arabia	Masirah Island (Oman)
Nahrwan Unitd Arab E	Saudi Arabia
Naparima BWI	United Arab Emirates
Netherland TRIAG '21	Trinidad and Tobago
NOU TRIAG France	Netherlands
NOU TRIAG Luxembourg	France
Observatorio 1966	Luxembourg
Old Egyptian	Corvo and Flores Islands (Azores)
Old Hawaiian Kauai	Egypt
Old Hawaiian Maui	Kauai
Old Hawaiian MEAN	Maui
Old Hawaiian Oahu	Mean Value
Oman	Oahu
Ord Srv Grt Britain	Oman
Pico De Las Nieves	England, Isle of Man, Scotland, Shetland Islands, Wales
Pitcairn Astro 1967	Canary Islands
PORTUGUESE 1973	Pitcairn Island
POTSDAM	Portugal
Prov So American '56	Germany
Prov SO Chilean 1963	Bolivia, Chile, Colombia, Ecuador, Guyana, Peru, Venezuela
Puerto Rico	South Chile
Qatar National	Puerto Rico & Virgin Isl.
Qornoq	Qatar
Reunion	South Greenland
Rome 1940	Mascarene Island
	Sardinia Island

RT 90	Sweden
Santo (Dos)	Espirito Santo Island
Sao Braz	Sao Miguel, Santa Maria Islands (Azores)
Sapper Hill 1943	East Falkland Island
Schwarzeck	Namibia
South American 1969	Argentina, Bolivia, Brazil, Chile, Colombia, Ecuador, Guyana, Paraguay, Peru, Venezuela, Trinidad/Tobago
South Asia	Singapore
SouthEast Base	Porto Santo and Madeira Islands
SouthWest Base	Faial, Graciosa, Pico, Sao Jorge and Terceira Islands (Azores)
Tananarive obsv 1925	Madagascar
Timbalai 1948	Brunei and East Malaysia (Sarawak and Sabah)
Tokyo	Japan, Korea, Okinawa
Tristan Astro 1968	Tristan da Cunha
Viti Levu 1916	Viti Levu Island/Fiji Islands
Wake-Eniwetok 1960	Marshall Islands
WGS 72	World Geodetic System 1972
WGS 84	World Geodetic System 1984
YACARE	Uruguay
Zanderij	Surinam

Appendix D: Troubleshooting Q & A

This section is designed to answer some of the common questions regarding the GNS 430's capabilities and operation. If you have a problem operating the unit, read through this appendix and refer to the reference section noted. If you don't find answers to your particular question here, use the index to find the appropriate section elsewhere in this manual. If, after reading through the appropriate reference section, you still haven't found the answer to your question, please see your authorized dealer or contact GARMIN directly at the address or phone numbers listed on page iv. GARMIN is dedicated to supporting its products and customers.



What is RAIM, and how does it affect approach operations?

RAIM is an acronym for Receiver Autonomous Integrity Monitoring, a GPS receiver function that performs a consistency check on all tracked satellites. RAIM ensures that the available satellite geometry will allow the receiver to calculate a position within a specified protection limit (2 nautical miles for oceanic and en route, 1 nm for terminal and 0.3 nm for non-precision approaches).

During oceanic, en route and terminal phases of flight, RAIM will be available nearly 100% of the time. Because of the tighter protection limit on approaches, there may be times when RAIM is not available. The GNS 430 automatically monitors RAIM and will warn you with an alert message (see Section 10) when it is not available, and the INTEG annunciator () will appear at the bottom left corner of the screen. If RAIM is not available when crossing the FAF, the pilot must fly the missed approach procedure. The GNS 430's RAIM prediction function (see page 146) will also allow you to see whether RAIM will be available for a specified date and time.

NOTE

If RAIM is not predicted to be available for the final approach course, the approach will not become active—as indicated by an “Approach is not active” message, a “RAIM not available from FAF to MAP” message and the INTEG annunciator.

APPENDIX D TROUBLE- SHOOTING

Why aren't there any approaches available for my flight plan?

Approaches are available for the final destination airport in a flight plan or as a direct-to (keep in mind that some VOR/VORTAC identifiers are similar to airport identifiers). If a destination airport does not have a GPS approach, the GNS 430 will indicate “NONE” for the available procedures—as listed on the *airport approach page*. For more information on selecting an approach, see page 66.



What happens when I select an approach? Can I store a flight plan with an approach, departure or arrival?

Whenever you load an approach, departure or arrival into the active flight plan, a set of approach, departure or arrival waypoints is inserted into the flight plan—along with a header line describing the instrument procedure you selected. The original en route portion of the flight plan will remain active, unless you “Activate” the instrument procedure; which may be done when the procedure is loaded or at a later time.

Flight plans can also be stored with an approach, departure or arrival. Keep in mind that the active flight plan is erased when the unit is turned off and overwritten when another flight plan is activated. When storing flight plans with an approach, departure or arrival, the GNS 430 will use the waypoint information from the current database to define the waypoints. If the database is changed or updated, the GNS 430 will automatically update the information if the procedure has not been modified. If an approach, departure or arrival procedure is no longer available, the flight plan will become locked until the procedure is deleted from the flight plan or the correct database is installed. For information on loading an approach, departure or arrival, see page 66. See page 57 for instructions on saving and copying flight plans.



Can I file slant Golf (“/G”) using my GPS?

Yes, you may file your flight plan as /G if your GNS 430 is a certified A1 or A2 installation. If you are flying en route, you may fly /G with an expired database only after you have verified all route waypoints. Non-precision approaches may not be flown with an expired database. See your approved Airplane Flight Manual Supplement for more information.

What does the **OBS** key do and when do I use it?

The **OBS** key is used to select manual (OBS mode) or automatic sequencing of waypoints. Activating OBS mode (as indicated by an **OBS** annunciation directly above the **OBS** key) holds your current 'active to' waypoint as your navigation reference and prevents the GPS from sequencing to the next waypoint. When OBS mode is cancelled, automatic waypoint sequencing is selected, and the GNS 430 will automatically select the next waypoint in the flight plan once the aircraft has crossed the present active-to waypoint.

NORMAL (no "OBS" annunciator)


Automatic sequencing of waypoints
Change in HSI does not affect CDI deflection
Always navigates 'TO' the active waypoint
Must be in this mode for final approach course

OBS

Manual sequencing- 'holds' on selected waypoint
Manually select course to next waypoint from HSI
Will indicate 'TO' or 'FROM' waypoint
Cannot be set for final approach course or published holding patterns

Whenever OBS mode is active, the GNS 430 allows you to select the desired course to/from a waypoint using the HSI (much like a VOR) and display a to/from flag for the active-to waypoint. If an external course input is not available, you may select the OBS course on-screen, via a "Select OBS Course pop-up window. With OBS mode cancelled, the CDI will always display a 'TO' indication for the next waypoint once you've crossed the active waypoint (provided the active waypoint is not the last waypoint). Refer to page 72 for an example using the **OBS** key.

One application for the **OBS** key is holding patterns. The **OBS** key is used to suspend waypoint sequencing and select the desired course along the waypoint side of the hold. For many approach operations, setting and resetting of waypoint sequencing is automatic. Holding patterns that are part of an approach will automatically disable waypoint sequencing, then re-enable waypoint sequencing after one time around the holding pattern. A "SUSP" annunciation will appear directly above the **OBS** key (see illustration left) to indicate that automatic waypoint sequencing is temporarily suspended and course selection is not available. If more than one trip around the holding pattern is desired, press the **OBS** key to again suspend waypoint sequencing. An example of this operation is an approach which begins with a holding pattern at the initial approach fix (IAF). See page 73 for more information on the "SUSP" annunciation and approaches with holding patterns.



APPENDIX D **TROUBLE- SHOOTING**

When should I use the **OBS key to return to auto sequencing, and what happens when I do?**

The most common application for using the **OBS** key is the missed approach. The GNS 430 will suspend automatic waypoint sequencing (indicated by a “SUSP” annunciation directly above the **OBS** key; see right) when you cross the missed approach point (MAP). This prevents the GNS 430 from automatically sequencing to the missed approach holding point (MAHP). If a missed approach is required, press the **OBS** key to return to automatic waypoint sequencing and sequence the approach to the MAHP. See page 72 for more information on missed approaches.



Why won't my unit automatically sequence to the next waypoint?

The GNS 430 will only sequence flight plan waypoints when automatic sequencing is enabled (i.e., no “OBS” or “SUSP” annunciation directly above the **OBS** key). For automatic sequencing to occur, you must also cross the “bisector” of the turn you are navigating. The bisector is a perpendicular line between two flight plan legs which crosses through the waypoint common to both legs.

How do I skip a waypoint in an approach, departure or arrival?

The GNS 430 allows you to manually select any approach, departure or arrival leg as the active leg of your flight plan. This procedure is performed from the *active flight plan page* by highlighting the desired waypoint and pressing **→** twice, then **ENT** to approve the selection (see illustration right). The GPS will then provide navigation along the selected flight plan leg, so be sure you have clearance to that position. See page 65 for more information.



How do I fly the GPS with an autopilot and DG heading bug?

If you do not have an HSI, you should make your course selections on the external CDI's OBS knob and the DG heading bug.

When does turn anticipation begin, and what bank angle is expected?


The GNS 430 will smooth adjacent leg transitions based upon a nominal 15° bank angle (with the ability to roll up to 25°) and provide three pilot cues for turn anticipation: 1) A waypoint alert (“NEXT DTK ###°”) will flash in the lower right corner of the screen 10 seconds before the turn



point. 2) A flashing turn advisory (“TURN TO ###°”) will appear in the lower right corner of the screen when you are to begin the turn. Set the HSI to the next DTK value and begin the turn. 3) The To/From indicator on the HSI (or CDI) will flip momentarily to indicate that you have crossed the midpoint of the turn. For more information on waypoint alerts and turn advisories, see section 5.


When does the CDI scale change, and what does it change to?

The GNS 430 will begin a smooth CDI scale transition from the 5.0 nm (enroute mode) to the 1.0 nm (terminal mode) scale 30 nm from the destination airport (see left). The CDI scale will further transition to 0.3 nm (approach mode) at 2 nm prior to the FAF during an active approach. If you are in a missed approach situation, and would like to return the CDI to the 1 nm scale, activate the missed approach sequence by pressing the **OBS** key, as described on page 72. The CDI scale will also be 1.0 nm (terminal mode) within 30 nm of the departure airport.



Why does my CDI not respond like a VOR when OBS mode is active?

Unlike a VOR, the CDI scale used on GPS equipment is based on the cross-track distance to the desired course, not an angular relationship to the destination (see right). Therefore, the CDI deflection on the GPS will be constant regardless of the distance to the destination, and will not become less sensitive when you are further away from the destination. For more information on the CDI scale, see page 153.



CDI Comparison: GPS vs. VOR





What is the correct missed approach procedure? How do I select the missed approach holding point?

To comply with TSO specifications, the GNS 430 will not automatically sequence past the MAP. The active-to waypoint will sequence to the first waypoint in the missed approach procedure, whenever the **OBS** key is pressed AFTER crossing the MAP. All published missed approach procedures must be followed, as indicated on the approach plate.

To execute the missed approach procedure prior to the MAP (not recommended), select the *active flight plan page* and use the **-B>** key (by pressing it twice) to activate the missed approach portion of the procedure, as described on page 65.

How do I re-select the same approach or activate a new approach after a missed approach?

After flying all missed approach procedures, you may reactivate the same approach for another attempt from the *procedures page*. Once you have been given clearance for another attempt, activate the approach from the *procedures page* by highlighting "Activate Approach?" and then pressing **ENT**. The GNS 430 will provide navigation along the desired course to the waypoint and rejoin the approach in sequence from that point on. See page 65 for information on activating a specific flight plan leg.

To activate a new approach for the same airport, select the new procedure from the *procedures page*. To view the *procedures page*, press **PROC** and rotate the large right knob (⦿) to highlight "Select Approach?". Press **ENT** and rotate the large right knob (⦿) to highlight the new approach you want to fly. Press **ENT** to select the approach, then select the desired transition. Finally, highlight "Activate?" at the bottom right corner of the screen and press **ENT** to activate the new approach.

To activate a new approach to a different airport, press **-B>** and select the desired airport using the small (⦿) and large (⦿) right knobs. Press **ENT** to accept the selected airport, then follow the steps in the preceding paragraph to select an approach for the new airport. See section 5 for more information on selecting and activating approaches.

A

Abbreviations171-174
 Accessory list iii
 Activating a flight plan20, 56, 58
 Activating a flight plan leg60, 65
 Activating a flight plan in reverse 56, 58, 61
 Activating an approach67-69
 Active flight plan options60-63
 Active frequency8, 22, 131
 Active leg28
 Active to & from waypoints13
 Active flight plan19, 54, 59
 Addresses, GARMIN i, iv
 Airport approach page94, 102-103
 Airport frequencies39-40, 94, 99-101
 Airport information ...17, 35, 97-107, 123
 Airport location page94, 97
 Airport runway page94, 98
 Airport type97
 Airspace alert messages .18, 127, 152, 154
 Airspace information .34, 97, 127-130, 154
 Altitude41, 45-48, 175
 Altitude buffer152, 154
 Approach procedures15, 66-93
 Approaches ...15, 61, 63, 66-93, 103, 182

Approach available, at airport97
 Arrivals15, 62, 94, 104-105
 Arrival alarm153, 155
 Automatic sequencing184
 Automatic squelch1, 21
 Automatic zoom32, 35-36
 Auto-tuning22-25, 132-135
 AUX page group135-161
 Aviation data (on map)35-36

B

Backlighting159-160
 Bearing (BRG)175
 Bearing measurements (on map)37

C

Cautions ii
 CDI13, 28, 88, 90, 134
 CDI key3, 91, 134
 CDI scale153, 155, 185
 CDI switching86-88, 153, 155
 Checklists145, 147
 CLR (clear) key2, 9-10, 28, 32
 Closest point of flight plan (FPL)63
 COM configuration160-161



COM flip-flop key1, 8, 22, 122
 COM power/volume knob1
 COM squelch21
 COM volume21
 COM window8, 22-23
 Contrast159-160
 Conventions, manualv
 Copying flight plans57-58, 61
 Course from Fix flight plan legs ...82-85
 Creating a flight plan19, 54, 58
 Creating user waypoints112-114
 Crossfill30, 58, 60, 136, 142
 Cursor knobs1-2, 8

D

Data fields ...9, 13, 29, 37, 42, 60, 63, 175
 Date & time154, 158

APPENDIX
E ***INDEX***

Database confirmation page	4
Database subscriptions	4
Declutter map	32
Default NAV page	10, 13, 27-30
Deleting all flight plans	59
Deleting flight plans	57-58, 61
Deleting user waypoints	116-118
Density altitude	139, 142
Departure time	148
Departures	15, 92, 106-107
Desired track (DTK)	175
Direct-to cancelling	53
Direct-to key	2, 12, 49-53, 65, 121, 184
Direct-to manual course selection	53
Direct-to navigation	12, 17, 34, 49-53, 121
Display backlighting	159-160

Display contrast	159-160
Distance (DIS)	175
Distance measurements (on map)	37
DME arcs	76-78
DOP	44, 46, 175
Duplex operations	126
Duplicate waypoints	96

E	
Editing flight plans	55, 64
Editing user waypoints	114-115
Emergency channel select	26
ENT (enter) key	2
EPE	44, 46, 175
Emergency channel select	26
ETA (estimated time of arrival)	175
ETE (estimated time en route)	175

F	
Field elevation	97
Flight plans	19, 54-65
Flight plan catalog	19, 54
Flight plan catalog options	58-59
Flight plan comments	56

Flight planning page	135-144
Flight timers	145-149
Foreword	i
FPL (flight plan) key	3, 19
Frequency fields	8
Frequency selection	8, 9, 14, 22-26, 87, 110, 122, 124-127, 131-133
Frequency usage restrictions	40, 100
Fuel planning	138-139
Fuels available, at airport	97
Full screen map display	37

G	
Generic timer	148
Going to a nearest airport	121
GPS receiver status	44-46
GPS window	8
Graphic track indicator	43
Ground speed (GS)	176
Ground track (TRK)	176

H	
Hold (in an approach)	72-75
Holding patterns	186

I

Ident audio129
 ILS approaches86-92
 Installation of NavData card177
 INTEG annunciation5, 146, 181
 Intersections94, 108
 Inverting flight plans56, 58, 61

K

Key functions1-3
 Knob functions1-2

L

Land data (on map)35-36
 Land data page5
 Loading an approach66-69
 Local time setting158
 Locked waypoints166

M

Magnetic variation153, 156
 Main page groups10, 11
 Manual conventionsv
 Manual sequence (course from fix legs) .85

Map datums154, 157, 179-180
 Map declutter32
 Map direct-to34
 Map orientation35-36
 Map page9-11, 27, 30-38
 Map page options35-38
 Map panning33
 Map scales30-32, 98
 Map setup32, 35-36
 Max speed149
 Measurement units153, 156
 MENU key2
 Message page5
 Messages5, 163-171
 Missed approaches70, 186
 MSA (minimum safe altitude)41
 MSG (message) key3, 5

N

NAV page group10, 27-48
 NAVCOM page10, 13-14, 39-40
 NavData cards177
 Navigation terms175-176
 NDBs94, 109



Nearest airport page16-17, 119-123,
160-161
 Nearest airspace62-65
 Nearest center (ARTCC) page 16, 119, 125
 Nearest FSS page16, 119, 126-127
 Nearest intersection page16, 119
 Nearest NDB page16, 119
 Nearest user waypoints page16, 119
 Nearest VOR page16, 119, 123, 132
 NRST page group16, 119-130

O

OBS key3, 72, 74, 183-186
 Odometer149
 Overzoom32



P

Packing list	iii
Page groups	10, 11, 27, 94
Pointer, panning	33
Position format	154, 157
Position page	10, 41-43
Power/volume knob	1, 4
Power on (normal)	4
PROC (procedures) key	3, 15, 66
Procedure turns	69-71
Procedures page	15, 66-67
PUSH C/V (small left) knob	1
PUSH CRSR (small right) knob	2

R

RAIM prediction	146, 150, 181
-----------------------	---------------

RAIM protection limits	153
Radar coverage information	101
Reference waypoint	42, 112-115
Removal of NavData card	177
Removing approaches	63-64
Removing arrivals	63-64
Removing departures	63-64
Renaming user waypoints	117
RNG (range) key	2
Roads (on map)	35-36
Runway information	98

S

Satellite status page	5, 10, 44-46
Scheduler messages	144
Scroll bar	3, 120
Selecting approaches	61, 66, 68
Selecting arrivals	62, 66
Selecting departures	62, 66
Self-test (power-on)	4
Setup 1 page	135, 152-158
Setup 2 page	135, 159-161
SIDs	62
Signal strength	46

Sky view	46
Software/database versions	146, 151
Sorting flight plans	59
Specifications	178
Standby frequency	6, 22, 133
STARs	62
Stuck microphone	26
SUSP annunciation	72, 74, 183
Sunrise/sunset times	146, 151
Squelch	1, 21
Symbols, default NAV page	28
Symbols, map page	31

T

Table of contents	v-vi
Target pointer	33
Terms	175-176
3D GPS navigation	45
Time	154, 158
Timers	145-149
Track (TRK)	177
Transitions	68-87, 102
Trip planning	135, 140
Trip statistics	146, 149

Trip timer145, 149
True air speed137, 141
Tuning cursor22
Turn advisories70-87, 185
Turn anticipation185
2D GPS navigation45

U

Units of measure153, 156
User waypoint list116-117
User waypoint page94, 111
Utility page135, 145-151

V

Vectors-to-final67, 79-81
Vertical navigation (VNAV)46-48
Vertical navigation page10, 46-48
VLOC audio131
VLOC flip-flop key 1, 8-9, 91, 124, 132-134

VLOC volume knob1
VLOC window8, 23, 131-133
Volume1, 4, 21, 131
VORs94
VSR (vertical speed required)176

W

Warrantyiv
Waypoint alerts70-89, 185
Waypoint entry95, 112-114
Waypoint holding183-184
Waypoint identifiers95
Waypoint list (user waypoints) ...116-117
Waypoint sequencing184
Weather broadcasts109-110
Winds aloft137, 141
WPT page group94-118



