




REV	DESCRIPTION	APPROVED BY	PREPARED BY	DATE
-----	-------------	-------------	-------------	------



FCC ID: K7GT5720 4.5V

NOTE:

1. MATERIAL: 0.05mm THK. WHITE POLYESTER THERMAL TRANSFER LABEL, ZEBRA TECHNOLOGIES Z-ULTIMATE 3000 OF EQUIVALENT, ADHESIVE MATERIAL: ACRYLIC BASED, 3M#467 OR EQUIVALENT.
2. PLEASE PROVIDE THE BLANK LABEL IN ROLL FORM.
3. THE MATERIAL MUST PASS TEST AS THE MOTOROLA'S QA SPECIFICATION REQUEST. THE DETAIL AS FOLLOWS.
 - a> THE RUBBING TEST: INCLUDE USE THE WATER AND PETROLEUM.
 - b> THE HIGH AND LOW TEMP. TEST.
 - c> THE HUMIDITY TEST.

GIANT ELECTRONICS LTD.

TITLE <i>BARCODE LABEL W/O PRINTING</i>		MODEL	
MATERIAL <i>SEE NOTE</i>		DRAWING NO. <i>KEM-PK7183</i>	
TOLERANCE TABLE FOR UNTOLERANCED DIMENSIONS		PROJECTION 	UNIT MM
DIMENSIONS	TOLERANCE	SCALE FREE	DRAWN BY MS ZHANG
0.00 TO 25.00	±0.10	GENERAL DRAFT ANGLE (MAX)	DATE MAR.1,2002
25.01 TO 50.00	±0.15		CHECKED BY QL SUN
50.01 TO 100.00	±0.20	GENERAL WALL THICKNESS	DATE MAR.1,2002
100.00 AND ABOVE	±0.30	DO NOT SCALE DRAWING	APPROVED BY JAMES HO
ANGLES	±1.00'	SHEET 1 OF 1	DATE MAR.1,2002
		SIZE A4	

THE CONTENT OF THIS DOCUMENT IS GIANT INTELLECTUAL PROPERTY AND IS THE PROPERTY OF GIANT. IT IS TO BE TREATED AS STRICTLY CONFIDENTIAL AND IS NOT TO BE DISCLOSED, REPRODUCED, OR USED EXCEPT AS AUTHORIZED IN WRITING BY GIANT ELECTRONICS LTD. IN CONNECTION WITH THE MANUFACTURE, MAINTENANCE AND USE OF THE GIANT EQUIPMENT TO WHICH IT PERTAINS. COPYRIGHT © GIANT ELECTRONICS LTD. ALL RIGHTS RESERVED