

Exhibit 9.2
Effective Radiated Power Test Data

ITS Intertek Testing Services

Company: ORA Electronics
Project #: J98034297
Model: IDR 3000
Engineer: Xi-Ming Yang
Date of test: December 30, 1998

FCC Part 90 Radiated Emissions

Frequency	Antenna Polarity	Reading	Antenna Factor	Pre-amp	Cable Loss	Corrected Reading	ERP	ERP
MHz	H/V	dB(uV)	dB(1/m)	dB	dB	dB(uV/m)	dB(pW)	dBm
806.0	V	113.0	22.0	0.0	0.8	135.8	130.6	38.4
813.5	V	112.5	22.0	0.0	0.8	135.3	130.1	37.9
821.0	V	110.4	22.0	0.0	0.8	133.2	128.0	35.8

Note: 1. All measurement were made at 3 meters

ITS Intertek Testing Services

Company: ORA Electronics
Project #: J98034297
Model: IDR 3000
Engineer: Xi-Ming Yang
Date of test: December 30, 1998

FCC Part 90 Radiated Emissions

Frequency	Antenna	Reading	Antenna	Pre-amp	Cable	Corrected	EIRP	ERP
MHz	Polarity	dB(uV)	Factor	dB	Loss	Reading	dB(pW)	dBm
851.0	V	88.1	22.7	0.0	0.8	111.6	106.4	14.2
858.5	V	85.6	22.7	0.0	0.8	109.1	103.9	11.7
866.0	V	89.0	22.7	0.0	0.8	112.5	107.3	15.1

Note: 1. All measurement were made at 3 meters