
JULY 17, 2003
Federal Communications Commission
Equipment Approval Services
7435 Oakland Mills Road
Columbia, MD 21046

SUBJECT : ImageQuest Co., Ltd.
FCC ID: PJIP4200S001
FCC Part 15 Subpart B Certification

Gentlemen:

Transmitted herewith, on behalf of ImageQuest Co., Ltd. is an application for a FCC Part 15 Subpart B Certification of the following 42-inch PDP Monitor:

FCC ID : PJIP4200S001
Model / Type: PD421 / P4200S001

Attached is the applicant's Cover Letter, External/Internal Photos, Test Set-Up Photos, FCC ID & Label Location, User'S Manual, Block & Circuit Diagram and Test Report.

Should you have any questions or comments concerning the above, please contact the undersigned.



KI SOO KIM
EMC MAMAGER

cc: Mr. YONG TAI KIM ----- R & D CENTER / MANAGER

• Solution for EMI

We, ImageQuest CO.,LTD. , announce that all modifications will be incorporated into each unit sold in the U.S.

- 1. Attach a gasket to the Board cover and main cover**
- 2. Apply a ferrite Core to the Power Cable and Green(Ground) cable drive a screw in Main frame**
- 3. Attach a copper foil between main frame and EMI filter shield**
- 4. Attach a gasket & finger strip to the Stand hole**
- 5. Attach a gasket Speaker input assembly frame and apply ferrite core to signal line**
- 6. Apply a ferrite Core to the speaker cable and shorten it (12 inch)**

(Please refer to next page of the photographs for Solution for EMI)


ImageQuest CO.,LTD.

2003.7.14


**R & D CENTER / MANAGER
YONG TAI KIM**




1. Attach a gasket to the Board cover and main cover





2. Apply a ferrite Core to the Power Cable and Green(Ground) cable drive a screw in Main frame




3. Attach a copper foil between main frame and EMI filter shield






4. Attach a gasket & finger strip to the Stand hole



5. Attach a gasket Speaker input assembly frame and apply ferrite core to signal line



6. Apply a ferrite Core to the speaker cable and shorten it (12 inch)

