



Nemko Dallas, Inc.

Dallas Headquarters:

802 N. Kealy
Lewisville, TX 75057
Tel: (972) 436-9600
Fax: (972) 436-2667

Data Plot		Occupied Bandwidth	
Page 1 of 1		Complete <u>X</u>	
Job No.: 1L0456R	Date: 8/30/01	Preliminary _____	
Specification: Part 24	Temperature(°C): 22		
Tested By: David Light	Relative Humidity(%) 50		
E.U.T.: PCS PCMCIA Modem			
Configuration: Installed in Laptop per typical configuration			
Sample Number: 9			
Location: Lab 1	RBW: Refer to plots	Measurement	
Detector Type: Peak	VBW: Refer to plots	Distance: <u>N/A</u> m	
Test Equipment Used			
Antenna: _____	Directional Coupler: _____		
Pre-Amp: _____	Cable #1: 1045		
Filter: _____	Cable #2: _____		
Receiver: 1036	Cable #3: _____		
Attenuator #1: 1473	Cable #4: _____		
Attenuator #2: _____	Mixer: _____		
Additional equipment used: _____			
Measurement Uncertainty: +/-1.7 dB			
Ref Lvl 34.2 dBm RBW 30 kHz VBW 30 kHz SWT 7 ms RF Att 20 dB Mixer -10 dBm Unit dBm 24.2 dB Offset 99% BW=1.23 MHz 1 VIEW 5950CBW 1MA Center 1.88 GHz 246 kHz Span 2.46 MHz Date: 30.AUG.2001 10:08:46			
Notes: Channel 600			