

4


3

2

1

B

B



- Notes:
- 1. 915MHZ
 - 2. Matched to 50 Ohms
 - 3. PCB thickness: .032"
 - 4. Etched on top surface only

Ground Plane

A

A

PROPRIETARY AND CONFIDENTIAL
THE INFORMATION CONTAINED IN THIS DRAWING IS THE SOLE PROPERTY OF PICA PRODUCT DEVELOPMENT. ANY REPRODUCTION IN PART OR AS A WHOLE WITHOUT THE WRITTEN PERMISSION OF PICA PRODUCT DEVELOPMENT IS PROHIBITED.

		UNLESS OTHERWISE SPECIFIED:		NAME	DATE	PICA Product Development		
		DIMENSIONS ARE IN INCHES	DRAWN	S.S.	7/14/25	TITLE: Etched Antenna Versa Sensor		
		TOLERANCES:	CHECKED					
		FRACTIONAL ±	ENG APPR.					
		ANGULAR: MACH ± BEND ±	MFG APPR.					
		TWO PLACE DECIMAL ± .01						
		THREE PLACE DECIMAL ± .005						
		INTERPRET GEOMETRIC TOLERANCING PER:	Q.A.					
		MATERIAL	COMMENTS:					
		Black Silicone Rubber XHG 151 - Shore 70	Rev A - 7/14/25 - New			SIZE	DWG. NO.	REV
		FINISH				B	VERSAANT	A
NEXT ASSY	USED ON	Gloss						
APPLICATION		DO NOT SCALE DRAWING				SCALE: 3:1	WEIGHT:	SHEET 1 OF 1

4


3

2

1

Alfred Starnes

5/1/2025



Skylhawk Versa Sensor
90-240118 Rev E

Antenna Gain:0dBi

SWR = ~1.79

Start: 15.82-46.18j

~~1st: 3.9nH Series X~~

~~7.5nH Series X~~

End: 49.25-28.79j

15nH series